

THE SOIL

Terminal.




22102044649

Med
K3007



Photograph showing transition from Rock into Subsoil and Soil by Weathering
(Hythe Beds, Great Chart, Kent).





Professor J. Percival

With A. D. Hall's Compliments

THE SOIL



THE SOIL

AN INTRODUCTION TO THE
SCIENTIFIC STUDY OF THE
GROWTH OF CROPS

BY A. D. HALL, M.A. (Oxon.)

DIRECTOR OF THE ROTHAMSTED STATION
(LAWES AGRICULTURAL TRUST)

FORMERLY PRINCIPAL OF THE SOUTH-EASTERN AGRICULTURAL COLLEGE

LONDON

JOHN MURRAY, ALBEMARLE STREET

1903

8827

11.144 397

WELLCOME INSTITUTE LIBRARY	
Coll.	welMOMec
Call	
No.	54

INTRODUCTION

THE study of the soil, which is fundamental in any application of science to that part of agriculture which deals with the growth of crops, has received greatly increased attention during the past few years. The crude chemical point of view, which in the main regarded the soil as a nutritive medium for the plant, has been altogether extended, by a consideration of the soil as the seat of a number of physical processes affecting the supply of heat and of air and water to the plant, and again as a complex laboratory, peopled by many types of lower organisms, whose function is in some cases indispensable, in others noxious, to the higher plants with which the farmer is concerned. These three kinds of reaction—chemical, physical, and biological—interact upon one another and upon the crop in many ways; they are affected by, and serve to explain, the various tillage operations which have been learnt by the accumulated experience of the farming community, and the hope for future progress lies in the further adaptation for practical ends of these processes at work in the soil. But it must not be supposed that science is yet in a position to reform the procedure of farming, or even to effect an immediate increase in the

productivity of the land: agriculture is the oldest and most widespread art the world has known, the application of scientific method to it is very much an affair of the day before yesterday. Nor can we see our way to any radical acceleration of the turnover of agricultural operations that shall be economical; the seasons and the vital processes of the living organism are stubborn facts, unshapable as yet by man with all his novel powers. But even if the best farming practice is still a step beyond its complete explanation by science, yet the most practical man will find his perception stimulated and his power of dealing with an emergency quickened by an appreciation of the reasons underlying the tradition in which he has been trained; and such an introduction to the knowledge of the soil it is the aim of this little book to supply. The book is primarily intended for the students of our agricultural colleges and schools, and for the farmer who wishes to know something about the materials he is handling day by day. While a certain knowledge of chemistry is assumed, it is hoped that the subject is so treated as to be intelligible to the non-technical reader who is without this preliminary grounding. Though the book is in no sense an exhaustive treatise, it has been my desire to give the reader an outline of all the recent investigations which have opened up so many soil problems and thrown new light on difficulties that are experienced in practice. The scope of the book precludes the giving of references and authorities for all the statements which are made; but, for the sake of the more advanced student, a bibliography has been appended, which will take him to the original sources, and give him the means of learning both sides of the more controversial questions.

The same reason—want of space—has prevented me

from giving an adequate justification of some of the points of view indicated. Any worker in so novel and unsurveyed a field as the study of the soil still presents, must arrive at certain personal conclusions, and I have tried to steer a middle course between an over insistence on these points on the one hand, and the colourlessness that would come from their entire exclusion on the other. No great part of a text-book can pretend to be original, but in the sections dealing with the chemical analysis and the physics of the soil, I have incorporated a good many unpublished measurements and observations; for the mass of the results on which the book is based, I am chiefly indebted to the work of Lawes and Gilbert, as set out in the Rothamsted Memoirs, and to the writings of Warington in this country, of King, Hilgard, and Whitney in America, of Wollny in Munich.

I have to thank Professor J. Percival, of the South-Eastern Agricultural College, for notes respecting the association of plants with specific soils and many suggestions on biological questions; Major Hanbury Brown, C.M.G., head of the Egyptian Irrigation Department, for information concerning "salted" lands in Egypt; Mr F. J. Plymen, who has been associated with me in carrying out a soil survey of the counties of Kent and Surrey, and has executed many of the observations recorded here; Mr W. H. Aston, one of my pupils, to whom I owe the observations on pp. 124 and 125; and finally, Dr J. A. Voelcker, to whom I am greatly indebted for reading the proof-sheets, and making many valuable suggestions thereon.

A. D. HALL.

THE ROTHAMSTED EXPERIMENTAL STATION,
December 1902.



CONTENTS

INTRODUCTORY

	PAGE
In the Scientific Study of Soils, Chemical, Physical, and Biological Considerations are involved	I

CHAPTER I

THE ORIGIN OF SOILS

Sedentary Soils, and Soils of Transport—Weathering—The Composition of Rock-forming Minerals and their Weathered Products—Distinction between Soil and Subsoil—General Classification of Soils	6
---	---

CHAPTER II

THE MECHANICAL ANALYSIS OF SOILS

Nature of Soil Constituents: Sand, Clay, Chalk, and Humus—Methods of Sampling Soils—Methods for the Mechanical Analysis of a Soil—Interpretation of Results	32
---	----

CHAPTER III

THE TEXTURE OF THE SOIL

Meaning of Texture and Conditions by which it is affected—Pore Space and Density of Soils—Capacity of the Soil for Water—Surface Tension and Capillarity—Percolation and Drainage—Hygroscopic Moisture	57
--	----

CHAPTER IV

TILLAGE AND THE MOVEMENTS OF SOIL WATER

Water required for the Growth of Crops—The Effect of Drainage—Effects of Autumn and Spring Cultivation, Hoeing and Mulching, Rolling, upon the Water Content of the Soil—The Drying Effect of Crops—Bare Fallows	84
--	----

CHAPTER V

THE TEMPERATURE OF THE SOIL

Causes affecting the Temperature of the Soil—Variation of Temperature with Depth, Season, etc.—Temperatures required for Growth—Radiation—Effect of Colour—Specific Heat of Soils—Heat required for Evaporation—Effect of Situation and Exposure—Early and Late Soils	111
---	-----

CHAPTER VI

THE CHEMICAL ANALYSIS OF SOILS

Necessary Conventions as to the Material to be Analysed—Methods Adopted—Interpretation of Results—Distinction between Dormant and Available Plant Food—Analysis of the Soil by the Plant—Determination of "Available" Phosphoric Acid and Potash by the Use of Weak Acid Solvents	128
---	-----

CHAPTER VII

THE LIVING ORGANISMS OF THE SOIL

Decay and Humification of Organic Matter in the Soil—Alinit—The Fixation of Free Nitrogen by Bacteria living in Symbiosis with Higher Plants—Nitragin—Fixation of Nitrogen by the Soil—Nitrification—Denitrification—Iron Bacteria—Fungi of Importance in the Soil: Mycorrhiza, and the Slime Fungus of "Finger-and-Toe"	154
--	-----

CONTENTS

xiii

PAGE

CHAPTER VIII

THE POWER OF THE SOIL TO ABSORB SALTS

Retention of Manures by the Soil—The Absorption of Ammonia and its Salts; of Potash; of Phosphoric Acid—Chemical and Physical Agencies at Work—The Non-Retention of Nitrates—The Composition of Drainage Waters—Loss of Nitrates by the Land—Time of Application of Manures	189
---	-----

CHAPTER IX

CAUSES OF FERTILITY AND STERILITY OF SOILS

Meaning of Fertility and Condition—Causes of Sterility: Drought, Waterlogging, Presence of Injurious Salts—Alkali Soils and Irrigation Water—The Amelioration of Soils by Liming, Marling, Claying, Paring, and Burning—The Reclamation of Peat Bogs	212
--	-----


CHAPTER X

SOIL TYPES

Classification of Soils according to their Physical or Chemical Nature—Geological Origin the Basis of Classification—Vegetation Characteristic of Various Soil Types: Physical Structure, Chemical Composition, Natural Flora and Weeds characteristic of Sands, Loams, Calcareous Soils, Clays, Peat, Marsh, and Salt Soils—Soil Surveys, their Execution and Application	246
--	-----

APPENDICES

APPENDIX I.—Chemical Analyses of Typical Soils	274, 275
" II.—Bibliography	277
INDEX	281



LIST OF ILLUSTRATIONS

FIGURES	PAGE
Photograph showing transition from Rock into Subsoil and Soil by Weathering (Hythe Beds, Great Chart, Kent)	47
<i>Frontispiece</i>	
1. Photograph of Soil-sampling Tools	47
2. Diagram illustrating Pore Space	59
3. Diagram illustrating Capillary Rise and Depression of Liquids	69
4. Photograph illustrating Liquid Film round Soil Particles	70
5. Diagram illustrating Liquid Film round Soil Particles .	72
6. Water Content of Columns of wetted but thoroughly drained Sand and Soil	73
7. Diagram showing Rainfall and Percolation at Rothamsted, Monthly Means, 1870-90	75
8. Soil Temperatures at 9 A.M., Monthly Means, 1896	112
9. Soil Temperatures at 9 A.M., Daily Readings	114
10. Soil Temperatures at 6 in. depth, as affected by the state of the surface	118
11. Temperatures of Drained and Undrained Bog	122
12. Distribution of the Sun's Rays on Southerly and Northerly Slopes	123
13. Temperatures (Max. and Min.) at Various Altitudes	125
14. Nitrates in Cultivated and Uncultivated Soil	175
15. Losses of Nitrogen in Drainage from Rothamsted Wheat Plots	205
16. Nature and Distribution of Alkali Salts	225



THE SOIL

INTRODUCTORY

In the Scientific Study of Soils, Chemical, Physical, and
Biological Considerations are involved.

THE whole business of agriculture is founded upon the soil; for the soil the farmer pays rent, and upon his skill in making use of its inherent capacities depends the return he gets for his crops. Taking rent as a rough measure of the productive value of land, it is clear that enormous differences must exist in the nature of the soil, for in the same district some land may be rented at £2, and other land at as little as 5s., per acre. Of course rent is not wholly determined by the nature of the soil, but depends also on the proximity of a market, and the adaptability of the land to special purposes; a light sandy or gravelly soil, almost worthless for general agricultural purposes, may be valuable in the neighbourhood of a large town, because its earliness and responsiveness to manure make it specially suitable for market gardening.

In some cases the difference between soils is seen in the quality of the crop produced rather than in the productiveness; for example, the "red lands" of Forfarshire are famous for the high quality of the potatoes grown upon them: such potatoes will sell at 80s. to 90s.

per ton, when potatoes grown upon the Lincoln warp soils are at 60s., and those from the black soils of the fen country are only fetching 45s. to 50s. This extra price for the red land potatoes is due to the fact that they can be cooked a second time, after cooling, without changing colour, whereas the ordinary potato is apt to blacken a little when once cooked and allowed to grow cold.

The scientific study of soils is concerned with the differences indicated above; its endeavour is to obtain such a knowledge of the constitution of the soil and the part it plays in the nutrition of the plant, as will make clear the cause of the inferiority of any given piece of land, and ultimately enable the farmer to correct it. The problems involved are far more complex than they appear; at first sight nothing would seem easier than to make a chemical analysis of the soil and find out in what respects it differs from another soil of known value; then the deficiencies or the excesses, as compared with the good soil, could be corrected by suitable manuring. The matter is not, however, quite so simple, for if on the one hand the soil can be considered as a great reservoir of plant food which can be recovered in crops, on the other hand it is equally correct to regard the soil as a manufactory, a medium for transforming raw material in the shape of manure into the finished article—the crop. In new countries where virgin soil is being exploited, and in districts where the systems of agriculture are primitive, the former point of view is the correct one; nothing is given to the soil beyond that amount of labour which will enable some of its inherent value to be realised in a crop. Little by little the capital, which may be practically boundless, as in the great wheat lands of Manitoba, or initially little enough, as on a Connemara heath, is being drawn

upon and not replaced. But in a Kentish hop-garden or other land where an intensive system of cultivation is practised, the crop does not remove as much as it receives, often the land is intrinsically poor, and owes its value to the manner in which it will elaborate the raw material supplied as manure. And not only are these very special soils gaining, rather than losing fertility with each crop, but, from a general point of view, all countries that are being highly farmed, like parts of Great Britain, are steadily increasing in fertility at the expense of other countries which are growing crops on virgin soil; in the linseed, the maize, the cotton seed, that are fed to our stock, there travels to our soil some of the wealth of the lands upon which these crops were grown. Hence the study of the inherent resources of the soil is perhaps less important than an examination of the manner in which the soil deals with such materials supplied under cultivation.

The complete knowledge of the soil and the part it plays in the nutrition of the plant requires investigation along three lines, which may be roughly classed as—chemical, physical or mechanical, and biological; naturally these points of view are not independent of one another, but are only so separated for convenience of study.

In the first place, we know that the plant derives certain substances necessary to its development from the soil: nitrogen and all the ash constituents reach the plant in this manner. We have, therefore, to investigate the proportions in which these constituents are present in the soil, the state of combination in which they may respectively exist, and the variations in these factors normally exhibited by typical soils, all of which questions may be described under the head of chemical analysis. Further investigations of a

chemical nature deal with the power of various soils to retain manure, the causes of sterility or fertility, and the measures that can be adopted for the amelioration of soils.

The soil is, however, not merely a storehouse of food for the plant, since water is equally indispensable to its existence, and is immediately derived from the soil; hence it is of prime importance to study the causes which underlie the movement of water in the land, and its supply to the growing crop. In the relation between soil and water the cultivation to which the land is subjected plays a prime part, hence it will be necessary to trace the effect of each of the main operations of tillage upon the structure of the soil. Again, the texture of the soil and the proportions of water and air it retains, affect its temperature and that responsiveness to change of season which we roughly indicate by the terms "early" and "late" soils. The general consideration of these questions may be termed soil physics.

Finally, the soil is not a dead mass, receiving on the one hand manure, which it yields again to the crop by purely mechanical or chemical processes; it is rather a busy and complex laboratory where a multitude of minute organisms are always at work. By the action of some of these organisms, vegetable residues and manures are reduced, we might almost say digested, to a condition in which they will serve as food for plants; others strike up a joint existence with the higher plants, and aid directly in their nutrition; others again are noxious or destructive to the food stores in the soil.

The work of these organisms is much affected by cultivation—in fact, it would not be too much to say that most of the operations upon the farm have received

a new light from the knowledge that has been acquired in the last few years of the living processes taking place in the soil. In this direction also new developments of agriculture seem to be possible, and though the progress is only small as yet, we see indications that the productive capacity of the land may be permanently increased by the introduction of certain organisms capable of assisting the work of the higher plants.

On the biological side we have also to study the association of certain plants with particular soils; an examination of the natural flora of any district will show that some species are almost confined to sandy soils, others to soils containing chalk, rarely wandering on to different types of soil; again, particular weeds are characteristic of clay land, others of sand; and some even of our cultivated crops show a marked intolerance for particular soils.

The full story of the soil cannot yet be told; small wonder that in the course of the many centuries man has been cultivating the face of the earth, he has found out much which science can barely explain, still less improve upon. Nor are the problems simple—the food, the water, the temperature, the living organisms in the soil are all variables, affected by cultivation and climate, themselves also variable; they all act and react upon one another and upon the crops; hence we can easily understand that the smallest farm may present problems beyond the furthest stretch of our knowledge.

CHAPTER I

THE ORIGIN OF SOILS

Sedentary Soils, and Soils of Transport—Weathering—The Composition of Rock-forming Minerals and their Weathered Products—Distinction between Soil and Subsoil—General Classification of Soils.

THE study of soils must begin with some knowledge of their origin and their relationship to the rocks that underlie them, out of which, in most cases, they have been formed.

Perhaps the best way of arriving at an idea of the natural processes which result in soil, is to visit a river valley and examine, first a quarry on the flanks of the hills, and then one of the cuttings for gravel or brick-earth, which often lie a little above the river level.

The face of the quarry shows at a depth of 10 feet or so from the surface the massive rock, unaltered as yet by any action of the weather. Closer examination, however, shows that even at this depth the rock is not quite solid; if it be a stratified rock the planes of bedding are apparent, along which the rock can be split. Joints again traverse the rock at right angles to the bedding planes, and along both joints and bedding planes it is evident that water makes its way, for the edges of the cracks are slightly altered and discoloured. Nearer the surface, the cracks and lines of

weakness in the rock become more palpable; in some cases the joints have been forced open by the intrusion of the roots of trees; minor cracks have started from the main ones, and the disintegration of the rock at the edges of the cracks has proceeded further, till at a distance of 3 or 4 feet from the surface the whole material is loose and shattery, though still preserving the appearance of solid rock. Still nearer the surface, the rock structure seems to have disappeared; rock may be there in lumps and fragments, but is embedded in small material that may fairly be termed soil or earth. Still nearer the surface the rock fragments become smaller, and the proportion of fine earth larger, till in the top 9 inches or so a new change begins. Here the stones are generally small, and the material is dark from the admixture of decaying vegetable matter, residues of the crops that have covered the surface for long ages. This is the *soil* proper, generally shading gradually into the *subsoil* below, which in its turn passes insensibly into the underlying rock. It is obvious that a soil such as we have been describing has been directly formed from the rock—it is, in fact, the rock disintegrated and reduced by frost and snow, air and rain; all those agencies we group together under the name of “weathering.” We are dealing with a soil formed *in situ*, or, as it is sometimes termed, a *sedentary* soil.

The frontispiece shows a photograph of such a case of weathering of rock into subsoil and soil, as seen in a section of the Hythe Beds, near Great Chart, Kent.

But when we examine the section of the gravel pit or the brick earth workings lower down in the valley, the sequence is not the same; we still have the soil proper passing into the subsoil, but this is fairly even throughout instead of showing a progressive change

as we descend ; if it be gravel, the stones continue of the same size ; if brick earth, neither stones nor hard stratified clay make their appearance. Should the exposed section be deep enough, we find at last the subsoil suddenly giving place to entirely different material—solid chalk, or massive clay, or sandstone, as the case may be—perhaps incapable, when disintegrated, of furnishing the stuff of which the upper stratum of gravel or brick earth is composed. In this upper stratum we see the clearest evidence of the action of water ; the brick earth is free from stones and is of even texture, the gravel contains hardly any fine material, and its constituent stones are worn and partly rounded ; only running water can sift the heterogeneous results of the weathering of rocks, and grade them into different deposits. From what can be seen of the present work of the river, it is clear that the brick earth was deposited where the water was moving very slowly, in quiet bays and in cut-offs, which only from time to time get filled up with muddy flood water ; the gravel must have been laid down in the strongest wash of the currents.

Soils and subsoils of this type, which bear no particular relation to the underlying rocks, but have travelled from a distance by means of running water or some kindred agency, are known as *soils of transport*, or, to use the terminology of the Geological Survey, as *drift* soils.

Weathering.

The study of geology teaches us that nearly all the rocks termed stratified or sedimentary, which cover the greater part of the surface of the British Islands, have been formed from the waste of previous rocks by weathering, and by the subsequent re-deposit and con-

solidation of the weathered material. A grain of sand, for example, is practically indestructible; it may have become cemented to the other grains on the sea beach where it was lying, and give rise to the rock we term sandstone; the rock thus formed may have been elevated into dry land, broken up into loose grains, and washed down to the sea to form a new beach, over and over again in the world's history; so long a time has elapsed since water first began to work on the earliest rocks. For this reason, if we want to trace out the origin of a soil in detail, we must in most cases go beyond the sedimentary rock from which it immediately derives, back to the so-called primitive or crystalline rocks, which represent in a sense the original materials of the earth's crust.

Here we shall find certain fundamental minerals, which in a weathered state, altered both mechanically and chemically, go to form both the sedimentary rocks and the soil which is our immediate study. Though the number of distinct minerals is immense, practically the mass of the earth's crust is made up of a few only; silica, various complex silicates of alumina, iron, lime, magnesia, potash and soda, together with carbonate of lime, which is generally of organic origin, are all that need be considered in regard to soils.

The various agencies which reduce rocks to soil, grouped under the general term of weathering, may be distinguished as mechanical—including the work of alternations of temperature, frost, wind, rain and glacial ice—and chemical, the complex effects of solution and oxidation that are brought about by water, especially when charged with carbonic acid.

In dry climates the alternations of temperature between day and night set up sufficient strain to fracture even large rocks, and eventually reduce them to dust. The dust and sand of the deserts of Central Asia, the

barren lands of the United States, and many parts of both North and South Africa, are formed in this way; through the dryness of the atmosphere radiation is extreme, and the temperature of the rock surface will rise to 60°C . in the day and fall below zero at night. Crystalline rocks soon disintegrate under such alternations of temperature, and the fine angular dust thus formed is transported by wind into the plains and valleys, giving rise to soils largely wind-borne. Richthoven has supposed that the immense *loess* deposits of China are in the main dust that has been blown from the Central Asian deserts. Even in a humid country like our own the wind plays a considerable part in forming soil, material being constantly removed from any bare surface and deposited elsewhere as dust. When all the country was in its natural state and clothed with vegetation, the amount of transport as dust must have been considerably smaller than at present, but even then worm casts brought up in the spring would crumble in dry weather, and be moved to lower levels by the wind. The thickness of the dust deposit may be gauged by the rapidity with which shingle beds newly won from the sea become covered with vegetation; in the neighbourhood of Dungeness shingle beds known to be less than fifty years old are already clothed with a scanty flora. On scraping away a few inches of the shingle the interstices between the stones are found to be filled with a fine black sand, which can only have been wind-borne; this rapidly increases as the first vegetation checks the velocity of the wind above the stones and arrests the dust, till at last it reaches the surface and the grass begins to spread over the stones. Exact dates are difficult to obtain, but probably considerably less than a century is sufficient to form a thin turf over a bare shingle bed.

But the great weathering agency in temperate climates is undoubtedly frost acting upon water contained within the rocks and stones; the water expands as it changes into ice, and exerts an enormous pressure—indeed about 100 atmospheres would be required to keep water in a liquid condition at -1°C . All rocks when freshly exposed, hold, by capillary attraction, a certain amount of water known as the “quarry water,” which amounts in the white chalk to as much as 19 per cent. A piece of such chalk will be shattered into fragments by a single night’s frost. Even after the quarry water has been dried out the most close-grained rocks will absorb a small quantity of water. The face of polished granite rapidly deteriorates in severe climates owing to the freezing of the water that finds its way into the minute divisions between the crystals: Cleopatra’s Needle, which had retained its smooth face for centuries in Egypt, soon became affected after its removal to London, and has to be protected by a waterproof varnish, as have all the granite monuments in Canada.

In nature also, all rocks are traversed by joints and bedding planes; these cracks are filled with water and opened and extended by its conversion into ice in the winter, till finally a block is wedged off and a fresh surface exposed to the action. Where flagstones are quarried, the workmen are in the habit of saturating the surface of the rock with water before the winter sets in: thus the rock is split along its bedding planes more effectively than by any artificial means. The fragments that have been broken off the main rock will be continually reduced in size by successive frosts, until they reach the ultimate fragments which are no longer penetrated by water; even in a soil the disintegration is still proceeding.

The weathering agencies just described would gradu-

ally cover any exposed rock with a layer of debris, which would protect the lower layers from further action, were it not that the rain is always washing the finer particles into the valleys and so leaving the rock open to fresh attack. Even on grass land the fine mould brought to the surface by worms, moles, ants, etc., is constantly travelling downhill by the agency of rain. On arable land containing stones it is a common expression to say that the stones "grow": however thoroughly the surface may be picked clean of stones, in a year or two they will seem as numerous as ever; the fine soil gets washed away to lower levels, leaving the stones standing upon the surface. Even the stones themselves gradually creep downhill, the rain undermines them till they fall over, they must fall a little lower down the slope till they eventually reach the valley and are subject to further transport by running water. At the bottom of many of the smaller dry valleys on the chalk rests an enormous accumulation of flints of all sizes; in one case in a small upland valley the deposit was 6 or 7 feet thick, the unworn flints were so close as to be practically in contact, only the interstices being occupied by soil; yet the surface carried good crops.

The material which thus creeps down the sides of the valleys is further sorted out by the streams and rivers and deposited as beds of gravel, sand or clay, the "alluvium" which underlies the level river meadows. The coarser the material the more readily will it settle, the finer particles are only deposited when the velocity of the stream has been almost entirely checked. The gravel and sand are deposited in and about the stream course itself, the finer material falls on the meadows in flood time, so that their level is gradually raised from year to year. Wherever the meadows get water-logged the surface vegetation will begin to accumulate as

peat; the stream also wanders about from side to side of the valley, hence borings through any extensive deposit of alluvium will disclose alternating beds of gravel, sand, brick earth, and peat, of variable extent and thickness. The great alluvial flats or marshes at the mouths of many of our rivers are formed in this manner; the deposit takes place in the sea or in the estuary, until the tides and currents work the material up to high-water mark, after which only fresh-water beds are laid down.

Although most of the materials of which rocks are composed are in the ordinary sense insoluble in water, few of them, except the pure sand grains, can resist the attack of water charged with carbonic acid. The rain water when it reaches the ground has little carbonic acid in solution, but the gases in the soil contain a considerable quantity derived from the decay of vegetable matter in the surface layer, and the water in contact with these gases will dissolve a proportionate amount. The proportion of carbonic acid in the soil gases varies very much both with the permeability of the soil and the proportion of humus, but at a depth of 1.5 metres Wollny found it vary from 3.84 per cent. to 14.6 per cent. at various periods of the year. At greater depths the amount is still higher, so that the percolating water becomes a weak solution of carbonic acid, and attains a considerable solvent power. Not only are the alkaline silicates attacked by the weak acid thus formed, but as lime, magnesia, and iron protoxide also form soluble bicarbonates, all minerals containing these bases are liable to attack. Probably some of the organic acids produced by the decay of vegetable matter in the surface soil aid in the solvent power of soil water; yet, undoubtedly, water containing carbonic acid is the great natural solvent, and some of the more striking cases of

its action in breaking down rocks will be discussed later under the heads of felspar, augite, and calcium carbonate.

The attack of frost and water upon rocks is much assisted by the roots of plants and trees; if we examine a fresh section of the soil over a quarry or brick pit, the roots of ordinary field plants can be traced downwards for 4 feet or more, while the roots of a tree may be seen working far into tiny fissures of the almost unaltered rock. The roots follow the water in the fissures: at first they can enter very minute cracks; as they grow, the pressure they exert widens the cracks; finally, the roots decay and leave a channel down which water can percolate freely. The fine roots themselves have a certain solvent action; after plants had been grown in a pot filled with powdered granite rock, which had been freed from all fine particles by washing, an appreciable quantity of mud and clay was found.

The opening up of the subsoil to weathering by the action of roots is also carried out by worms, which have been observed making their burrows to the depth of 5 feet, thus introducing both air and water into the lower strata. But the great work of worms in regard to soil lies rather in the production of the fine surface layer of mould rich in vegetable matter: Darwin calculated that on an ordinary chalky pasture the whole of the fine surface soil to a depth of 10 inches was passed through worms and cast up on the surface in the course of fifty years. During their passage through the gizzard of the worms the stony particles will receive a certain amount of rubbing and be reduced in size, so that some of the finer particles in the soil owe their origin to worms. The deposit of the fine soil on the surface in the shape of worm casts, which are afterwards spread by the action of rain and wind, explains why chalk, ashes, or even stones placed on pasture land gradually sink below the

surface. Darwin found in one case that a layer of burnt marl spread on the surface had sunk 3 inches in fifteen years, in another case a layer of chalk was buried 7 inches after an interval of twenty-nine years; in neither case, however, can we estimate the part played by the accretion of dust in forming this deposit. When we consider for how long a period worms must have been working in our cultivated soils, it is clear that the whole must have been through them over and over again, and that much of the fineness of the surface soil must be due to their action, both in actually grinding the fragments and in constantly bringing the finest portions back to the top.

In addition to the alluvial deposits proper, which are still in process of formation, beds of gravel, sand, and brick earth occur in many river valleys, as terraces on the flanks of the hills, often much cut and denuded by the modern river. These high level formations probably represent alluvial deposits of a former epoch where the general slope of the land was greater and the rivers, fed by a higher rainfall in the hills, ran in greater volume. That the material of which these deposits consist has been sorted by running water is evident from the uniformity of size it possesses in each bed: while the coarseness of the gravel, and the fact that in some cases the stones are not made from the immediately underlying rock, all point to a great lapse of time and a river of higher transporting power than the present one. The wide deposits of brick earth in the neighbourhood of London and in East Kent were probably laid down either by floods on the river meadows or in quiet bays and lagoons of an estuary.

Over a great part of Britain north of the Thames, especially in the midlands and the eastern counties, the surface of the land is covered with beds of clay and sand which owe their origin to glacial ice. In

Scotland, the north of England and Wales, these beds are full of ice-scratched stones, and clearly represent material that has been ground down by a moving glacier: but the origin of the glacial drift of the eastern counties is more obscure, for water seems to have played some part in its formation. The beds are mostly stiff and clayey in character, and by their included fragments show from what formation, as a rule not very remote, they have been derived.

Rock-forming Minerals.

In the solid crust of the earth D'Orbigny has estimated that the chief minerals are present in the following proportions—felspars, 48 per cent.; quartz, 35 per cent.; micas, 8 per cent.; talc, 5 per cent.; carbonates of lime and magnesia, 1 per cent.; hornblende, augite, etc., 1 per cent.; other minerals and weathered products, 2 per cent.

The following table shows the composition of these chief minerals, with a few others that play some part in the formation of soil:—

	Silica.	Potash.	Soda.	Magnesia.	Lime.	Alumina.	Ferrous Oxide.	Ferric Oxide.	Water.
Quartz	100
Felspar { Orthoclase	64.2	17	18.4
{ Albite	68.6	...	11.8	19.6
{ Anorthite	43.1	20	36.9
Mica {	45	6	0	26	1
{	10	10	10	10	10
{	50	10	1.5	36	4.7
{ Hornblende	39	10	10	3	3
{ Augite	10	10	10	10	10
{	49	27	15	15	20
Olivine	41	49.2	9.8
Talc	63.5	31.7	4.8

Quartz, the crystalline form of silica, is found massive and in veins in the primitive rocks, and in fragments of all sizes in the granites, gneisses, and similar rocks. From the waste of these crystalline rocks are derived the sandstones of all geological ages, and directly or indirectly the sands now existing. In a sandstone rock the grains of quartz are bound together by a cement, which may be oxide or carbonate of iron, as in the Lower Greensand of Surrey and Beds, and in some of the Wealden sandstones, or carbonate of lime, as in the Kentish Rag, or even silica itself, as in the hard blocks of tertiary sandstone, which are left as "grey wethers" on the surface of the chalk. In some of the older sandstones the rock is practically homogeneous; heat, pressure, and solution having thoroughly felted the grains together. Many sandstones weather rapidly, through the solution of the cement binding the grains together; the resulting sand has the same texture as it possessed before it was cemented into a rock.

The grains of sand that are first weathered from a crystalline rock possess an angular shape, but are soon rubbed down in running water into rounded grains with a surface like fine ground glass. Hence the degree of angularity which the sand grains show gives some indication of the amount of wear and tear they have suffered since their origin as sand. Below a certain size, however, quartz grains seem no longer capable of rubbing against one another, but remain angular even after long travel in running water. Daubrée has shown that angular fragments of sand of less than 0.1 mm. in diameter will travel in water without becoming rounded, hence any rounding of smaller grains of sand must have been due to solution.

Silica in the crystalline state is very slightly soluble

in water, a certain amount of solution taking place even at ordinary temperatures: most natural waters show a little silica in solution, though this more probably arises from the decomposition of natural silicates by water containing carbonic acid, rather than from the direct solution of quartz.

Amorphous silica in the form of "flint" plays a conspicuous part in the constitution of many soils in the south and east of England; owing to their durability and the former greater extension of the chalk, they are found in many districts remote from the chalk, even in the drift beds of the Channel Islands. When first won from the chalk, flints possess a clear black translucent structure, and are easily fractured and crushed; when weathered, either in flint gravels or on the surface of the soil, they become yellow or brown in colour, more opaque, and much harder, so that weathered flints are always preferred for road-making. The surface also becomes covered with a white incrustation, extending to a depth of $\frac{1}{16}$ of an inch or more; this is, however, only incipient weathering, probably due to the freezing of the small amount of water that soaks in at the surface.

The Felspars constitute the most important group of minerals found in the crystalline rocks: they are double silicates of alumina and some other base, potash, soda, or lime, of the general formula $R_2O, Al_2O_3, 6SiO_2$, where R_2O may be either K_2O , Na_2O , or CaO . In granites and gneisses the common felspar is orthoclase or potash felspar; in the volcanic rocks plagioclase felspars predominate, in which the base is lime, generally with some admixture of soda and potash.

The felspars are all distinguished by the ease with which they are attacked by water containing carbonic acid, those containing lime more readily so than the

potash felspar. The lime or the alkali is removed in solution, some of the silica is also removed ; the alumina remains as a hydrated silicate, $\text{Al}_2\text{O}_3, 2\text{SiO}_2, 2\text{H}_2\text{O}$, called kaolinite. Owing to this disintegration of felspar, the crystalline rocks in which felspar is present weather rapidly, the other materials, quartz, mica, hornblende, become loosened from the matrix, and the whole rock becomes rotten. The granite of Cornwall and Devon is generally covered to a considerable depth, as much as 100 feet in some cases, with a layer of kaolinite, in which the unchanged quartz and mica are embedded ; the kaolinite, freed by washing from the quartz, mica, etc., forms the "china clay," or kaolin of commerce. In the same way the basalts and other kindred rocks give rise to a red clay, consisting of kaolinite with the red iron oxides which result from the oxidation of the magnetite and the hornblende, augite, etc., containing ferrous silicates. From the decomposition of the felspars, augite, hornblende, etc., all our clays arise ; as these minerals also generally contain potash, they are the source of the potash required by crops, which is always more abundant as clay predominates in the soil.

Daubrée caused 3 kilos of fragments of felspar to revolve in an iron cylinder with 3 litres of water, so that they practically performed a journey of 460 kilometres, with the result that 2.72 kilos of mud were formed, of which 36 grams were clay, and in the water there were 12.6 grams of potash in solution as silicate.

Senft examined the action of water charged with carbonic acid upon two granites, one (A) composed of orthoclase, quartz, and potash mica, the other of (B) plagioclase, quartz, and magnesia mica, and obtained in solution—

	A.	B.
Potash as Bicarbonate . .	25 to 25 per cent.	5 to 8 per cent.
Soda as Bicarbonate . .	2 " 6 "	8 " 10 "
Lime as Bicarbonate . .	1 " 2 "	4 " 5 "
Magnesia as Bicarbonate .	a trace	10 " 15 "
Silica	a little	a little
Iron as Bicarbonate . .	a trace	a trace

The undissolved residue of A was a white, of B a yellow, clay containing fragments of quartz and flakes of mica.

The following analyses show the change that takes place in passing from orthoclase felspar to kaolin; in the third column the analysis of kaolin is recalculated to show what arises from 100 parts of felspar, on the assumption that none of the alumina is removed by solution:—

	Orthoclase Felspar.	Kaolin.	Kaolin from 100 Felspar.
Silica . . .	64.2	46.8	23.1
Alumina . .	18.4	37.3	18.4
Potash . . .	17	2.5	1.1
Water	13	6.4
	99.6	99.6	49

Mica is essentially a double silicate of alumina and potash, with some oxide of iron: the potash being replaced by magnesia in black mica or biotite. Mica splits up into minute flakes as the rock weathers, but these flakes are fairly resistant to chemical change, and may be detected in most sands and sandstones. Ultimately, however, they pass into hydrated silicates of

alumina, and are rarely to be detected in the soils resting upon sedimentary rocks.

Hornblende and Augite, though differing in crystalline shape, are chemically identical, and consist of silicates of varying proportions of lime, magnesia, alumina, ferrous and ferric oxides; manganese and the alkali metals are generally also present. They constitute, with plagioclase felspar and magnetic oxide of iron, the chief part of the rocks that are sometimes roughly termed "greenstone," basalts, diorites, etc., of both volcanic and plutonic origin. They decompose under the action of carbonic acid charged water, especially those containing much lime, while those with much magnesia are the most resistant; the products of the action are kaolinite, oxides of iron, and carbonates of lime and magnesia. The following analysis (Ebelmar) show the chemical change in the weathered layers of a basalt from Bohemia and a greenstone or dolerite from Cornwall:—

	BASALT.		GREENSTONE.	
	Unaltered.	Weathered.	Unaltered.	Weathered.
Silica	44.4	42.5	51.4	44.5
Potash	4.8	} 2.0	1.6	1.2
Soda	2.7		3.9	1.7
Lime	11.3	2.5	5.7	1.4
Magnesia	9.1	3.3	2.8	2.7
Alumina	12.2	17.9	15.8	22.1
Iron Protoxide	12.1	...	12.9	...
Iron Peroxide	3.5	11.5	3.0	17.6
Titanium Oxide	trace	1.2	0.7	1.0
Water	4.4	20.4	1.7	8.6

The loss amounts to about 44 per cent. in the case of the basalt, and 34 per cent. in that of the greenstone.

Another example may be given of the analysis

(Hanamann) of a basalt from Bohemia, with that of the weathered crust and of the resulting soil:—

	Rock.	Weathered Crust.	Soil.
Silica . . .	41.84	39.7	39.17
Potash . . .	0.82	0.83	0.94
Soda . . .	3.45	2.51	1.03
Lime . . .	11.16	8.02	4.72
Magnesia . .	3.63	3.20	2.92
Alumina . . .	17.51	16.94	16.58
Iron Protoxide .	3.71
Iron Peroxide .	12.77	15.05	14.22
Phosphoric Acid	0.5	0.48	0.48
Carbonic Acid .	0.88	2.67	0.61
Water . . .	3.56	10.5	19.28

Olivine is essentially a silicate of magnesia and protoxide of iron, not uncommon in some basalts, which easily weathers and becomes a soft hydrated silicate, called serpentine, to which *talc* is very similar in composition. These magnesian silicates are not of great importance in the British Islands; only in the Lizard district of Cornwall are they extensively developed and give rise to poor, barren soils.

Calcium Carbonate, though present in many of the older rocks in its crystalline form of Calcite or Iceland Spar, is there to be regarded rather as a secondary product brought by infiltrating water than an original mineral. *It is soluble in water charged with carbonic acid*; hence when the complex silicates containing lime are weathered, the lime is removed in this form. The calcium carbonate is redeposited when the water loses the carbonic acid either by evaporation or by diffusion on contact with air. In a massive form calcium carbonate forms many of the sedimentary formations—the older ones hardened to limestones, and the more recent ones soft like the chalk; in these cases it has been secreted

from natural waters by living organisms, foraminifera, corals, etc., and only gets a crystalline structure by later change. Calcium carbonate from organic sources is present to some extent in nearly all sedimentary rocks; the vast majority of the fossils there found are constituted of Calcite.

In the limestone and chalk rocks the calcium carbonate is never quite pure; in the white chalk, which is the purest, the proportion of calcium carbonate, after excluding the flints, is only about 98 per cent.; in others the proportion of clay and mud which were simultaneously deposited gradually increases, so that we can find rocks of every gradation between chalk and clay or sandstone.

Owing to its solubility, the weathering of limestone takes the form of the removal of calcium carbonate more or less completely, leaving a fine-grained residue of the insoluble clay or sand. In the case of chalk and of the purer limestones, the insoluble residue consists mainly of a fine red or yellow clay; the chalk downs, when not obscured by drift formations, are covered with a sticky, reddish soil, only as a rule a few inches in thickness, and though the actual chalk is so close, in many cases this soil is almost deprived of all its calcium carbonate. Almost exactly similar material may be obtained in the laboratory by dissolving a few pounds of chalk or limestone in dilute hydrochloric acid. Whenever a section is exposed in chalk or limestone rocks, it will be noticed that the dividing line between soil and rock is very irregular; thin as the soil may be as a whole, in places it descends into cavities and "pipes" in the rock, sometimes 20 or 30 feet deep. In these depressions the soil is the same reddish clay as occurs on the surface, mixed with flints in the case of the upper chalk; they are essentially the

results of solution, and represent the lines along which the drainage of the rain water has been more active, owing to a joint or fissure in the rock below.

Other minerals which do not constitute any large proportion of the earth's crust, but still play some part in the soil, are apatite, glauconite, selenite, limonite, and iron pyrites.

Apatite, or crystallised phosphate of lime,— $\text{Ca}_5(\text{PO}_4)_3\text{F}$,—is present in small quantities in many of the fundamental rocks, and is probably the ultimate source of the phosphoric acid of soils. Apatite also occurs massive in some of the older strata, and is worked as a raw material, for the manufacture of phosphatic manures, in Norway and Canada.

Selenite, hydrated sulphate of lime, $\text{CaSO}_4, 2\text{H}_2\text{O}$, termed gypsum when massive, is not a fundamental mineral, but occurs in most clay rocks in well developed crystals. Diffused through the soil and dissolved in soil water, selenite doubtless provides most of the sulphur required by plants.

Limonite, hydrated oxide of iron, occurs in lumps and bands in many of the sedimentary rocks; in a diffused state it is the main colouring matter of soils; in heavy, undrained soils it often forms a layer or "pan" some inches below the surface. It is deposited from water containing bicarbonate of iron on exposure to the air; the rusty deposits and stains from chalybeate springs and wells consist of limonite. The action appears to be as follows—the hydrated peroxides of iron in the soil when in contact with humus (decayed vegetable matter) and water charged with carbonic acid become first reduced to the ferrous state by the organic matter, and then dissolved as bicarbonate. On exposure to the air, the excess of carbonic acid escapes by diffusion, the ferrous carbonate, as it is precipitated, is also oxi-

dised by the oxygen of the air, and deposited as limonite. It will be noticed that stones taken from peaty land are always bleached white, through the removal of iron, and the surface sand of heathy land is always similarly bleached. On examining a section of any purely sandy formation, the surface soil will be found to be bleached below the layer of vegetable matter to the depth of a foot or more. Then comes a layer an inch or two thick nearly black in colour, where the sand is more or less cemented together by limonite, and below this the normal brown or yellow sand begins. The black band is formed at the depth to which the air usually penetrates the soil; it consists of limonite deposited at the evaporating surface of the soil water, which contains the iron dissolved from the bleached surface sand. In a similar manner arises the hard layer of limonite, the "iron pan" or "moor-band pan," found just below the cultivated soil on many undrained lands, and again the deposit of "bog iron ore" which is generally to be seen beneath the black peaty accumulation in any swampy place. The solution of iron as bicarbonate, and its precipitation as limonite, do not occur in soils containing any calcium carbonate, being essentially a sign of an acid condition of the soil and its need for lime or chalk.

Glauconite is a hydrated silicate of iron, alumina, and potash, with a little lime and magnesia, which occurs as dark green grains in many sedimentary rocks, especially of the Cretaceous age. It is to the presence of this material that the Greensand formations owe their name; it is sometimes also to be seen in chalk and in the tertiary sandstones. It readily weathers to brown oxides of iron.

Iron Pyrites, FeS_2 , occurs in small brass yellow cubic crystals in many of the older rocks, especially

those of a clay character; another form, in fibrous masses of a lighter colour, is called marcasite, and is common in the more modern clays, especially the London clay, and again in round balls in the chalk. Marcasite readily oxidises in moist air to ferrous sulphate and sulphuric acid: and many clay soils contain basic sulphates, soluble in dilute acids but not in water, arising in this way. Selenite and the soluble sulphates present in well waters, especially in clay soils, are probably secondary products arising from the oxidation of marcasite. In a finely divided condition iron pyrites forms the colouring matter of many dark green or olive rocks and clays.

Soil and Subsoil.

Although the transition from soil to subsoil is gradual, the distinction between the two is, as a rule, easy to be made; the change begins an inch or so below the usual limit of cultivation on arable soils, on pastures at the depth to which the mass of the roots penetrate. The most obvious difference between the two lies in the comparative richness of the staple in decaying vegetable matter or humus, which indeed would be entirely confined to the surface layers were it not for the decay of the deeper roots and the work of worms. To the humus is also due the difference in colour; not only does the colour deepen towards black as the proportion of humus increases, but by it the sands and clay are to a greater or less extent bleached through the removal of the iron oxides which colour them, hence the inorganic material is lighter and duller in colour in the soil than in the subsoil. In stiff clays the subsoil often shows signs of imperfect oxidation at comparatively slight depths. On an old pasture on the Gault Clay a trench was dug, the top 3 inches were black

or nearly so, and gradually changed to a stiff brown loam which extended to a depth of 9 or 10 inches, becoming lighter and more distinctively yellow as the admixture of humus diminished; below this depth the clay became mottled, grey and yellow mixed, till at a depth of 4 feet practically the whole was a dark blue unweathered clay, owing its colour to iron pyrites and glauconite or kindred silicates of iron protoxide. One of the greatest distinctions between soil and subsoil lies in their respective texture; in humid climates like our own the soil is almost invariably composed of coarser grains than the subsoil, though in arid climates soil and subsoil appear to be almost uniform. This is due to the rain constantly percolating through even the stiffest soils and washing down the finest particles; in heavy rains also, water runs off the surface into the ditches, carrying with it the finest particles of the soil and leaving behind the coarser grains on the surface. Naturally, this loss of the finer particles is greater as the soil is more worked and made open to percolation and washing; to some extent it is counterbalanced by the work of worms bringing the fine mould to the surface from below, so that the difference is least in an old pasture. *Per contra*, it is greatest in an old garden soil, where the constant working and further opening of the soil by the introduction of bulky manure often results in so complete a washing down of all the finer particles that the soil proper loses its power of cohering, falls into dust when dry, and is popularly said to be "worn out."

In addition to its humus the soil is often richer than the subsoil in all the essential elements of plant food, despite the fact that crops have been raised on it for generations; the crops, in fact, have been the cause of the difference, for the deeper roots draw food from

the subsoil and leave it behind on the surface as the plants decay. Potash is perhaps an exception in this connection; being essentially a product of the weathering of felspar, and removable from the soil by water containing carbonic acid, it is often more abundant in the comparatively unweathered subsoil. The richness of the humus, its greater warmth and the freer access of air also cause it to be more abundantly supplied with those organisms which play such an important part in preparing the food of the higher plants: as will be seen later, subsoils become almost without living organisms at a very slight depth.

For all these reasons,—the absence of humus, and of the organisms associated with it, the comparative poverty in inorganic plant food, the presence sometimes of unoxidised material, and on stiff soils the great change of texture,—the subsoil is often comparatively unfertile and may be almost barren. Desirable as it is to work the subsoil and open it to the access of air and the free penetration of roots, all methods of cultivation should be avoided that would bury the surface soil and bring the subsoil to the top. A plough which inverts the soil should not go below the former limit of cultivation, and if it is desired to deepen this limit, it should be done by degrees, half an inch or so each year. Immense damage has been done to the fertility of many of the heavier soils by rash ploughing with steam, especially where the old "lands" were thrown down, burying the fertile soil in the furrows and baring the raw clay on the tops of the ridges.

General Classification of Soils.

Although a distinction has been drawn between sedentary soils and soils of transport, there are few sedentary soils that do not contain material which has

been carried from some other formation at a distance ; only on great stretches of flat country belonging to a single geological formation may be expected a soil purely derived from the rock below. Especially in Britain, where the outcrops of the different formations are generally narrow, and where the surface is always undulating, we find that the continual creeping of soil particles to lower levels has resulted in an admixture of foreign material in most soils. "La couche très-mince de la terre végétale est un monument d'une haute antiquité" (Elie de Beaumont), so that in many places the soil contains the débris of formations now removed by denudation. In the south-east of England the soils that rest on the chalk, which may be only from a few inches to a few feet below, contain abundance of quartz sand, even up to 75 per cent. Little sand exists in the chalk itself, it must have come from the lower tertiary beds which once overspread the chalk. On the wide flats of Weald Clay in the same district, the soil contains sand that has crept from the central hills of the Weald or from the Lower Greensand escarpment, often several miles away. The following analysis of a soil resting on a brick earth bed in the valley of the Kentish Stour, shows that the brick earth, which contains little or no chalk, has become covered with chalky rain-wash from the hills flanking the valley :—

Depth—Inches . . .	0 to 6	6 to 12	12 to 18	18 to 24
Calcium Carbonate %	9.20	7.16	2.6	0.96

In the main, however, the bed below gives its character, both chemical and physical, to the soil ; and the ordinary rough classification of soils into sands, clays, marls, and loams, follows closely the nature of the underlying geological stratum. A coarse-grained

sandstone gives rise to a typically sandy soil, such as the soils derived from the Bagshot beds, which form the New Forest and the heathy land in the Aldershot district; on the Lower Greensand lie the sandy heaths in west Surrey, Hampshire, and in Beds; again, on the Bunter beds of the New Red Sandstone lie many of the uncultivated commons and parks of the Midlands, such as Sutton Park, Cannock Chase, and Delamere Forest. These coarse sandy soils which have so often remained unenclosed as forests and commons are generally deficient in chalk, and accumulate peat wherever a parting of clay gives rise to stagnant water.

Clay soils are common in nearly every part of Britain; they arise from the great clay strata of all ages, like the London Clay, the Weald Clay, and the Oxford Clay, or from metamorphic rocks like slate, or from the crystalline rocks like granite and basalt, or even from the limestones by solution.

Between the sands and the clays come mixtures of all grades, better working than the clays and more fertile than the pure sands; sometimes the clay formation itself contains sand, as in the upper beds of the London Clay, or we may have a fine-grained sandstone mixed with clay, as in some of the carboniferous rocks. In all these cases, when chalk is absent, and drainage incomplete, there will be an accumulation of humus, resulting in a peaty formation.

Some argillaceous limestones give rise to typical "marls," mixtures of chalk and clay; *e.g.*, some of the beds of the Lias and of the Keuper.

Other limestones with a sandy basis, and fine-grained sandstones cemented by carbonate of lime, give rise to "loams," which are free-working soils, mainly composed of fine sand with some clay and a little calcium carbonate. The alluvial soils in the valleys

are loams, passing in places into gravels ; these are generally the richest soils ; as a rule they are mixtures derived from many formations, and so are well supplied with humus and the mineral elements of plant food ; they are deep, and not over consolidated, thus admitting of the percolation of water and the descent of roots ; yet they are fine grained enough to prevent them drying out too rapidly. But though these terms, sands, clays, marls, loams, and peaty soils, serve for rough descriptive purposes, a more exact determination of the constituent particles is necessary to properly characterise a soil, and for this we must resort to what is termed the "mechanical analysis" of a soil.

CHAPTER II

THE MECHANICAL ANALYSIS OF SOILS

Nature of Soil Constituents : Sand, Clay, Chalk, and Humus—
Methods of Sampling Soils—Methods for the Mechanical
Analysis of a Soil—Interpretation of Results.

IT has already been indicated that as soils are derived from the waste of rocks, they consist of a mass of particles of various minerals and of all sizes, together with a certain amount of humus of vegetable origin, and that they may be roughly classified according to the predominance of the coarse-grained particles called "*sand*," or the very fine "*clay*."

The mechanical analysis of a soil consists in pushing this rough "eye and hand" classification a stage further into the region of exact measurement, and in determining the minute physical structure of the soil by estimating the proportions in which particles of various sizes are mixed together in the soil. Upon the physical structure of the soil so determined, or as we should practically term it, the *texture*, depend some of its most important features, particularly its behaviour with regard to the supply of water to crops and its amenability to cultivation.

In the first place it will be necessary to discuss a little more thoroughly the nature of the four substances

to which the texture of the soil has been referred—the sand, clay, chalk, and humus—of which the first two are of most importance, since soils which are mainly characterised by chalk or humus are less commonly in cultivation.

Sand.—On the seashore, in beds of an alluvial nature, and in formations of all geological ages, we are familiar with sand; in the main it consists of grains of quartz, rounded by continual rubbing, and more or less coloured by oxide of iron. It represents the quartz contained in the fundamental rocks, weathered and worn by the action of running water: in some cases of comparatively recent origin, in others it is material that has repeatedly been formed into a sedimentary rock, disintegrated afresh and sorted by the action of running water. The coarser the grains of which a sand is made up, the more rapid must have been the current of water from which it was deposited. The following table shows the rate of flow which is necessary to carry sand grains of various sizes:—

Diameter of Grains mm.	Velocity of Current mm. per sec.
0.5	64
0.3	32
0.16	16
0.12	8
0.072	4
0.047	2
0.036	1
0.025	0.5

A closer examination of most sands will show that they do not consist wholly of quartz grains, but also contain rounded fragments of many of the minerals present in the fundamental rocks which have any resistance to weathering. Flakes of mica are common,

fragments of more or less altered felspar, of oxide of iron, and even of tinstone, rutile and zircon, may be identified. In fine-grained sands the fragments of minerals other than quartz become as a rule more abundant, till they begin to predominate over the quartz grains in the finest silts and muds that are deposited from very gently moving water. Under the microscope the quartz grains show a crystalline structure, and a surface more or less dulled and rounded according to the travel the grains have suffered. In mass the chief characteristic of sand is its want of coherence when dry.

Clay.—The material we call clay is characterised by certain properties that are shown when the clay has been “puddled,” *i.e.*, kneaded when in a moist condition. The clay is *plastic*, it can be moulded and worked into various shapes, even into quite thin leaves, and it will retain these shapes on drying. During the drying process a shrinkage takes place: the dry material is hard and tenacious, and can only be broken or crumbled with difficulty. The shrinkage is considerable: a little brick was made of good modelling clay 7 inches long, and about 1 square inch in section; two marks were then made on this 6 inches apart; after a fortnight's drying in a room the marks were only 5.7 inches apart, showing a shrinkage of 5 per cent. Clay is further impermeable to water when in the moist puddled condition, for which reason it is used to line the bottoms of ponds in pervious soil, and is built up inside the retaining dams of reservoirs; quite a thin layer of clay will hold water indefinitely as long as it is not allowed to dry and crack, nor to be washed away by the action of running water.

From a chemical point of view, all clays are found to consist largely of kaolinite, the hydrated silicate

of alumina, which is formed by the weathering of felspar; the other materials present consist of extremely fine grains of quartz and other weathered minerals, together with more or less oxide of iron. "China clay" and the best "pipe clays" contain little or no iron; the deep-seated clay formations are generally coloured dark green or blue or black by the presence of ferrous silicates, like glauconite; on weathering and exposure at the surface the clays become yellow or brown, owing to the oxidation of these ferrous to ferric salts.

Water in which a little clay has been rubbed up remains turbid for a very long time; days and even weeks elapse before the particles settle down to the bottom—indeed, however long the liquid may be at rest, a slight haze or cloudiness may be observed within it. Schloesing has drawn a distinction between the part of the clay, amounting to 1 or 2 per cent. only of the whole, which persists in remaining suspended and the portion which settles down; he has called it "colloid clay," and attributes many of the typical clay properties to the jelly-like medium of colloidal matter in which the other defined particles of the clay exist. Schloesing associates this colloid clay with such typical colloids as the highly hydrated forms of silica and organic bodies like starch and gum which, though they appear to be truly dissolved, yet cannot diffuse through a membrane, and form, on drying, hard non-crystalline masses, with much shrinkage and a characteristic fracture. But later researches on colloids seem to show that they are not essentially different from suspended matter; they consist of particles too fine to settle down in water, or to be arrested by a filter even of porous porcelain, but still sufficiently coarse to show their presence when a strong beam of light is

passed through the liquid, as is not the case with bodies truly dissolved. From this point of view the "colloid clay" would only represent the limiting states of fineness, differing in degree, but not in kind, from the other clay particles.

It seems impossible to ascribe to clay any distinctive chemical composition, or to draw a sharp line of separation where sand ends and clay begins. The characteristic "clay" properties are due to the fineness, and not to the nature, of the particles composing the material.

The following considerations support this view— a sample of crude kaolinite rock as dug in Cornwall from the surface of granite, was powdered and passed through a sieve retaining all particles above 0.2 mm. in diameter; the remainder, which consisted mainly of kaolinite with a little mica, was further separated by sedimentation from water into four fractions:—

Fraction.	Approximate Size of Particles in mm.	Per cent. of Original Material.
1	0.2 to 0.05	22
2	0.05 " 0.01	39
3	0.01 " 0.005	21
4	below 0.005	20

Of these fractions the first contained all the mica, the others were practically pure kaolinite, yet the second fraction showed none, and the third very little of the characteristic properties of clay; when dried they fell or could easily be rubbed into a fine powder, only the fourth and finest fraction dried into a hard coherent mass. Thus we can have material which consists entirely of kaolinite, and yet is not clay; such as we see in natural deposits of Fuller's Earth, which

consists of kaolinite but possesses no plasticity, and falls on drying into a fine powder.

In the same way a natural soil contains particles of silicates of alumina of all sizes, though they only begin to predominate in the fractions of finest grain. A sandy soil separated into fractions by sedimentation and then analysed, showed the following proportions of alumina. The fractions were ignited before weighing to drive off constitutional water, etc. :—

Fraction.	Approximate Size of Particles, mm.	Per cent. of Original Soil.	Per cent. of Alumina in Material.	Per cent. of Kaolinite, calculated as $\text{Al}_2\text{O}_3, 2\text{SiO}_2$.
1	1 to 0.2	28	2.4	5.3
2	0.2 " 0.05	23	3.1	6.7
3	0.05 " 0.01	23	4	8.7
4	0.01 " 0.005	3.6	9	19.6
5	below 0.005	7.9	19	41.3

From thirteen soils resting upon the London Clay, the Gault Clay, and the Chalk respectively, the material finer than 0.005 mm. and usually regarded as clay, was separated by washing, attacked with ammonium fluoride, and the alumina estimated. The average per cent. of alumina in the ignited material was 28.8 per cent., the highest proportion being 34.2 per cent., and the lowest 20.8 per cent.; pure kaolinite $\text{Al}_2\text{O}_3, 2\text{SiO}_2, 2\text{H}_2\text{O}$, after ignition would yield 45.9 per cent.

Furthermore, if pure quartz be reduced to a very fine powder by grinding in an agate mortar, and then separated by sedimentation, it will be found that the finest grades of particles, 0.01 to 0.005 mm., and below 0.005 in diameter, show all the characteristics of clay and cohere strongly on drying.

Thus we must conclude that clay is not necessarily kaolinite, but is rather a general term for very fine-

grained material; we must take an arbitrary dividing line, and it is convenient to classify all particles below 0.005 mm. in diameter as clay, all above that size as sand or silt. The reason for the large proportion of kaolinite among these fine particles is to be seen in its origin from felspar by chemical action of water charged with carbonic acid, the resulting material falls naturally into a state of extreme subdivision; even the coarser particles are porous, and perhaps imperfectly kaolinised, so that frost and further decomposition and solution rapidly reduce them in size. On the other hand, quartz grains are almost wholly reduced by mechanical rubbing, they suffer little by solution or frost, and as attrition almost ceases when they have reached a certain degree of fineness, they will be relatively most abundant in the coarser fractions of the soil.

One property of clay which is of great agricultural importance is that when in a wet state the fine particles can be caused to aggregate loosely by a variety of agencies, especially by the addition of a very small quantity of certain dissolved salts. The following experiment will illustrate this: six cylinders were prepared, each containing 500 c.c. of the turbid liquid obtained by rubbing up a few grams of good plastic clay with distilled water; to one cylinder no further addition was made; to the second, third, and fourth, 0.1 gram of salt, gypsum, and alum respectively were added; to the fifth, 1 c.c. of semi-normal sulphuric acid ($=.0245$ gram H_2SO_4), and to the sixth, 50 c.c. of lime water ($=.065$ gram CaO) were added. The gypsum, alum, acid, and lime water caused the clay to coagulate and fall in about three hours, leaving an almost clear liquid above; the salt caused the same settlement in twelve hours; whereas the clay diffused in pure water remained in suspension, so as to cause turbidity for days.

In another experiment, three lots of 10 grams of crude china clay, and of fine plastic clay used for modelling, were each rubbed up with 250 c.c. of water; to one lot no addition was made; to the second, 0.1 gram of salt; and to the third, 0.1 gram of gypsum were added; the six were then left to stand, and separated into fractions by sedimentation in the manner described later, with the following results:—

250 Water with	CHINA CLAY.			MODELLING CLAY.		
	0	0.1 Salt.	0.1 Gypsum.	0	0.1 Salt.	0.1 Gypsum.
Falling in 1 minute .	2.22	2.54	2.28	0.53	0.45	0.41
Suspended for 1, but falling in 25 minutes	3.91	6.04	7.3	1.45	8.76	8.3
Suspended for 25 minutes, but falling in 24 hours	2.08	1.5	0.37	2.33	0.9	1.38
Suspended for 24 hours	2.0	5.53
Total Grams .	10.21	10.08	9.95	9.84	10.11	10.09

Joly has shown that in dilute solutions the flocculation power of various salts depends upon their ionisation, and varies with the valency of the electro-positive ion; thus a dissolved molecule of a sodium and of a potassium salt would have the same effect, but only half that of a molecule of a calcium or a magnesium salt, and one-third that of the molecule of an aluminium salt. The remarkable power of a trace of dissolved alum in causing the clearing of turbid water has long been used in practice.

The coagulating power of lime upon clay, by causing the fine particles to form into aggregates, is taken advantage of in the process of liming clay land to improve its "texture." The effect may be illustrated

by kneading up clay with a small quantity of milk of lime and moulding it into a brick as previously described; such a block made up with lime shrank 0.2 inch only, when the pure clay shrank 0.3 inch, and moreover could be easily powdered when dry.

A piece of clay exposed to weather for some time, so that it undergoes alterations of temperature, freezings and thawings, wetting and drying, will experience a certain amount of coagulation, so that if caught at the right state of partial dryness it may easily be crumbled. On the contrary, if clay be worked when wet, the aggregates that may have been formed by coagulation will be broken up and resolved into their ultimate particles; the clay so treated will retain water obstinately, shrink very considerably on drying, and then form a mass of extreme tenacity; the clay has been brought into its finest grained condition by the working, and all the characteristic clay properties are manifested in the extreme.

Chalk, or carbonate of lime, is present in all soils, with the exception of a few extremely open sands, and peaty soils that are practically of vegetable origin. The proportion varies enormously according to the origin of the soil; on some of the thin loams derived directly from the great calcareous formations like the chalk or the oolite, the calcium carbonate in the soil may rise to as high a proportion as 60 per cent., but in the majority of the loams under cultivation the proportion is nearer 1 per cent., and it often falls much below this in clays and sands. Chalk in the soil is essentially a transitory substance, as it is constantly removed by the action of percolating water charged with carbonic acid arising from the decay of vegetable matter in the surface soil. Many of the fermentation changes that also take place in this vegetable matter

give rise to acids, which in their turn combine with the calcium carbonate. So rapid are these removals of calcium carbonate that it is difficult to understand how any of it persists in the surface layers of many soils, the subsoil of which shows that they must have been initially poor in chalk, were there not some compensating agencies at work. Amongst these agencies must be reckoned the calcium salts in plants, which in many cases have been drawn up by deep-seated roots from the subsoil, and become calcium carbonate on the ultimate decay of the plant tissues.

In a normal soil the particles of calcium carbonate are of all sizes, many of the finer particles of silt and clay are loosely cemented together by calcium carbonate, as may be seen by the increase in the finer fractions if a soil be washed with dilute acid before it is separated by sedimentation.

Humus.—The term humus is applied to the black or dark brown material of vegetable origin which gives to surface soil its characteristic darker colour as compared with the subsoil. It is essentially a product of bacterial action; there are a number of bacteria working in the absence of air and universally distributed, which attack the carbon compounds of plant tissues, especially the carbohydrates, with the production of marsh gas or hydrogen, carbonic acid, and humus. In the presence of air the characteristic humus-forming fermentation is replaced by one which results in the complete combustion of the organic matter to carbonic acid. For this reason more humus is found in a pasture than in a continually aerated arable soil, more again in clays than in the lighter soils through which air is always being drawn as the rain percolates, and the accumulation of humus reaches its maximum where considerable rainfall and an impermeable stratum combine to make the soil so

water-logged that all access of air is cut off, as in swamps and bogs. The presence of chalk in the soil also assists in the destruction of humus, since it neutralises the acids which largely compose the humus, and which tend to inhibit the further action of bacteria.

The chemical composition of humus is indefinite ; it is a variable mixture of several substances, themselves of very complex constitution ; it always contains more carbon and less hydrogen and oxygen than the vegetable tissues from which it was formed. The following figures show the composition of grass and of the top brown layer of turf in a peat bog, also of the same peat of greater age at depths of 7 and 14 feet, the mineral matter and moisture being excluded in calculation in each case:—

	Grass.	Top Turf.	Peat at 7'.	Peat at 14'.
Carbon . . .	50.3	57.8	62	64
Hydrogen . . .	5.5	5.4	5.2	5
Oxygen . . .	42.3	36	30.7	26.8
Nitrogen . . .	1.8	0.8	2.1	4.1

Substances akin to humus can be formed from the carbohydrates (such as sugar, starch, and cellulose), by heating them for some time with water under pressure, the action being more rapid if a trace of mineral acid be present ; these substances are weak acids and form salts, so are generally termed humic acid :—

	HUMIC ACID.	
	From Sugar.	Natural.
Carbon . . .	63.9	56.3 to 59
Hydrogen . . .	4.6	4.4 " 4.9
Oxygen . . .	31.5	32.7 " 36
Nitrogen	2.8 " 3.6

Part of the natural humus is acid in its nature and is generally present in the soil in the form of a salt; if soil rich in humus be first treated with dilute acid to decompose the humates, and after washing away the acid, be well shaken with a 5 per cent. solution of ammonia or other alkali and allowed to stand, a dark brown solution will be formed. This is akin to the dark liquid draining from a dung heap, which consists of humus dissolved by the alkaline carbonates of the fermented urine. The solution does not contain the whole of the organic matter of the soil; when neutralised with an acid a brown precipitate of so-called "humic acid" is precipitated, which does not, however, include the whole of the humus dissolved by the alkali. Another portion of the natural humus of soils is soluble in acids, it seems to contain nitrogen, and to be of the nature of an amide.

Although dark brown humic substances can be prepared from carbohydrates, and therefore contain only carbon, hydrogen, and oxygen, yet the organic matter of the soil, even when dissolved and reprecipitated, always contains some nitrogen, nor can it be obtained entirely free from phosphorus and mineral matter. The original vegetable matter is made up not only of carbohydrates, but of other carbon compounds containing nitrogen, and in some cases both nitrogen and phosphorus; these all break down under bacterial action into dark-coloured substances richer in carbon, and roughly classed as humus. The splitting-up process continues in the soil, so that humus becomes one of the great sources of nitrogen for the food of plants, and a soil well supplied with humus is generally regarded as fertile.

During the formation and continued decomposition of humus the carbohydrates appear to be first attacked,

and the nitrogen-containing bodies, *e.g.*, the nucleins in particular, resist the action of bacteria. For this reason, where we find the proportion of humus in a soil is low, the proportion of nitrogen in the humus itself will be high, the decay of the humus falls more heavily on the purely carbonaceous part of the material.

This is seen in the figures obtained by Lawes and Gilbert, for the ratio that exists between the proportions of carbon and nitrogen in various soils:—

	RATIO $\frac{C}{N}$.	
Cereal Roots and Stubble	.	43
Leguminous Stubble	.	23
Dung	.	18
Very old Grass Land	.	13.7
Manitoba Prairie Soils	.	13
Pasture recently laid down	.	11.7
Arable Soil	.	10.1
Clay Subsoil	.	6

Hilgard and Jaffa also found that the humus of soils in an arid climate, where the deficiency of rainfall causes the soil to be very open, contains a higher proportion of nitrogen than is found in the humus of damper soils:—

	No. of Samples Examined.	Average per cent. of Humus in Soil.	Average per cent. of Nitrogen in Humus.
Arid Soils . . .	18	0.75	15.87
Semi-arid Soils . .	8	0.99	10.03
Moist Soils . . .	8	3.04	5.24

These results would seem to indicate that the most valuable humus, which is most likely to decay rapidly and yield nitrogen compounds available as food for plants, is that possessing a high ratio of carbon to nitrogen.

Against this, Berthelot and André have investigated the ratio of carbon to nitrogen in the different portions of the humus which can be dissolved by alkalis or acids, and they find that the most soluble portions contain the highest proportion of nitrogen. It does not, however, follow that the substances most soluble in acids or alkalis are necessarily those which will most readily be converted by bacteria into a form available for plants, and, on the whole, the evidence seems to show that a humus rich in nitrogen will yield it very slowly to crops.

Humus acts as a weak cement and holds together the particles of soil, thus it serves both to bind a coarse-grained sandy soil, and, by forming aggregates of the finest particles, to render the texture of a clay soil more open. In determining the sizes of the constituent particles of a soil, the "mechanical analysis," it is desirable to remove the humus as far as possible, and so break up these temporary aggregates.

Sampling of Soils.

The first step in the analysis of any soil, mechanical or chemical, consists in obtaining a sample that shall adequately represent the land in question.

In this country it is customary to take a sample down to a depth of 9 inches as representing the soil proper; it is, however, doubtful if this is not too deep, being below the depth to which cultivation is generally carried; probably a 6-inch sample would more truly represent the cultivated soil. In many cases it will be found that the true soil does not extend to a depth of anything like 9 inches, but that there is a sharp change into subsoil or even rock before this point: *e.g.*, on the chalk downs the soil is often not more than 4 inches deep, below which

white broken chalk rock begins. In such cases the sample must only be taken to the depth at which the visible change begins.

To obtain the sample two methods are generally adopted. At Rothamsted a steel box, without top or bottom, 9 inches deep, and 6 inches square in section, is used; the sides are wedge-shaped, about $\frac{3}{4}$ inch thick at the top, and taper off to cutting edges below. The surface, if uneven arable land, is first raked over and gently beaten level, then the box is placed in position and driven down with a heavy wooden rammer till the top of the box is flush with the surrounding soil. The soil enclosed by the box is then carefully dug and scraped out into a bag for conveyance to the laboratory; two or three samples to the same depth being taken from the same field and afterwards mixed. Should samples of the subsoil be required, the box is left in position after its contents have been scraped out, and the surrounding soil is dug away to the 9-inch level, the box is then rammed down for the second 9 inches, and its contents removed: the process being repeated till the required depth has been reached.

A modification of the Rothamsted method consists in marking out on the surface a square 9 inches on the side, and digging away the surrounding soil until a 9-inch cube of earth remains standing; over this a wooden box is slipped, and the cube is cut off by pushing a spade beneath at the 9-inch level.

On soils which do not contain many large stones, samples may be taken with an auger, both more rapidly and with greater security of obtaining an average sample. A convenient tool for the purpose consists of a cylindrical auger made of steel about $\frac{1}{16}$ inch thick, of 2 inches internal diameter and 12 inches deep, with a slot $\frac{3}{4}$ inch wide running from top to bottom; the lower






FIG. 1.—Photograph of Soil-sampling Tools.

edge of the cylinder and the edges of the slot are sharpened ; to the upper end of the cylinder a handle carrying a wooden crossbar is rivetted. The auger is forced gently into the soil with a twisting motion until the required depth is reached, when the tool is withdrawn and the core scraped out into a bag. Six to ten cores at least are taken at regular intervals in the same field and mixed to secure an average sample. Each boring can be continued to obtain subsoil samples as deep as the length of the handle permits. It is impossible to obtain samples with the auger when the soil is dry. Fig. 1 shows a photograph of both types of soil sampling tools.

When the samples reach the laboratory they are spread out on shallow trays to dry, which process may be accelerated by a gentle warmth, not exceeding 40° C. In dealing with stiff soils it is advisable to crumble all the lumps by hand while the earth is still somewhat moist. When the whole is sensibly dry the stones are separated by a sieve having round holes 3 mm. in diameter ; the material that does not pass the sieve is gently worked up in a mortar with a wooden pestle, care being taken not to break the stones, chalk, etc., but only to crush the lumps of earth. Finally, the material upon the sieve is roughly weighed and well washed in a stream of water till all the fine earth is gone, dried, picked over to free it from roots and stubble, and weighed as "stones." To get the proportion borne by the stones to the soil, the fine earth is also weighed, an addition being made of the weight lost by the stones in washing.

Of course the figure obtained for the proportion of stones is only approximate, for if the stones are of any size they will be very irregularly caught by the auger or even by the 6-inch square tool. The material passing the sieve is again spread out in a thin layer in an ordinary room, until the surface maintains the same

colour as the lower layers; it is then bottled up as "air-dry fine earth" for analysis.

The Mechanical Analysis of a Soil.

The mechanical analysis that follows consists in dividing the fine earth into a series of fractions consisting of particles of known size; we can use sieves to sort out the coarser grades, but the finer ones must be separated by their relative powers of remaining suspended in water.

The methods in use depend on two principles: in one, the hydraulic method (Hilgard, Schöene, Nöbel), soil is washed by successive currents of water of velocities calculated to carry particles of the required size according to the table on p. 33: in the other, the sedimentation method of Osborn, Knop, and Schloesing, the soil is suspended in water and allowed to stand, the separation being effected either by the times required for the particles to settle down through a fixed distance, or by the distances fallen in a given time. The method to be described is based upon the latter principle. The hydraulic method requires special apparatus, and is only suited to laboratories entirely devoted to soil analysis.

Method of Analysis.

1. Ten grams of the air-dry fine earth are weighed out into beaker or basin and treated with 100 c.c. of hydrochloric acid containing 2 c.c. of the strong acid; the soil is well worked up with a rubber pestle (made by fixing a glass rod into a small solid rubber bung) until all the lumps of clay, etc., are broken up.

The object of the acid is to dissolve the carbonates and humates, and thus loosen the particles in any aggregates, where chalk or humus form the cement.

After standing with the acid for an hour, the whole is thrown on a tared filter and well washed until all acid is removed. The filter and its contents are dried and weighed, the loss the soil has suffered represents the material dissolved and the hygroscopic moisture.

2. The soil is now washed off the filter into a glass cylinder 5 cm. in diameter and 20 cm. high. It is well worked with the rubber pestle, and distilled water is added up to a mark 15 cm. above the bottom of the tube. 1 c.c. of strong ammonia is added, the whole well shaken and put to stand.

The ammonia completes the dissolution of the humates, and also masks the effect of any traces of soluble salts which may be left and would cause aggregation in the manner indicated earlier, p. 39.

After twenty-four hours at rest, the turbid liquid is poured off the sediment, which is again worked up with the rubber pestle; water and ammonia are added as before, and after twenty-four hours' standing the supernatant liquid is poured off and added to that obtained in the previous operation. The process is repeated as long as there is a distinct turbidity in the liquid above the sediment which falls in the twenty-four hours; about eight or ten operations usually suffice. The turbid liquid, amounting to about 2 litres, is evaporated over a water-bath in a tared porcelain basin, the residue ignited and weighed as "clay."

The liquid containing the clay may be well shaken, measured, and an aliquot, 500 c.c. or a litre, taken for the estimation of clay. From a second portion the clay may be precipitated by the addition of $\frac{1}{2}$ gram of potassium chloride, the clear brown liquid evaporated over the water-bath, and the residue dried and weighed as "soluble humus," a deduction being made of the saline residue left after ignition.

3. Some beakers, about 9 cm. high and 8 cm. in diameter, are now prepared with a mark on the side 7.5 cm. above the bottom. The sediment from which the clay has been separated is thrown on a small sieve of woven wire, 100 meshes to the linear inch, such as is used in the examination of basic slag; this allows all particles with a smaller diameter than 0.2 mm. to pass. The sieve is placed in the mouth of a beaker, and the material washed through with a jet from a wash bottle, aided if necessary by a little gentle rubbing with the pestle. After drying, the material on the sieve is put through a sieve with round holes 1 mm. in diameter, the portion arrested is ignited and weighed as "fine gravel"; the portion passing through the 1 mm. holes, but which has been caught by the woven sieve, is similarly ignited and weighed as "coarse sand." The sediment in the beaker, from which the clay and gravel have been separated, is now rubbed up with the pestle, and distilled water added to the mark. The contents of the beaker are then thoroughly agitated by stirring with the pestle, and the pestle is carefully withdrawn, so as not to leave the liquid with any sensible circular motion. After standing exactly sixty seconds the supernatant liquid is steadily but rapidly poured off the sediment. The operations of pestling, filling up with water, stirring and pouring off after sixty seconds, are repeated as long as there is anything left in the beaker which does not settle down in the minute. The sediment is then washed into a tared porcelain basin, dried, ignited, and weighed as "fine sand"; the particles will be found to range between the 0.2 mm. passed by the sieve and 0.05 mm. There will now be left a series of beakers containing material which can remain in suspension for sixty seconds but not for twenty-four hours; this has to be divided into two or

more fractions. The beakers are all filled up to the mark, agitated, and allowed to stand for twenty-five minutes before pouring off as before. The sediments in each are then united into a single beaker, the contents of which are made up to the mark with water, agitated, and again allowed to stand for twenty-five minutes before pouring off. These operations are repeated until the supernatant liquid clears in the twenty-five minutes. The sediment which has fallen in the twenty-five minutes, but previously remained suspended for one minute, is dried, ignited, and weighed as "silt"; its particles range in size between 0.05 and 0.01 mm. The turbid liquid, now amounting to 2 litres or more, may be further subdivided, using five hours as the time of settling, or may be evaporated and the residue ignited and weighed as "fine silt." The particles which compose this fraction range in size from 0.01 mm. down to the limit we have adopted for clay, which is about 0.005 mm.

The sizes of the particles, the depth of the liquid, and the times adopted above are purely empirical. The time of settlement required to obtain a fraction of any given range of size can be determined by a series of trials, the material remaining suspended in each case is measured under the microscope until the right time is hit off to secure the desired range of size in the sediment.

The hygroscopic moisture and the loss on ignition also require determination, which is described under the chemical analysis of a soil.

Interpretation of Results.

It is as yet impossible to predict the behaviour of a soil under cultivation from a consideration of its mechanical analysis; in a general way we can see

whether a soil is heavy, whether it is likely to dry "steely," or whether it will crumble readily under proper cultivation, and whether it is more suitable for market gardening or wheat growing, but the more refined points of difference connected with the management of given soils, which become known by experience to a good practical farmer, cannot as yet be deduced from the analysis. It is necessary to accumulate more data, until we possess the mechanical analysis of a large number of soils whose texture and amenability to cultivation have been ascertained by long practice; then we shall be able to assign any soil by its mechanical analysis to a known type.

The power of a soil to retain moisture and resist moderate drought depends on a predominance of the finer particles and of humus; good wheat land or land that will form sound permanent pasture will contain at least 30 per cent. of silt and clay. The case with which a soil suffers the rain to percolate depends upon the relatively low proportion of silt and clay rather than on the amount of coarse-grained material; the fine particles pack in among the larger, and the soil is equally resistant to the passage of water, whether the finest material is diffused among coarse sand and gravel, or among the finer grades of sand. The shrinkage of a soil on drying, and its tenacity when dry, are even more dependent on low proportions of coarse sand, humus, and chalk, than on the actual amount of clay and silt which cause the shrinkage. The really difficult soils to work are those containing less than 20 per cent. of sand above 0.1 mm. in diameter.

The following examples will serve to illustrate these points :—

SOILS.						
	1	2	3	4	5	6
	Coarse Barren Sand.	Coarse Sandy Loam.	Fine Sandy Loam.	Light Calcareous Loam.	Heavy Clay Loam.	Heavy Clay.
Moisture	1.35	1.83	1.62	2.93	3.08	9.5
Loss on Ignition	4.73	3.16	3.46	5.06	4.22	9.1
Calcium Carbonate	0.33	3.7	...	0.4
Fine Gravel, 3 to 1 mm. . .	0.2	7.6	0.50	0.5	2.8	0.4
Coarse Sand, 1 to 0.2 mm. .	22.6	44.9	15.03	16.1	14.1	0.8
Fine Sand, 0.2 to 0.05 mm. .	60.8	23.1	48.99	31.9	31.2	6.4
Silt, 0.05 to 0.01 mm. . .	4.8	4.3	15.26	21.5	17.4	18.6
Fine Silt, 0.01 to 0.005 mm. .	0.6	2.9	3.90	3.7	6.9	13.6
Clay, below 0.005 mm. . .	1.76	11.7	9.74	13.4	18.5	42.2
SUBSOILS OF ABOVE.						
Moisture	1.97	1.71	2.35	6.35	6.3
Loss on Ignition	1.94	2.49	5.56	4.73	7.3
Calcium Carbonate	0.05	14.9	...	0.1
Fine Gravel, 3 to 1 mm.	10.6	0.86	0.3	0.2	0.2
Coarse Sand, 1 to 0.2 mm.	35.4	16.55	11.4	1.4	0.5
Fine Sand, 0.2 to 0.05 mm.	15.1	42.60	24.8	7.3	6.2
Silt, 0.05 to 0.01 mm.	8.4	17.16	21.8	9.3	15.9
Fine Silt, 0.01 to 0.005 mm.	4.2	4.73	4.8	10.6	10.2
Clay, below 0.005 mm.	11.3	12.56	13.2	56.2	48.9

Of the above soils, No. 1 represents the surface soil only of a barren, unenclosed heath, situated upon the Lower Greensand in Surrey; it will be seen that more than 83 per cent. of the soil consists of "sand," while the finer fractions only amount in all to 7.2 per cent., of which less than 1.8 per cent. can be reckoned as "clay." Calcium carbonate also was entirely wanting in the soil, which serves to explain the comparative richness in humus. This is a typical example of the barren sands which naturally carry heather and pine, and accumulate peat wherever they are low-lying.

No. 2 represents a coarse sandy loam under arable

cultivation, and situated on the Lower Greensand in West Kent; this soil contains as much as 68 per cent. of sand, of which nearly 45 per cent. is the coarse sand of diameter greater than 0.2 mm.; there is also a comparatively large proportion of "fine gravel," so that the whole soil has a very gritty feeling. The proportion of clay is, however, nearly up to 12 per cent., and this with the 7 per cent. or so of "silt" gives the soil a fair amount of cohesion and power of retaining moisture. However, the large proportion of coarse sand causes the soil to fall to pieces on drying; and were the soil not deep and naturally well supplied with water by soakage, it would carry very indifferent crops. Though the proportion of calcium carbonate is very small, this soil possesses a neutral reaction, and is healthy. It is noticeable that there is very little change in texture in passing down to the subsoil; it is a "sedentary" soil, formed out of very soft sandstone rock, and the only change noticed, even down to a depth of 5 feet, was a brighter colour and an increased proportion of stony fragments.

Soil 3 is a fine-textured sandy loam, resting upon the Thanet Sands in East Kent; in this soil the fine sand and silt preponderate, and the subsoil is of very similar texture. This represents a soil of excellent texture, easily worked, drying readily after rain, yet possessing a fair retentivity for moisture, and a great power of lifting the subsoil water by capillarity, so that the land does not suffer readily from droughts. One difficulty in the cultivation of these soils is, that when a tilth has been established, they are apt to run together under heavy rain and then dry with a hard cake on the surface. These fine-textured soils, when not naturally drained to excess, give rise to land of great fertility for all purposes, warm and easily

cultivated, and answering well to applications of manure.

Soil 4 is a typical light calcareous loam, resting on the Chalk in the Isle of Thanet. The proportion of calcium carbonate is high and increases in the subsoil, which is otherwise very similar in texture to the surface soil; probably the whole is more or less a "drift" deposit rather than a true sedentary soil. The characteristic feature of the soil is the predominance of fine sand and silt, which with the calcium carbonate causes the soil to be sticky when wet, and liable to dry very steely, although the amount of clay is not high.

This soil drains very rapidly, and possesses only a moderate power of retaining water; it easily suffers from drought, but chiefly because it is naturally shallow and rests upon the Chalk, for there is enough of the silt and fine silt in both soil and subsoil to ensure a good capillary lift of any subsoil water to the surface.

This soil might be taken as a typical "sheep and barley" soil; too light for wheat, and much benefited by the consolidation effected by folding sheep upon it. Soils of this type require the free use of the roller in the early months of the year.

Soil 5 is a strong wheat and permanent pasture soil, resting upon the London Clay in West Surrey. This land is suited to arable cultivation, and not too heavy to prevent a good tilth being secured. It will be noticed that the proportion of sand in the surface soil is comparatively high, as much as 45 per cent., of which 14 per cent. is coarse sand; this ensures a fair measure of friability, though the finer fractions amount to 43 per cent., 18.5 per cent. being clay.

The subsoil consists of very pure clay, containing more than 76 per cent. of the three finest groups of particles, as much as 56 per cent. being reckoned as clay. Such an impervious subsoil holds up the water very considerably in the cultivated portion, and to some extent explains the manner in which wheat and pasture flourish on this soil, for the analysis of the surface soil does not represent a really heavy or strong soil.

Soil 6 is a heavy, undrained London Clay, which will carry nothing but poor pasture. At one time it would carry in favourable seasons heavy crops of wheat and beans, but the expense of cultivation and the danger of missing a season have rendered it quite unprofitable to farm under the plough.

It will be noticed that the soil consists almost wholly of the finer fractions, nearly one-half being "clay"; nor is there any difference between soil and subsoil, except in the humus, which improves the texture of the surface.

CHAPTER III

THE TEXTURE OF THE SOIL

Meaning of Texture and Conditions by which it is affected—Pore Space and Density of Soils—Capacity of the Soil for Water—Surface Tension and Capillarity—Percolation and Drainage—Hygroscopic Moisture.

IN the preceding chapter, the nature of the particles composing the soil has been discussed; it now remains to consider the manner in which they may be arranged, and the structure that results from the interaction of the soil particles, the water, and such salts as may be dissolved in the water. On these factors depend what the farmer knows as the "texture" of the soil, the degree of resistance it affords to the passage of a plough, etc., the ease or otherwise with which that prime object of cultivation, the preparation of a seed bed, can be attained.

It is clear that as a soil consists of particles there must be between them a certain amount of space which is occupied by air or water; this is known as the "pore space," and on its amount will largely depend the density of the soil. Taking the simplest theoretical case, a soil made up of equal spheres in contact with one another, it will be found that the pore space is dependent upon the method of packing, but not upon the

size of the spheres. If the system of packing shown in A and B, Fig. 2, is adopted, the pore space reaches its maximum and amounts to 47.64 per cent. of the whole volume occupied by the soil; this proportion is the same though the soil particles have a smaller diameter, as in B; as long as the spheres are uniform in size, whatever that may be, and are packed as shown in the diagram, the pore space will be at its maximum. The minimum pore space is attained by the packing shown in C and D; it amounts to 25.95 per cent., and is again independent of the size of the particles, provided they are uniform. If the spheres that are packed together are, however, of very different sizes, so that smaller spheres lie wholly within the spaces between the larger spheres, as in the arrangement shown in E, the pore space may be indefinitely reduced. *Per contra*, if aggregates of particles exist in the soil, containing both pore space between the ultimate particles and between the aggregates which behave as single particles, as in F, the pore space may rise much above the maximum of 49 per cent. A soil *in situ* generally possesses a pore space larger than the proportions indicated above; various causes, such as the stirring due to cultivation, the decay of vegetation, etc., leave definite cavities in the soil: for example, if a hole be dug for any purpose in ordinary cultivated ground and afterwards filled up with its own soil, it is rarely possible to fill the hole completely, especially if a little pressure has been used to trample down each layer.

In ordinary soils the pore space varies from a little over 50 per cent. among the stiff clays, down to 25 or 30 per cent. in the case of coarse sands of uniform texture. The reason for the greater pore space with the finer grained soils lies in the fact that the weight of the small particles of clay is not sufficient to overcome the




FIG. 2.—Diagram illustrating Pore Space between Spherical Particles.

friction and move the particles into the arrangement giving the minimum pore space. If some small shot are shaken into a graduated measure and the pore space determined by pouring in a measured volume of water, the indicated minimum will be found; but if the experiment be repeated with sand which has been sifted to get approximately a uniform size, a higher figure will result. In the one case the particles are too light to exert much force towards the rearrangement of the mass; in the former case the heavy smooth shot slip straightway into the most compact arrangement, because by it the shot attain their lowest position. In consequence of the pore space, the density of a soil *in situ* will differ very much from that of the materials of which it is composed, nor will all soils possess the same apparent density when dry. Perhaps the best way of ascertaining the apparent density of a soil or soil materials is to get a smooth metal pint pot or like measure, fill it with the material in question with gentle tapping, and then strike off the upper surface smooth with a rule. The weight of the contents divided by the volume gives the apparent density, from which the true volume and the pore space can be calculated, if the true density of the material be known. The following table shows the true and apparent density of the chief soil materials; as a mean figure for purposes of calculation, 2.65 can be taken as the true density of ordinary soils:—

	True Density.	Apparent Density when dry.
Humus	1.2	.34
Clay	2.5	1
Sand	2.6	1.45
Calcium Carbonate . . .	2.75	...
Hydrated Oxide of Iron .	3.4 to 4	...

The following table shows a few determinations made in the laboratory, of the apparent density of various soils in a roughly-powdered state and without the stones, which, being solid, would add to the apparent density of the soil. The results are also re-calculated to show the weight of a cubic foot of the soil, and the weight per acre of a layer 9 inches deep :—

	Apparent Density.	Weight per cubic foot.	Lbs. per acre to 9".
Heavy Clay	1.062	66.4	2,150,000
Sandy Clay	1.279	80	2,600,000
Sandy Clay Subsoil	1.18	73.7	2,380,000
Light Loam	1.222	76.4	2,480,000
Light Loam Subsoil	1.144	71.5	2,320,000
Sandy Loam	1.225	76.7	2,490,000
Sandy Peat	0.782	49	1,580,000
Light Sand	1.266	79.2	2,560,000

The figures given above are not exactly comparable with soils under natural conditions, because of the powdering, the exclusion of stones, etc., but they serve to show that the clay soils usually described as "heavy" are really less dense, and weigh less per cubic foot than some of the lighter soils, whereas pure sands are the densest of all. The farmer's terms of "light" and "heavy" land refer to the draught of the plough, the resistance the soil opposes to being torn asunder, and not to the actual weight of the portion moved; sands which he calls "light," being, as the table shows, heavier per cubic foot than the clays which the farmer calls heavy soils.

This point will be further elucidated by the following table, which shows the weight per cubic foot of the arable soils at Rothamsted and Woburn down to a depth of 3 feet. These results represent the real weights

of the soil as obtained by cutting out a block 6 inches square by 9 inches deep, weighing it, and afterwards ascertaining the deduction to be made for water. The Rothamsted soil is a stiff clay with many flints; the Woburn soil is a loose, coarse-grained sand, with only a little stone derived from the rock below. It will be seen that, if the stones be excluded, the density increases with the depth, because of the greater consolidation caused by the weight above and to some extent by the washing down of the finest particles, but the increase does not continue much below the depth of 3 feet, the limit of these measurements:—

		Weight per cub. foot.	Per cent. of Stones.	Weight per acro.
		LBS.		LBS.
Rothamsted Arable Broadbalk	0" to 9"	95.4	16.8	3,116,000
	9" " 18"	93.0	12.0	3,037,000
	18" " 27"	92.0	7.1	3,004,000
	27" " 36"	92.2	7.5	3,012,000
Woburn Arable	0" " 9"	96.6	2.96	3,157,000
	9" " 18"	103.8	5.95	3,382,000
	18" " 27"	106.2	4.92	3,462,000
	27" " 36"	106.9	7.83	3,501,000

From the data thus obtained as to density and pore space, together with a mechanical analysis to show the proportion of particles of various sizes, it is possible to calculate for any given soil both the number of soil particles and the area of the surface they expose, on the assumption that the particles are spherical. Approximately with grains 1 mm. in diameter, there would be 700 grains in 1 gram of the soil, and the number of grains to the gram will vary inversely as the third power of the diameter, *i.e.*, if the diameter be divided by 10 and become 0.1 mm., there will then be

700,000 grains to the gram. The surface possessed by all the soil grains can be similarly deduced by calculation, and will be found to vary inversely as the diameter of the individual grains; a sphere 1 inch in diameter will have only half the surface of the eight spheres of half an inch in diameter which possess the same volume. Hence it follows that the surface of an ordinary soil must be extremely extensive, and as many of the properties of the soil are dependent upon the surface it becomes important to arrive at some measure of this quantity. By calculation only a very rough idea of its extent can be formed, both because every departure of the soil grains from the spherical form will increase the surface without affecting the weight, and also because the mechanical analysis of a soil gives only a generalised statement of the distribution of soil particles of various sizes in the soil. But the surface of the soil grains in the case of a sandy soil where the grains are all free, may be calculated from the observed rates of flow of fluids like air or water through a measured portion of the sand; and by using this method King has computed the surface of the constituent particles of various types of soil with the results set out below:—

	Pore Space, per cent.	Area of Surface per cubic foot of Soil.
Finest Clay	52.9	173,700
Fine Clay Soil	48	110,500
Loamy Clay Soil	49.2	70,500
Loam	44.1	46,500
Sandy Loam	38.8	36,900
Sandy Soil	32.5	11,000

As a rough figure to remember, the surface of the particles in one cubic foot of an ordinary light loam

may be taken as about an acre; this will increase as the soil approaches more and more to clay, and diminish as the soil becomes increasingly sandy. The extent of surface exposed by the soil particles is important because it is their active part; other conditions being equal, the amount dissolved from a solid body in a given time by any solvent will be proportional to the surface exposed.

Again, the water in a soil usually exists as a film, coating the surface of the soil particles, and the amount of water that can be held under particular conditions becomes a function of the extent of surface; even the power of a soil to remove certain salts from solution is likewise dependent on the surface.

Capacity of the Soil for Water.

So far, the structure of the soil in a dry state has only been considered, it is now necessary to consider its behaviour when fully saturated with water, before passing on to the more usual state when the soil contains both air and water.

The amount of water which a soil will hold when completely saturated will depend upon the pore space, will, in fact, be the pore space together with whatever water the material of the particles can imbibe without causing any swelling. Perhaps the best method for determining the water capacity of a soil is one devised by Hilgard. A small cylindrical brass box is constructed, 1 cm. deep and 6 cm. in diameter. The bottom is a sheet of perforated brass, and the whole is supported on three legs; the capacity of the box is about 30 c.c. The exact capacity is determined by waxing up the holes, weighing, filling with water, and re-weighing. A circle of thin filter paper cut to fit the box is laid inside

and wetted, any superfluous water that comes through being wiped away. The box is then weighed, carefully filled with fine earth, and gently tapped to settle the soil down; finally, the surface is struck off level with a straight-edge. The box is now weighed again to find the quantity of dry soil taken, and placed in a dish of distilled water, so that the water stands about 1 mm. above the lower surface of the soil inside the box; the dish is then covered over to prevent evaporation. The water rises in the soil, displacing the air, and in about an hour's time the soil absorbs all the water possible. The box is lifted above the water a little, allowed a few minutes to drain, the excess of water clinging to the under surface is wiped away with a clean cloth or filter paper, and the whole is then weighed. A previous determination of the moisture present in the "air-dry fine earth" must also be made, to provide all the data necessary for the calculation of the water contained in the saturated soil. This calculation may be made in three ways: either the proportion the water in the saturated soil bears to the dry soil, or the proportion of water in the wet soil may be estimated, or again, the proportion by volume that is occupied by water and soil respectively may be calculated. The figures obtained will vary very considerably, because the less dense soils which contain clay and humus absorb the more water; thus the proportion which the water absorbed bears to the weight of the dry soil becomes exaggerated in their case. Perhaps the soundest picture of the state of affairs is attained by considering the volume that is occupied by the water in the soil, and expressing it either as a percentage by volume, or as lbs. or inches of water per cubic foot of wet soil. The following figures show the results obtained for four distinctive

soils, calculated out in the different ways described above.

	MAXIMUM.			MINIMUM.			Per cent. of Water when Air-dry.
	Water absorbed, per 100 of Dry Soil.	Per cent. of Water in Saturated Soil by Weight.	Per cent. of Water in Saturated Soil by Volume.	Per 100 Dry Soil.	Per cent. by Weight.	Per cent. by Volume.	
Coarse Sandy Soil	45	31	50.5	18	15.3	22.2	0.8
Light Loam . .	50.5	33.5	55.8	29.2	22.6	35.4	2.9
Stiff Clay . .	98.6	49.6	67.6	56.4	36.1	45.6	6.9
Sandy Peat . .	155	60.8	63.2	116	53.7	52.8	8.3

Under natural conditions a soil is rarely saturated to the extent indicated in the previous table; as the rain water enters from above the surface of the soil is wetted first and the air within the soil finds a difficulty in escaping, so that even after long-continued rain the pore space does not become entirely filled with water.

The following table shows the water contained in a few field soils sampled a day or two after the cessation of long-continued rain, and calculated as percentages of the wet soil by weight.

	Per cent. of Water in Wet Soil.
Sand at Water Level	18.4
Rothamsted Wheat Land, unmanured	23.0
" " manured with artificials	24.7
" " manured with dung for 26 years	37.6
Light " Loam above " Chalk	20.3

Hellriegel has shown that the optimum proportion of water in the soil for the growth of the plant is

attained when it contains 40 to 50 per cent. of the maximum required for saturation.

Flow of Water through Soils.

The freedom with which water will move through soils under the action of gravity or other force will depend not only on the pore space, but upon the mean size of the channels formed between the soil grains. King made some experiments with sands graded by sieves and formed into columns 14 inches long and 1 square foot in section, above which the water was maintained at a head of 2 inches. He obtained the following results expressed in inches of water passing in twenty-four hours; the second column gives the number of meshes to the inch of the sieves which respectively passed and retained the sand.

Medium.	Sieves.	Inches.
Sand	40 to 60	301
"	60 " 80	160
"	80 " 100	73.2
"	passing 100	39.7
Clay Loam	1.6
Black Marsh Soil7

It will be noticed that there is a great diminution in the rate of flow as soon as a soil containing small clay particles is introduced; of course, one of the characteristic properties of clay is that it will not allow any flow of water through it when it has been puddled. In the puddled condition, the particles constituting the clay are no longer aggregated, the material is in its finest-grained condition, so that the pore spaces between them must have become extremely small. Not only is the flow diminished by the increase

of friction in the narrow channels, but in the case of clay their dimensions have become so small that probably the contained water is wholly within the range of the molecular forces to be described later, and is thus prevented from flowing at all, only moving by diffusion. If we assume for clay particles a mean diameter of 0.0002 mm., and a structure similar to A in Fig. 2, p. 59, it is easy to show that no molecule in the space between the spheres can be further than about $\frac{1}{5}$ of the diameter of a sphere or 0.00004 mm. from one or other surface, while the range of molecular forces as calculated by Quincke extends to about 0.00005 mm. from the surface.

Surface Tension and Capillarity.

The existence of attraction between the molecules causes the free surface of any liquid to become a sort of stretched elastic film, in tension itself, and exerting a certain pressure inwards when free. The molecules within the liquid are equally attracted in all directions by the surrounding molecules, and are therefore in equilibrium; the molecules on the surface, having nothing on one side, are only attracted inwards, and so, as a whole, exert a pressure on the liquid similar to that which would be caused by a stretched elastic skin over the liquid.

The existence of this force of "surface tension," as it is called, may be demonstrated by many simple experiments, *e.g.*, by the familiar fact that a clean needle will float when placed carefully on the surface of water; or, by the fact that a portion of any liquid, so small that the force of gravity on it is not large compared to the molecular forces, immediately assumes the spherical shape. Of all figures, a sphere has the smallest surface in proportion to its contents, *i.e.*, the stretched film on

the surface of a drop of liquid shrinks as far as it can until the liquid is packed into the smallest possible compass, which must be the form of a sphere.

When a liquid and a solid are in contact, the form of the surface and the resulting pressure or tension depend on whether the liquid "wets" the solid or not. For




FIG. 3.—Capillary Rise and Depression of Liquids in Glass Tubes.

example, if a series of very fine or "capillary" glass tubes are dipped into water and mercury respectively, the water will rise up the tubes in inverse proportion to their diameters, the mercury, which does not wet the glass, will be correspondingly depressed.

The water surfaces *a*, *b*, *c* (Fig. 3), are convex to the water, and become more convex the narrower the tube is; the pressure below the convex surface must

be less than atmospheric, or the water would not stand higher within than without the tube; further, the pressure beneath *a*, the most convex and therefore most stretched surface film, is lower than the pressure beneath *b*, and still lower than that beneath *c*. *Per contra*, the mercury surfaces are convex outwards, and exert pressure on the liquid beneath, depressing it below the general surface of the liquid in proportion to the degree of convexity. These instances will help us to realise that the surface of a liquid may exert either a pull or a pressure on the liquid within, according to the curvature of the surface, and the greater the curvature the greater will be the force exerted. It is this tension of the surface film which causes movements of water in soil, other than those due to gravity; for example, if a flowerpot stands in a shallow dish of water the whole of the soil within the pot is kept moist; or if water is poured on to dry soil it is seen to work outwards through the soil, the water advancing from particle to particle as it wets them, just in the same manner as it rises up the capillary tubes. When a soil is saturated the whole pore space is filled with water; if this soil be allowed to drain, some of the water is pulled away by gravity, but much remains clinging round the particles in the stretched film condition, the tension in the film balancing the pull due to gravity. Perhaps the best illustration of the state of affairs in a wet but drained soil may be obtained by linking a series of toy balls together, as shown in the photograph (Fig. 4), and then dipping the whole into oil. When the oil has ceased to drip it will be seen that every ball is covered by a thin film of oil, and that between the balls there is a layer of oil much thicker in the lower than in the upper layers. The whole surface film is equally stretched, but the stretching in the upper



FIG. 4.—Photograph illustrating Liquid Film round Soil Particles.



layers is largely due to the pull from the oil below, while in the lowest layer of all the whole tension exerted by the stretched film is devoted to holding its own thick film of oil. If oil be taken away at any point, the curvature of the film, and therefore the tension of the surface in that region, is increased: a readjustment then takes place till the stretched film regains the same tension everywhere, which is effected by a motion of the oil to the place where the tension has been increased. If the withdrawal of the oil be continued, the film round the balls becomes thinner and thinner; the more it is stretched, the more closely it clings to the surface, so that the removal becomes progressively more difficult; at last the film becomes so much stretched that it ruptures and reunites again over a smaller surface, hence with a diminished tension. The rupture naturally takes place where the film is thinnest, on the top layer of balls, which become more or less "dry," while the lower balls are still surrounded by their film.

Just in a similar way water will always move in a soil from a wet to a dryer place, till the film surrounding the particles is equally stretched throughout.

For example, if A, B, C (Fig. 5) represent three soil particles, of which A and B are surrounded by a thin, and C by a thicker, film of water: when the spheres are in contact the water will fill up part of the angle between the spheres, as shown in the diagram. But the water surface at *a* is more curved than at *b*, *i.e.*, it corresponds to the surface at *a* in the fine capillary tube (Fig. 3) as compared with the surface at *b* in the wider tube. But the diminution of pressure caused by *a* is greater than that caused by *b*, as shown by the greater height to which water is raised in the tube; hence in the same way the pressure inside the liquid

at *a* (Fig. 5) will be lower than that at *b*, and there will be a flow of water from *b* to *a*, until the curvatures and corresponding surface tensions are equalised.

In a wet soil, then, surface tension is a force tending on the one hand to retain a certain amount of water round the particles, and on the other to equalise the distribution of water, by causing movement towards any point where the surface tension has been increased. For example, if the water in a soil is in equilibrium and evaporation begins at the surface, the film there is made





FIG. 5.—Diagram illustrating Liquid Film round Soil Particles.

thinner, and the curvature increased in the angles between the soil particles: hence the pull exerted by the film is increased, and water is lifted from below against gravity. *Per contra*, if rain fall on such a soil the films round the upper particles are thickened, their tension is lowered, and the pull of the film below now acts with gravity in drawing the water down into the soil.

Percolation.

The state of affairs illustrated by the model of balls dipped in oil is seen in the case of a soil which has been thoroughly saturated so that all the pore space is occupied by water, and then allowed to drain until the remaining water is held in the soil by surface tension only.






FIG. 6.—Water Content of Columns of wetted but thoroughly drained Sand and Soil.

In the upper layers the film will be stretched to the utmost, or even broken by the pull of the water below; in the lower layers the film will be wholly engaged in holding the water immediately in contact with the particles of the layer: these layers may be saturated, while the upper layers hold an amount dependent on their distance from the saturated zone, and on the extent of surface exposed by the particles.


The accompanying diagram (Fig. 6) expresses the results of an experiment of King's, where columns of sand and soil, 8 feet and 7 feet long respectively, were saturated and then allowed to drain till they parted with no further water, which required a period of sixty days in the case of the soil columns, and of more than two years for the sand. The tubes were then cut up, and the proportion of water in the sand or soil in successive 3-inch lengths of the tubes was determined.

It will be seen that the sands retain very little water by surface tension in the upper layers, whereas the clay loam, with the enormous area its particles expose, holds practically the same proportion throughout.

If we also consider the following table, showing the time taken by the same sands and soils to part with their water, the difference of the texture of the soils will be even more evident.

	INCHES OF WATER LOST IN				
	30 min.	31 to 60 min.	24 hrs. (?)	2 to 11 days.	12 to 21 days.
No. 20 Sand .	10.25	4.68
" 60 " .	5.67	4.52
" 100 " .	1.21	.84
Sandy Loam	2.64	5.07	.9
Clay Loam	1.96	2.11	.49

The downward movement of rain water through soils is known as "percolation," and is distinguished from "flow" by the fact that the water is supposed to have free surfaces, so that surface tension comes into play. It takes place under the action of gravity through the pore space proper, and also through the cracks, the worm tracks, the passages left by decayed roots, and other adventitious openings in the soil. The percolation proceeds until the zone is reached where the pore space is completely filled; this is known as the "water table," and is the level at which water stands in the wells. Above the water table the soil will be more or less in the state represented in the diagram showing sands and soils in which percolation has ceased; though there will be most probably a more irregular distribution, with zones which contain an excess of water travelling downwards with greater or less rapidity according to the texture of the soil. It is these temporarily saturated zones which cause the ordinary tile drains to run, although situated many feet above the permanent water table. A soil in which percolation has ceased, though it may still contain much water, will not part with it to a drain; the water cannot break away from the elastic film and run away down the drain, unless it be present in such an excess that the surface tension is insufficient to hold it against gravity. But in a clay soil, percolation is so slow that the upper few feet of soil may become saturated by the winter rains and remain so for months, if percolation has to proceed all the way down to the water table; by the introduction of drains, the percolating column is shortened to the distance between the surface and the drain. In a coarse-grained sandy soil percolation is very rapid, the land dries quickly after rain, and retains a minimum of water by surface






FIG. 7.—Diagram showing Rainfall and Percolation at Rothamsted, Monthly Means, 1870-90.

tension; in fine-grained soils, which are, however, not too fine for percolation, the excess of rain will be removed rapidly enough to keep the soil below the saturated condition, yet enough water may be retained to supply the needs of the crop between the intervals of rain.

While the flow of water from a field-drain may be taken as a rough measure of the amount of percolation going on at any given time for that soil, the movement may be followed more closely by means of a lysimeter or drain-gauge. As a rule, the records of these instruments are vitiated by the disturbance undergone by the soil in filling them; but the drain-gauges at Rothamsted were constructed by building cemented walls round blocks of earth *in situ*, and then gradually introducing a perforated iron plate below to carry the soil. The accompanying diagram (Fig. 7) shows the mean monthly records of rainfall and percolation through a depth of 20 inches and 60 inches respectively, over a period of twenty years.

It will be seen that of the total rainfall a little less than one half percolates through 20 inches of the Rothamsted soil, and about 45 per cent. through 60 inches; it should be remembered, however, that the surface of these gauges is kept firm, but free from weed or any growth. When the ground has become dried to any depth in the summer, percolation may be much hindered by the air within the soil and the want of a continuous film of wetted surfaces to lead the water down by surface tension. The top layer of soil becomes thoroughly wetted and will not allow the air below to escape; only after some time are local displacements of the air set up, which enable the water above to make connection with the wetted subsoil below, so that percolation can begin. For this reason summer rains

falling in a season of drought are often noticed to be of little benefit to the crop, because they are retained near the surface until wholly evaporated, instead of increasing the stock of moisture at the lower levels where the roots of the plant are then operative in obtaining water.

Minimum Capacity of Soil for Water.

The amount of water retained in a soil by surface tension alone, when percolation has removed as much as possible, is rather an important factor to determine, as upon it depends to some extent the power of the soil to resist drought by retaining water for the crop between intervals of rain. If short columns of sand and soil which have been saturated and then allowed to drain away into a state of equilibrium are considered, it is clear that very different proportions of water are retained by the various soils. Suppose, however, the column be of such a length that at some level the upper film of water cannot be further stretched, but the particles cease to be wet; the layer immediately below this dry soil contains the minimum amount of water consistent with a continuous film at all.* Soil in this condition may be regarded as at the minimum of saturation; it will part with no more water by drainage, and will become drier only by evaporation. In order to obtain such a sample of soil for determination of its water content, much trouble would be necessary, and a long time must elapse before equilibrium could be obtained in the long tube filled with wet soil. Practically, however, the same result can be reached with the apparatus previously described for estimating the maximum capacity of the soil for water, by constantly bringing the thin layer of soil

there used into contact with dry soil, until the previously saturated soil no longer parts with water to the new soil.

After the determination of maximum water capacity, as previously described (p. 64), a little more fine earth, which has been standing for some time over water in a closed space so that it has acquired all the hygroscopic moisture it can, is shaken lightly over the surface of the wet soil in the box to the depth of $\frac{1}{4}$ inch or so. It rapidly becomes wet, as will be evident by a change in colour, whereupon it is struck off by drawing a fine wire tightly stretched across the top of the box and shaking the loosened layer off. More fine earth is then poured on and struck off as before when wetted, the operation being repeated again and again, until a thin dry layer remains on the surface for half-an-hour or so without showing by change of colour any absorption of water. During this wait the box should be in a closed chamber over water. With fine-grained clays and loams the process does not take long, with a coarse sand the water moves slowly into the dry layer, and it is difficult to hit off the exact end point, when the soil particles are still surrounded by water but the surface tension is too great to allow this water to pass into dry soil. Finally, the box and its contents are weighed, dried in the oven, and re-weighed. The second weighing when dry is necessary, because the box will be found to hold more dry soil than was originally filled into it; a certain amount of consolidation has taken place through the addition of the dry earth and the subsequent striking off when wet. The numbers in the columns headed minimum in the table on p. 66 were obtained in this way: they show that though the maximum capacity for water, or pore space, may not vary very greatly for different soils, there is a much wider and

more important divergence between the amounts of water they will retain by surface tension alone, this last being the important factor in judging of the power of the soil to retain a reserve of moisture for crops.

Variations in Surface Tension.

The surface tension of water is very high, but it is easily raised or lowered by the presence of small amounts of material in solution. The effect of altering the surface tension of a film at any point is to cause motion, as is seen in the well-known experiment of covering a plate with a thin film of coloured water and dropping a little alcohol into the middle of the film. The alcohol immediately weakens the surface tension of the film in the middle to such an extent that all the liquid runs to the outer edge and leaves the plate bare in the middle. Most of the salts which are used as artificial manures and are soluble in water increase the surface tension of the soil water, hence an application of salt or nitrate of soda may, by increasing the tension of the surface film, lift more water from the subsoil and maintain the top layer of soil in a moister condition. *Per contra*, solutions of organic matter, particularly of the many organic substances used as manure which have a little oil in them, extracts of dung, etc., have a surface tension below that of water. To this fact may be attributed the "burning" of soils which is sometimes seen when organic manures are applied late in the season and dry hot weather succeeds; the soil water at the top in contact with the manure has a lower surface tension and consequently less lifting power for the subsoil water; hence any shallow rooted crop is deprived of some of the subsoil water which would have otherwise been lifted to it. A rise of temperature diminishes the

surface tension of water, and therefore lessens the lifting power of the film; as it also lessens the viscosity of water, percolation will often recommence on a rise of temperature from soil that had apparently ceased to yield any more drainage. This effect may sometimes be seen in variations in the flow of land drains or in the level of water in shallow wells. The following table shows the comparative surface tension of water and various solutions.

Nature of Solution.	Density.	Surface Tension.
		Dynes per sq. cm.
Water	1.0	7.532
Common Salt	1.1	7.911
Kainit	1.1	7.9
Nitrate of Soda	1.1	7.73
Dung	1.0013	7.464
Superphosphate	1.0104	7.414
Soil Extract	1.0	7.244
Garden Soil Extract	1.0	7.089

Cohesion caused by Surface Tension.

In certain cases the stretched film surrounding soil particles will give them an apparent cohesion by enclosing them and drawing them together. A handful of wet sand can be moulded into shape, but falls in pieces as soon as it is dry: just as in a camel hair pencil the bristles, which stand apart when dry or wholly immersed in water, are drawn together to a point if the brush be dipped in water and withdrawn. Or again, a flat sandy beach from which a smooth sea is just receding will often show above tide-mark one stretch of sand quite dry and loose, in which the feet sink deeply, and another very soft stretch just left by the tide where the sand grains are completely sur-

rounded by water. Between the two is a stretch of sand of the same character, but firm to walk upon; this is partly wet, and there is enough water to form a film round the grains and hold them in position with a certain amount of force. That this sand is really just as loosely arranged as the softer tracts that are either wetter or drier, may be seen by the fact that it will easily pack together under repeated gentle pressure with the foot. The shrinkage of soils, especially of clays, as they dry, may be attributed to the surface tension of the films surrounding the groups of soil particles; as the water content is lessened the films exert more force in their effort to contract, and drag some of the particles closer together, especially the very small particles whose weight is trivial compared to the forces exerted by the film. Clay shrinks more than other soils because of the greater number of particles, their small size, and the higher proportion of pore space into which motion can take place. The tenacity of wet clay is due to the number of water films that have to be ruptured, the vastly greater cohesion of dry clay probably to the fact that many of the particles have been dragged within the range of one another's molecular forces. There is a stage in the drying of clay when it will fall to pieces when worked; probably this represents the stage analogous to the partly wet sand, when cohesion is due to the surface films. The clay is neither so wet that the particles just slip over one another when pressure is applied—the pasty condition; nor have they been drawn so closely together as to cohere without the aid of any water. It is not quite intelligible why a piece of dried clay becomes soft and swells again when wetted, nor why the particles should once more move apart.

Hygroscopic Moisture.

If the withdrawal of water from a soil by evaporation be continued, a point is at last reached when the soil becomes air-dry: it still retains some water, which will vary in amount with the degree of humidity of the atmosphere and the temperature. This last film of water is held very closely and in a somewhat different manner from the ordinary film held by surface tension, though the two shade off into one another. For example, the film of hygroscopic moisture would be produced by condensation alone, if perfectly dry soil were placed in an atmosphere containing water vapour: the surface of materials like glass, sand, etc., has sufficient attraction for water to condense it from a state of vapour. The amount of hygroscopic water retained by different types of soil when air-dried and then allowed to stand in a saturated atmosphere at ordinary temperature, is given in the table below; it will be seen to be more or less proportional to the surface possessed by the soil particles, clay and humus retaining the most.

It is questionable whether this hygroscopic moisture can be of any service to plants: Sachs has shown by experiments in pots that tobacco plants will begin to wilt before the soil has parted with all its moisture. When wilting began with a sandy soil the sand in the pot still contained 1.5 per cent. of water, with a clay soil 8 per cent. of water, with a mixture of sand and humus there was as much as 12.3 per cent. of water retained by the soil. Heinrich has further shown that wilting begins before the water content of the soil has been reduced to the hygroscopic water limit, as the following figures demonstrate—

	WATER PER 100 OF DRY SOIL.	
	When Plants Wilt.	Hygroscopic Water.
Coarse Sand . . .	1.5	1.15
Sandy Garden Soil . .	4.6	3
Fine Sand, with Humus .	6.2	3.98
Sandy Loam . . .	7.8	5.74
Chalky Loam . . .	9.8	5.2
Peat . . .	49.7	42.3

This is easily intelligible in view of the fact that the root hairs cannot be in contact with all the soil particles, nor can the water move from particle to particle when it has been reduced to so low a proportion. King has made some observations of the amount of water still present in soils in the field which had become so dry that growth was at a standstill and the plants were wilting.

Depth.	Nature of Soil.	Per cent. of Water under Clover.	Under Maize.
0" to 6"	Clay Loam	8.4	7
6" " 12"	"	8.5	7.8
12" " 18"	Reddish Clay	12.4	11.6
18" " 24"	"	13.3	12
24" " 30"	Sandy Clay	13.5	10.8
40" " 43"	Sand	9.5	4.2

Under these conditions all the soils were about equally dry, so far as any power to part with their water went; if the estimates made previously of the area of surface of the particles constituting various kinds of soil be combined with these percentages to calculate the thickness of film of the water on that surface, it will be found that on all soils the film possesses approximately the same thickness, about 0.00003 inch.

Because of the quantity of water which some soils will retain rather than give up to the plant, it is possible that such soils may have less available water for the plant than a much coarser grained soil which starts with a lower initial amount of water. For example, the clay and sand in the table above contain when saturated about 26 per cent. and 18 per cent. of water respectively; as the crop can reduce this to 12 per cent. in one case, and 4.2 per cent. in the other, both sand and clay yield about the same amount of water to the crop.

Though it is doubtful if the hygroscopic moisture gathered by the surface soil in the cooler and damper periods of the night, can be passed on to the subsoil and given up to the roots, yet by its evaporation the next day it may help to keep the temperature of the soil down, and so indirectly diminish the loss of water to the soil. Of course in certain conditions of air and soil temperature there is condensation upon the soil of visible water which can be available to the crops; for example, in some months drain-gauges yield more water than the rainfall, though a certain amount of loss by evaporation must also have taken place. This usually happens in the early spring, and can be set down to the condensation of dews by the thoroughly chilled ground from a warm and moist atmosphere. Warrington has suggested that the persistent wetness of the soil in February must be attributed to this cause. In a coarse-grained soil mostly filled with air, the cooling of the surface that comes by radiation at night may result in an upward distillation of water from the wetter and warmer subsoil. Hilgard has suggested this explanation to account for the capacity of some Californian soils to maintain a crop during a rainless winter, when the soil itself shows only 3 per cent. or so of water.

CHAPTER IV

TILLAGE AND THE MOVEMENTS OF SOIL WATER

Water required for the Growth of Crops—The Effect of Drainage
—Effects of Autumn and Spring Cultivation, Hoeing and
Mulching, Rolling, upon the Water Content of the Soil—
The Drying Effect of Crops—Bare Fallows.

THE amount of water transpired by various plants during their growth has been investigated by Lawes and Gilbert at Rothamsted, by Hellriegel in Germany, and Wollny in Munich, and by King in America. The general principle upon which these observers have worked, has been to grow the plants in pots and measure the amount of water consumed during growth, care being taken to eliminate or allow for losses by evaporation from the bare ground, and also to render the conditions of the plant's life as similar to those of the open field as possible. Finally, the plant is washed free of soil, dried, and weighed, so that a ratio is obtained between the dry matter produced, and the water consumed during growth.

Some of the numbers obtained are given in the following table: it will be seen that the same plant gives very different results with the different observers.

	Lawes and Gilbert.	Hellriegel.	Wollny.	King.
Wheat . . .	225	359
Barley . . .	262	310	393	774
Oats	402	557	665
Red Clover . .	249	330	453	...
Peas . . .	235	292	477	447

per 1 dry matter

The divergencies in these results are intelligible, if we consider that the “transpiration” process by which the water is lost, and the “assimilation” process by which the plant gets heavier, have no necessary connection, though both become active under the same stimuli of light and warmth. Some leaves transpire rapidly as a means of maintaining a low temperature whilst absorbing large amounts of radiant energy from the sun; other plants which have to resist drought reduce the transpiration by a thickened cuticle, or by a more concentrated cell sap. Dr H. Brown has shown that of the radiant energy falling upon a sunflower leaf on a bright August noonday, about 95 per cent. was consumed in evaporating the transpiration water; of the energy falling upon the same leaf in bright diffuse daylight, only 28 per cent. was used up in evaporation. Comparing in these two cases the water transpired with the carbohydrate produced (and this will be about $\frac{9}{10}$ of the total dry matter) we find in the sunlight the ratio was 347.1, in the diffuse daylight 234.1. Further investigations are desirable; but, taking the whole group of observations, we shall be justified in assuming that our ordinary field crops transpire about 300 lbs. of water for each lb. of dry matter produced. It now remains to translate this approximate figure into tons of water per acre required to grow the ordinary crops. The following table shows the weight at harvest of a

fair yield of the crop in question, the percentage of water contained in the crop, the weight of dry matter produced per acre, then the water transpired as deduced from the dry matter produced, and in the last column this same amount of transpired water recalculated as inches of rain.

Crop.	Weight at Harvest.	Per cent. of Water.	Weight of Dry Matter at Harvest.	Calculated Water transpired during Growth.	
	Tons per acre.		Tons per acre.	Tons per acre.	Inches of Rain.
Wheat . . .	2.5	18	2.05	615	6.09
Barley . . .	2	17	1.66	498	4.93
Oats . . .	2.5	16	2.10	630	6.24
Meadow Hay .	1.5	16	1.26	378	3.74
Clover Hay .	2.0	16	1.68	504	4.99
Swedes . . .	17	88	2.04	612	6.06
Mangolds . .	30	88	3.60	1080	10.69
Potatoes . .	7.5	75	1.87	561	5.55
Beans . . .	2	17	1.66	498	4.94

It will be seen that in all cases the amount of water transpired by the crop is a notable fraction of the total annual rainfall, particularly so in the case of a root crop like mangolds, which in the south and east of England will often require a full half of the total rain falling within the year. As much of the rainfall runs straight off the surface into the ditches, and another portion is lost to the land by percolation into the springs, as again a considerable fraction is evaporated at certain seasons from the bare surface of the soil, it is evident that the water supply, even in our humid climate, is far from sufficient for the maximum of production, and may easily fall below that which is required for an average crop. Indeed, we may take it as a truism that the crop obtained is more often determined by the water available than by lack of the other essentials of

growth—light and heat, manure, etc. Of this we can have no better proof than the enormous crops grown by irrigation on sewage farms. Where the conditions are favourable, and the farm is situated on a free draining sandy or gravelly soil, so that the water can be often renewed and drained away to keep the soil supplied with air as well as water, the production of grass, cabbages, and other green crops is multiplied five or even tenfold by the unlimited supply of water. Speaking generally, over a great part of England, where the annual rainfall is from 35 to 25 inches, a large proportion of which falls in the non-growing season, it is necessary to husband the water supply, and it will be found that one at least of the objects of many of our usual tillage operations is the conservation of the moisture in the ground for the service of the crop. From this point of view, the various operations dealing with the land can now be considered, such as drainage, ploughing, hoeing, rolling, and other cultivations.

The Effect of Drainage.

Drainage is usually regarded as a means of freeing the land from an excess of water, but it also has an important effect in rendering a higher proportion of the annual rainfall available for the crop, so that drained land will suffer less from drought than the same land in an undrained condition.

Land may require drainage for various reasons: it may possess a naturally pervious subsoil, and yet be water-logged owing to its situation, or the subsoil may be so close in texture that percolation is reduced to a minimum and the surface soil remains for long periods almost saturated with water, especially if the slope is gentle and water lies after rain until very large amounts

soak in. The flat meadows adjoining a river are often water-logged because their surface is little above the water in the river and the general water table in the adjoining soil. In these cases tile drains are of no value because of the want of fall; open cuts and ditches draw off the water best, and by exposing some of the subsoil water both to aeration and evaporation, lead to the improvement of the land. Another cause of swampy water-logged land is the rising to the surface of a spring or a line of soakage, such as is always formed at the junction of a clay or other stiff soil with an overlying pervious formation, "when the sand feeds the clay," as the old rhyme runs. Such wet spots can be drained by tiles or by an open ditch cutting the springs or the line of soakage. Land lying on an impervious subsoil at the foot of a slope is often very wet because the water which has accumulated in the hill and soaked downwards is forced to the surface by the hydraulic pressure of the water above; such seepage water rising to the surface from the subsoil is characteristic of many valley soils, and can best be dealt with by a system of tile drains. But tile drains are most generally employed and are of greatest value in dealing with stiff impervious subsoils, which cannot get rid of the rain falling upon them; indeed, one of the prime improvements effected in English agriculture was the drainage of something like 3,000,000 acres of heavy land between the years 1830-70. A great portion was unfortunately of no avail, because at first there was a tendency to set the drains too deep, at 4 feet instead of the 2 to 3 feet which have been found to answer best. The benefits conferred by drainage depend upon the lowering of the permanent water table to the depth at which the drains are laid, so that instead of constantly stagnant water a movement of both

water and air is established in the soil above the drain. In the first place, the introduction of the air which follows the water drawn off by the drains, brings the whole depth of soil into activity, whereas previously only the portion not water-logged was available. Plant roots cannot grow without the oxygen of the air, hence in a water-logged soil the roots are confined to the surface layer only ; after drainage the roots can penetrate as far as the air extends. At the same time, all the fundamental chemical and biological processes of the soil, such as nitrification and weathering, are brought into action by the introduction of the oxygen upon which they depend. Later it will be seen that a water-logged soil results in the loss of nitrogen to the land when such manures as nitrate of soda are applied to it. It is the extended root range of the crop resulting from the introduction of air by drainage which enables the drained land to resist a drought better than before. In an undrained soil the roots are confined to a shallow layer, which they soon deprive of all moisture ; further supplies of water from the saturated soil move upwards very slowly in a clay soil, so that the plant suffers greatly. In a drained soil, on the contrary, the roots traverse the whole 3 feet or so into which air has been admitted ; this mass of soil, even after it has given up by percolation all the water it can, will still hold much more than is contained in the shallow layer alone traversed by roots before drainage. Following upon drainage, a slow improvement in the texture of clay soil is always manifest : by the drawing of air into the soil, by the consequent evaporation and drying, a certain amount of shrinkage and a clotting of the fine clay particles result, which is never entirely undone when they are wetted again. Roots, which afterwards decay and leave holes,

and deep worm tracks, are all brought into the soil by its aeration, and result in more rapid percolation. Again, the washing through the soil of soluble salts derived from the surface, especially the bicarbonate of lime which is so characteristic a constituent of drainage water, also induces flocculation of the fine clay particles. Lastly, there is a steady removal by the drains of the finest clay stuff, for whenever tile drains are running freely the water will be found slightly turbid with clay matter. All these causes contribute to establish a better texture in the drained soil, beginning at the tiles and spreading slowly outwards. The other result of drainage which may be noted here is the greatly increased warmth and earliness of a drained soil; the high specific heat of water, and the cooling produced by evaporation when the water table is near the surface, combine to hinder a water-logged soil from warming up under the sun's heat in the spring, so that undrained land is notoriously cold and late.

Effect of Autumn Cultivation upon the Water Content of the Soil.

In regions where the annual rainfall is not very high and occurs chiefly during the early winter months, it is important to get as much of it as possible into the soil for the use of the subsequent crop. Breaking up the stubbles after harvest is an important factor in catching the winter rain; all land which is to lie idle through the winter, previous to the sowing of roots or spring corn should be early turned over with the plough and left rough through the rainy season. On the old stubble which has been made solid by the weather and all the trampling during harvest, the rain lies for some time and evaporates, and if the land be at all on a slope the water shoots off into the ditches. But the broken surface of a

ploughed field both hinders the flow of the water and affords it many openings by which to sink in; at the same time the increase of pore space in the loose ploughed layer enables this portion to absorb more water before percolation begins. King has observed in May a difference of 2.3 per cent. of water in the top 3 feet of soil between land ploughed in the autumn and the adjoining land not ploughed; the gain in this case due to the ploughing was 110 tons of water per acre, or rather more than 1 inch of rain.

The following table shows the effect of ploughing up a stubble in autumn on a thin chalky loam at Wye, Kent, where the soil is only about 2 feet deep. The samples were taken on 3rd March 1902; there had been but little rainfall except in the previous December. The figures show mean percentages of water in the wet soil exclusive of stones.

	Land Ploughed in Autumn.	Adjoining Land not Ploughed.
1st foot . .	16.45	16
2nd foot . .	15.8	14.6

Of course the autumn ploughing has many other beneficial effects in addition to the above-mentioned gain of water; the ploughed soil gets alternately frozen and thawed, wetted and dried, with the result that on the stiff lands the puddling effects of trampling, etc., are obliterated, and the soil acquires a loose, open texture, out of which a seed bed can be made. Again, the additional surface which is exposed to the action of frost and rain causes increased weathering, and some of the dormant mineral plant food is brought into a more available condition.

Spring Cultivation.

In such climates as prevail in parts of England, where it is necessary to retain as much of the winter's rainfall in the land as possible, and where spells of drying weather are apt to set in with the spring, it is desirable to cross plough or otherwise move any land that is destined for a summer crop at as early a date as it will bear cultivation. This spring working is necessary for two reasons: to obtain a mulch, or layer of loose soil, which will conserve moisture in the subsoil during the dry periods to follow, and to give the surface soil an opportunity of drying gradually into a condition that will yield a good tilth. The land, even though ploughed in the autumn, will have been consolidated again to a considerable degree by the beating rains of winter. In this closely-packed material capillary water can move freely, and as the surface layer dries under the action of the sun and wind fresh supplies of water are lifted from the subsoil by surface tension, with the result that there is a steady and continuous drain of subsoil water through its connection with the exposed and rapidly evaporating surface. But if the top layer of soil is broken up and left loose upon the land by the cultivator, there is no longer a continuous film joining the exposed surface and the subsoil water; surface tension can only lift water as far as the film is unbroken, *i.e.*, as far as the unstirred soil extends, and this layer is protected from evaporation by the loose soil above. Regarding it from another point of view—in the undisturbed land there exist fine passages and capillary spaces extending from the surface down to the subsoil; up these passages water will rise as long as it is withdrawn by evaporation at the top; in consequence, the surface soil is not allowed to dry, being fed with

subsoil water which is constantly withdrawn from below. But when the land is cultivated the capillary channels are broken, water cannot rise into the loose layer of surface soil, which in the main is separated from the firm soil below by large spaces across which water cannot rise; hence the surface soil can become dry, because it is cut off from the subsoil water, which in its turn is preserved for use later. The drying of the surface soil which ensues, through its severance from the water-yielding subsoil, is of the greatest possible importance in obtaining a tilth. At a certain stage the soil can be dragged and will fall in pieces, but if it be not detached from the subsoil it will either remain persistently wet, so that it cannot be harrowed down, or if it be forced to dry under the action of wind and sun, it will set very hard and "steely," should it contain any admixture of clay. The sudden forced drying of strong land always produces hard and intractable clods, which may defy all the efforts of the cultivator during the rest of the season, unless a fortunate succession of weather enable him to begin to make his tilth over again.

It may be thought that the amount of water lifted by surface tension cannot be so large as to result in any serious losses to the subsoil store, but in soils of suitable texture enough can certainly be raised to keep the crop alive during periods of drought. In some of King's experiments with a cylinder full of very fine sand, he found that the evaporating surface lost daily an amount of water equal to 0.46 inch if the permanent water level were 1 foot below, 0.405 if the water had to be lifted 2 feet, and 0.18 inch if the water had to rise 4 feet to the evaporating surface. When the sand was replaced by a clay loam, the lift of water to the surface was somewhat less, but in all

cases the amounts were probably less than would be realised under field conditions, because the evaporation was not enough to dry the surface, and was further checked by the formation of a saline crust on the surface. Working in the field, King obtained a daily loss at the evaporating surface of 1.3 lb. per square foot, or 0.19 inch of water, the water table being from 4 to 5 feet below the surface.

The relative powers of different soils to lift water by capillarity alone is well seen during any long summer drought, such as prevailed in the south of England during 1899 and 1900. In the Thames valley, fields of swedes grew till the roots were one or two inches in diameter, and then died outright, although the water table was not more than 16 or 20 feet below; yet the coarse-grained gravel of which the subsoil was composed could not lift the water in any appreciable quantity to the surface. In the same seasons the crops upon the chalk hills were quietly growing; though the water table was as much as 200 feet below the surface there was still a steady capillary rise of water through the fine-grained chalk. In a drought it is always the gravels and coarse sands which suffer first, and this not because they start with less water, for we have already seen that what they absorb they can give up almost wholly to the plant, whereas a clay, which absorbs much more, can only hand over about the same proportion to the plant as the sand did, so much being held as hygroscopic moisture. The plant suffers because the small surface of the soil particles gives the coarse-grained sand or gravel a very limited power of lifting the subsoil water to the roots of the plant. Should a drought continue, the clay soils begin to suffer next, for though they start with large supplies of water and have an extensive surface of soil particles, yet water can be moved so slowly

through the very fine pore spaces that the upward lift cannot keep pace with the loss by transpiration and evaporation. The soils which are least affected by drought are the deep loamy sands of very uniform texture, fine grained enough to possess a considerable lifting surface, and yet not too fine to interfere with the free movement of soil water. The western soils which the American writers describe as capable of growing wheat with a winter rainfall of 10 to 12 inches and an unbroken summer drought of three months' duration, are deep, fine-grained, and uniform, with practically no particles of the clay order of magnitude to check the upward lift by capillarity.

The following table illustrates how the subsoil acts as a regulator to the amount of water contained in the surface layer, absorbing the water which descends by percolation during rainy periods, and giving it up again by capillarity to the surface soil during periods of drought. The first line shows the rainfall during the periods indicated, the second line the amount of evaporation during the same period, while the third line shows the changes in the water content of the top foot of soil. As this change is not represented by the difference between the rainfall and the evaporation, it is clear that water must have been in some cases passed down to the subsoil, in others lifted from it, in quantities shown by the last set of figures.

Water in inches.	30/iv. to 30/v.	30/v. to 9/vii.	9/vii. to 7/ix.	7/ix. to 27/x.
Rainfall	0.18	4.53	3.47	5.65
Evaporation	3.45	2.96	5.71	1.83
Gain or Loss of Water in top foot	- 1.0	+ 1.4	- 0.24	+ 0.61
Water furnished by (-), or passed on to (+) Subsoil	- 2.27	+ 0.17	- 2.0	+ 3.21

During the first period, the month of May, a dry spell prevailed, only 0.18 inch of rain fell, while the evaporation amounted to 3.45 inches; despite this loss the top foot of soil only contains 1 inch of water less than at the beginning, so that the rest of the excess of evaporation over rainfall must have come from the subsoil, which had in fact to furnish 2.27 inches. In the second period more water fell as rain than was evaporated; the surface soil gained 1.4 inch, which did not account for all the excess of rain over evaporation, a further .17 inch must have descended into the subsoil.

The following figures, obtained by King, illustrate how a spring ploughing preserves the soil moisture during a period of dry weather, by establishing a loose protecting layer over the water bearing subsoil. The upper line shows the water content of the top 4 feet of a certain piece of land on 29th April, on which date part of it was ploughed and part left untouched. On 6th May, no rain having fallen, the soil was sampled again, both on the ploughed and the unploughed piece, with the results set out in the lower figures:—

Lbs. of Water in each successive cubic foot.	1st.	2nd.	3rd.	4th.
Land on 29th April	14.1	20.1	18	16.6
Land on 6th May, ploughed 29th April .	13.9	20.7	18.3	16
Land on 6th May, not ploughed . . .	10.6	18	17.3	13.9

It is seen that the ploughed land practically lost no water during the week ending 6th May, whereas during the same period the land not ploughed lost 9.1 lbs. per square foot of surface, a quantity equivalent to $1\frac{3}{4}$ inch of rain.

A similar trial made on a light loam at Wye during a dry period in the spring of 1902, gave the following percentages of water in the wet soil.

	Land Ploughed Autumn and Spring.	Ploughed Autumn only.
1st foot . .	16.7	15.9
2nd foot . .	15.4	13.9

There can be little doubt that the earlier land which is intended for spring corn, or particularly for roots, can be moved in the spring, the more water will be saved for the use of the subsequent crop, and the easier will a good tilth be established. The chief danger lies on the very fine sandy soils which, when in a loose condition, are apt to run together under heavy rains and afterwards cake on drying.

Hoeing and Mulches.

The principles which have already been developed to explain the effect of an early spring ploughing in saving subsoil water, apply even more markedly to all the later spring and summer cultivations, hoeing and the like, which have for their object the maintenance of a loose tilth upon the surface. The loose soil becomes itself dry, but by reason of its discontinuity and coarse-grained condition, does not conduct the moisture from the firm subsoil to the surface exposed to sun and wind. Under these conditions the only loss will be of that water which evaporates from the moist soil into the air spaces of the loose upper layer and then diffuses into the atmosphere; the deeper the loose layer thus formed, the more effective will it be, and if it is destroyed by a fall of rain, which consolidates

the ground and establishes a continuous liquid film from the subsoil water right up to the surface, it should be renewed by a fresh cultivation as soon as the land will admit of working. It is often noticed that a casual shower during a dry period, or watering a garden unless the operation is done very thoroughly, may result in a greater drying up of the soil than ever, just because a film of water is created able to lift water from the subsoil up to the evaporating surface. The loose hoed ground practically forms a mulch, though the protecting material is the soil itself instead of straw or kindred substances.

Of course, the conservation of soil moisture is not the only good effect brought about by the surface cultivation during the summer: the aeration of the soil, the mechanical distribution of the nitrifying bacteria that is effected, the warmth of the surface layers due to their dryness, all combine to render nitrification active, and to bring into a form available for the plant the reserves of nitrogen in the humus of the soil. This point will be dealt with more at length later: for the time, it will be sufficient to remind the reader how a turnip crop with its frequent spring and summer cultivations is almost independent of any nitrogenous manure, though it removes something like 100 lbs. of nitrogen per acre: whereas a wheat crop removing less than half that quantity of nitrogen per acre often requires the application of a nitrogenous manure, because it is grown on undisturbed soil in the cooler season of the year.

The saving of soil moisture which can be effected by hoeing is illustrated by one of King's experiments, when, during a dry period, the soil on a piece of land kept cultivated to a depth of 3 inches was sampled from time to time down to a depth of 6 feet, samples being

taken simultaneously from an adjacent piece of land where the surface was kept smooth and firm. On the cultivated land there was a daily loss equivalent to $14\frac{1}{2}$ tons of water per acre, which was increased on the uncultivated land to 17.6 tons per acre; the difference during the 49 days over which the trial was spread, amounting to 1.7 inch of rain saved by the cultivation.

*The value of surface cultivation is well seen in other trials of King's, where the water content down to a depth of 4 feet was compared on two adjacent pieces of land, one stirred to the depth of 3 and the other to $1\frac{1}{2}$ inches only. The 3-inch soil mulch, taking the whole season through, preserved more soil moisture than the shallower cultivation, but by keeping the soil immediately below the mulch more moist, and therefore with a better developed water film, it also enabled this layer to lift more moisture from the 3 or 4 foot depth into the top or second foot, a position more available for the crop. Thus the average of three determinations of water content on 16th July gave the following results—

Per cent. of Water.	1st foot.	2nd foot.	3rd foot.	4th foot.
Soil cultivated, 3" deep .	12.3	18.6	16.8	14.6
„ $1\frac{1}{2}$ " deep .	11.2	17.6	17.8	16.2

On this occasion it is seen that the upper 2 feet of soil are being kept moister by their greater power of lifting water from the lower layers, which actually contain more water under the $1\frac{1}{2}$ -inch mulch than under the 3-inch mulch.

Although the gardener uses the hoe freely to establish soil mulches, he also employs dung, grass-clippings, and even straw to the same end, anything to break the

connection between the water-bearing subsoil and the exposed evaporating surface. Such mulches of loose organic material are even more effective in conserving soil moisture than a fine tilth, there is less tendency to form any continuity of water film between subsoil and mulch; moreover, the evaporation of the water they themselves contain helps to keep the temperature down. The great drawback to their employment is that they prevent the continual stirring of the ground which promotes aeration and nitrification.

Stones serve almost the same purpose as a mulch, especially when they are impermeable like flints and cover the surface at all thickly. They shield the land below from evaporation; indeed, on picking a flint off an arable field the ground below will generally be found cool and damp. The vineyards of the Rhine, etc., are generally set on steep slopes very thoroughly drained and exposed to the sun; it will be noticed that the utmost care is taken to keep the surface of the soil covered with the broken slaty rock.

Effect of Rolling.

Though it has been pointed out that maintaining a loose tilth on the surface is the most effective means possessed by the farmer of saving the soil water and minimising losses by evaporation, yet one of the fundamental acts of husbandry in the spring consists in rolling and otherwise consolidating the land. Particularly is this the case on the chalk and similar light soils; whenever a spell of dry weather prevails in the early part of the year the farmer will be observed rolling his seeds, or his spring corn, or his newly sown turnip land, as the case may be; he will even take a heavy cart wheel down between the drills when the roller will not give him pressure enough. The result of the

consolidation of the surface soil thus effected is to improve its power of lifting the soil water from below by capillarity, because the pore space is diminished and the wide intervals across which the water film cannot exist are largely closed up; just as the motion of water through surface tension almost ceases in a thoroughly loose soil, it is, *per contra*, increased when the particles are brought more closely together. Hence, on the rolled land there will be a greater lift to the evaporating surface and subsequent loss of water, but the farmer faces this loss in order to keep the upper few inches of soil supplied with moisture. Rolling is only done on land occupied by germinating seeds, young spring corn, or a young ley, where the roots, if any, are so close to the surface that the whole crop will perish if the top layer is allowed to dry. The effect of rolling is to increase the capillary lifting power of the top soil, so maintaining it in a moister condition, although the land as a whole is made dryer by the extra evaporation which must accompany the rise of subsoil water to the surface. It is a maxim in farming on the chalk, where there is always a store of subsoil water at some depth or other, and where also the surface soil is peculiarly liable to become open in texture through the action of worms and the rapid decay of dung, that the land will become moist if it can only be got "tight" enough. On any light cultivated land it is easy to notice how much moister the soil remains when it has been consolidated by a foot-mark; a gardener again, whose rich and deeply-worked soil is apt to get very open, always treads the ground as solid as possible in preparing a seed bed for onions and other small seeds. The following figures given by King as mean values from a number of measurements show how rolling dries the soil as a whole when samples are taken down to 2

feet or more, but maintains the surface soil, sampled only down to 18 inches, in a moister condition.

Depth of Sample.	PERCENTAGE OF WATER.	
	Rolled Ground.	Unrolled Ground.
Down to 18" . .	15.85	15.64
Down to 24" . .	19.49	19.85
Down to 36"-54" .	18.72	19.43

Since rolling dries the soil as a whole it is only desirable when shallow-rooted crops must be kept supplied with water at any cost; as soon as they get their roots down hoeing should begin to diminish the inevitable evaporation from the firm surface. Thus a tool like the old broadsharing plough, still used on the chalk, is particularly valuable in preparing a tilth for roots, for, while creating a loose surface tilth, it is consolidating the soil below and increasing its power of lifting water from the subsoil.

The Drying Effect of Crops.

Since a crop transpires about 300 lbs. of water for each pound of dry matter produced, any land which is carrying a heavy crop must contain much less water than the adjoining uncropped land, unless there has been such an excess of rainfall as to saturate the soil in either case. Any summer growing crop, however, especially one of roots, transpires so large a proportion of the customary rainfall during the period of growth that it must leave the soil much drier for its growth. As an example of this removal of water by the growing crop, the following figures obtained at Rothamsted during the very dry summer of 1870 may be quoted, showing as they do the water present in successive 9

inches of fallow and of adjoining land carrying a barley crop—

Percentages of Water in fine Soil, June 27-28, 1870.		
	Fallow.	Barley.
First 9" . . .	20.36	11.91
Second 9" . . .	29.53	19.32
Third 9" . . .	34.84	22.83
Fourth 9" . . .	34.32	25.09
Fifth 9" . . .	31.31	26.98
Sixth 9" . . .	33.55	26.38

The total difference between the cropped and uncropped land down to the depth of 54 inches, amounted to more than 900 tons of water per acre, or 9 inches of rain, which is quite half as much again as would be accounted for by the crop on the assumption that only two tons or so of dry matter had been grown at the date of sampling.

Another example of the withdrawal of water from the soil by the crop is seen in the proportions of water in the soil of certain of the permanent grass plots at Rothamsted, taken in July of the same year, 1870—

	PLOT 3.	PLOT 9.	PLOT 14.
	No Manure.	Mineral Manure + Ammonia Salts.	Mineral Manure + Nitrate of Soda.
Crop 1870 . . .	5½ cwt. of Hay.	29½	56½
Per cent. of Water.			
First 9" . . .	10.83	13.0	12.16
Second 9" . . .	13.34	10.18	11.80
Third 9" . . .	19.23	16.46	15.65
Fourth 9" . . .	22.71	18.96	16.30
Fifth 9" . . .	24.28	20.54	17.18
Sixth 9" . . .	25.07	21.34	18.06
Means . . .	19.24	16.75	15.19

Down to the depth of 54 inches the plot receiving minerals and ammonia salts contained 200 tons, and the plot receiving minerals and nitrate 325 tons, less water than the unmanured plot, quantities in this case somewhat less than would be indicated by the amount of dry matter produced.

There are two important cases in which the drying effect of vegetation needs to be taken into account, in the use of catch crops and in the planting of fruit trees. On the lighter lands of the south of England catch crops are not uncommonly taken on the land before roots. The stubbles are quickly broken up, and vetches, trifolium, or rye, are sown in time to make a start while the land is warm, and to be either cut green or fed off before the land is wanted for turnips in the following spring. The advantages of the practice are that the summer-formed nitrates in the stubble-ground are saved from washing, and that a valuable bite of early fodder is obtained: with the leguminous crops also, the farm is enriched by the nitrogen gathered from the atmosphere. The difficulty of getting catch crops lies in the fact that the stubble ground is left very dry by the preceding crop, so that a timely rainfall is needed to obtain a plant. The danger of their use is that they may so deplete the available soil water as to give the succeeding crop of roots a very poor chance of germinating or growing well. In America the practice has been suggested of sowing some leguminous crop like clover in the tillage orchards about the end of July, so that the new surface crop should so dry the ground as to forward the ripening of the apples on the trees; again, any second growth of the trees due to a late summer rainfall would be prevented, this moisture being dealt with by the catch crop.

The second illustration worthy of notice is that fruit

trees when newly planted in grass land often make a very poor growth for a year or two. This is because a fruit tree when planted is but indifferently supplied with water-collecting roots ; inevitably they are few in number and have a very restricted range. Hence they must be in a soil well supplied with moisture if they are to provide the tree with the necessary water, and are very ill fitted to compete with the matt of fibrous grass roots surrounding them, should the season turn out dry. In one experiment the moisture in the top foot of a pasture was found to be only half that present in the top foot of neighbouring uncropped land. Few crops so effectually dry the surface soil as grass does, because of the intimate way in which its roots traverse the soil ; hence a fruit tree cannot compete with grass for water as long as the two sets of roots are confined to the same layer. The experiments at the Woburn Fruit Farm of planting fruit trees and sowing the seed of coarse meadow grasses at the same time, show this competition at its highest degree, but even when trees are planted in old pasture care should be taken to keep a ring round the tree free from grass and well cultivated or mulched for at least two years. For similar reasons, when trees are planted in arable land weeds should be kept down, nor should crops like cabbages or mangolds be grown between the rows of trees ; such crops are usually considered to "draw the land," and deplete it of plant food, but the harm they do lies in the water they withdraw just at the most critical season, when the tree is making its first start in its new quarters.

Bare Fallows.

The custom of fallowing land, of leaving it entirely bare for a season, during which the land is worked as often as possible, is one of the oldest in agriculture ; a rotation of wheat, wheat, fallow, or of beans, wheat,

fallow, being almost universal, until the introduction of turnips gave the farmer a chance of cleaning his land and yet growing a crop at the same time. The objects of a fallow were various: in the first place, the summer cultivations resulted in a thorough cleaning of the land and in a free development of nitrates for the succeeding crop; also on the heavy soils, which are the most suited to fallowing, a good tilth was obtained that was often impossible otherwise. Indeed, at the present day it is found desirable and even necessary to introduce an occasional bare fallow when farming on the heavy clays of the south-east of England, in order to obtain a satisfactory tilth in that dry climate.

The effect of fallowing in causing the production of nitrates is well seen in the following measurements, due to King, of the amount present in the top 4 feet of soil. In the one case the ground was fallow, in the others under crop with oats and barley respectively.

LBS. OF NITROGEN AS NITRATE PER ACRE.			
	Fallow.	Oats.	Barley.
1st foot . .	246.4	5.9	2.6
2nd foot . .	26.7	8.1	5.1
3rd foot . .	6.5	4.7	4
4th foot . .	2.8	4.6	3

The following table also compares the nitrates present in spring in ground which had been cropped, and in ground which had been left fallow the previous year.

LBS. OF NITROGEN AS NITRATE PER ACRE.				
	1st foot.	2nd foot.	3rd foot.	4th foot.
Land previously fallow .	212	56	22	13
" " under crop	25	15	10	7

But in addition to the gain in available nitrogen due to fallowing, the land which does not carry a crop during a season will accumulate a store of water which may be of the utmost service to the succeeding crop. In the preceding section some figures have been given showing how much more water is present at the end of the summer in the fallow land than in the land which had carried a crop, so that in districts where the winter rainfall is small the fallowed land will start the next season with a great advantage. Indeed, in a semi-arid climate where the annual rainfall is insufficient, satisfactory crops may yet be grown in alternate years by using an intermediate fallow period in which to accumulate a reserve of subsoil water.

The following series of measurements will illustrate this point ; it shows the percentages of water in spring and autumn on fallow and cropped land respectively, also the water present in the same land in the following spring and autumn, when both plots were in oats.

	SPRING.		AUTUMN.		FOLLOWING SPRING AND AUTUMN.			
	Fallow.	Corn.	Fallow.	Corn.	Oats.	Oats.	Oats.	Oats.
	1.	2.	1.	2.	1.	2.	1.	2.
1st foot .	24 %	22 %	17 %	7 %	19 %	16 %	6 %	4 %
2nd foot .	20 "	19 "	20 "	12 "	21 "	18 "	10 "	5 "
3rd foot .	18 "	18 "	16 "	4 "	18 "	15 "	9 "	8 "

The effect of the fallowing in retaining more moisture in the soil is seen throughout the whole of the second season.

The way in which fallowed land is of benefit to the crop, both by making nitrates and particularly by saving water in a dry season, is easily seen in the superior plant always found on the outside rows or

edges of an experimental plot divided from the others by a bare path; on one side the plant has the benefit of fallow ground as well as of extra space, light, and air, and flourishes accordingly. The Lois-Weedon system of husbandry, where the land was divided into alternate 5-foot strips of corn and cultivated fallow land, was nothing but an application of this principle on a large scale, as indeed is any system of growing a crop in wide rows to admit of some form of hoe or cultivator working regularly at the ground between. In a humid climate or on a porous soil there is great danger of losing the nitrates formed in the summer by washing out during the autumnal and winter rains, nor is there any advantage gained by storing water where the usual winter rainfall is sufficient to saturate the soil. For this reason, in the Rothamsted experiments, the plot growing wheat continuously has given a greater crop per acre per annum than the plot fallowed and sown with wheat in alternate years, though the wheat crop following fallow has always been larger than the crop grown the same year on the unmanured plot.

Average Crop.	WHEAT EVERY YEAR.		FALLOW AND WHEAT.	
	Grain.	Straw.	Grain.	Straw.
1856-95 .	Bushels. 12 $\frac{3}{4}$	Lbs. 1127	Bushels. 8 $\frac{5}{8}$	Lbs. 798

Of course the average crop on the fallowed ground was twice the above figures, *i.e.*, 17 $\frac{3}{8}$ bushels of grain and 1595 lbs. of straw, but it was only grown every alternate year.

That the autumnal rainfall is the great factor in determining whether a bare fallow shall be profitable

or not to the following crop, may be well seen by a further examination of the results obtained at Rothamsted on these plots, by comparing the crops with the percolation which took place in the autumn previous.

The percolation through 60 inches of bare soil for the four months, September to December inclusive, as measured by the drain gauge previously described on p. 75, amounted on the average to 6.45 inches for the 31 seasons 1870-1901. If, then, we divide the harvest years into two groups according as the autumnal percolation is above or below the average, and allot to each year the crops on the continuous wheat and wheat after fallow plots for the harvest following the given percolation, we shall obtain the following average results, which show in group 1 the mean crops following autumns of less than average percolation, and in group 2 those following autumns of comparatively high percolation. The percolation is given in inches, the crops in lbs. per acre of total produce, both grain and straw; and as further evidence of the extent of percolation, the average number of days are given during the four months on which water ran from the tile drain underlying the continuous wheat plot.

		Percola- tion through 60-inch gauge.	No. of days on which tile drain ran.	CROP, LBS. PER ACRE.		
				Wheat after Wheat each Year.	Wheat after Fallow.	Gain due to Fallow.
1.	15 Years of Percolation below average	3.99	4	1807	2677	870
2.	16 Years of Percolation above average	8.92	13	1627	1757	130

Thus the bare fallow which increased the following crop above that given by the continuous wheat plot by nearly 48 per cent. in the seasons when a comparatively dry autumn succeeded the fallow, increased it by less than 8 per cent. when there was much percolation after the fallow.

It follows, therefore, that the practice of fallowing land is only an economical one where the annual rainfall is low and where the land is too strong to admit of free percolation; it is, however, admirably adapted to the successful cultivation of clay land in dry, hot climates.

CHAPTER V

THE TEMPERATURE OF THE SOIL

Causes affecting the Temperature of the Soil—Variation of Temperature with Depth, Season, etc.—Temperatures required for Growth—Radiation—Effect of Colour—Specific Heat of Soils—Heat required for Evaporation—Effect of Situation and Exposure—Early and Late Soils.

THE life of a plant is practically suspended below a certain temperature, which is about 40° F. for the majority of cultivated plants; all the various changes which are essential to the development of the plant, such as germination, vegetative activity, and the bacterial processes in the soil, show a similar dependence upon temperature.

These vital actions cease below a certain minimum, above which they usually increase with the temperature until an optimum is reached, when the action is at its greatest; beyond this point the action decreases until a superior limit is reached, which again suspends all change. It therefore becomes important to study the manner in which heat enters and leaves the soil, because upon the temperature acquired depend such practical questions as the suitability or otherwise of the land for particular crops, the season at which to sow, and the earliness or lateness of the harvest.

The surface soil receives heat in four ways:—

- (1) By direct radiation from the sun, whose rays both of light and invisible heat are absorbed

and raise the temperature of the absorbing soil.

- (2) By precipitation, as in the spring when warm rain enters the ground and brings with it a considerable quantity of heat, or when aqueous vapour in the air is condensed on the colder soil.
- (3) By conduction from the heated interior of the earth a small amount of heat reaches the surface.
- (4) By the changes which result in the decay of the organic material of the soil, when as much heat is developed as if the same material had been burnt in a fire.

The surface soil loses heat :—

- (1) By radiation ; like any other body possessing heat, the surface of the soil is always emitting invisible radiant heat, which may, or may not, be counterbalanced by the corresponding radiations it is absorbing.
- (2) By conduction either to cooler layers of earth below or to cooler air above.
- (3) By the evaporation of the water contained in the soil ; at ordinary temperatures the evaporation of 1 lb. of water would absorb enough heat to lower the temperature of about 7500 lbs. of soil by 1° F.

The actual temperature attained by a given soil at any time depends upon the relative effect of the heating and cooling actions set out above.

Soil Temperatures.

The accompanying curves (Fig. 8), show the monthly mean temperatures of the soil at 6 inches, 3 feet, and 6 feet respectively, as compiled from readings




FIG. 8. — Soil Temperatures at 9 A.M., Monthly Means, 1896.

taken at 9 A.M. at Wye during 1896, the soil being a light, well-drained loam under grass. It will be seen that the variations in temperature diminish with the depth: in fact a point is soon reached, about 50 feet down, below which the effect of the gain or loss of heat at the surface is inappreciable, and the temperature is constant from day to day, only increasing with the depth, according to the well-known law. Each curve cuts each other curve at least twice; for a certain period the upper layer is giving, and during the rest of the year, receiving heat from the layer above or below. The maximum temperature attained at a depth of 3 feet comes a little later in the year than the maximum for 3 inches, and the maximum at 6 feet lags still further behind, owing to the slowness with which the heat is conducted. It will be seen that the curve indicating the temperature at 6 inches (and the mean figures for 3 and 9 inches are almost identical) only reaches the 41°F. required for the beginning of vegetative growth during April; it is, however, constructed from monthly averages only, and from observations taken at 9 A.M., when the surface soil has been considerably cooled during the night. Much higher temperatures are obtained during certain parts of the day even in the early spring months, otherwise no germination could take place; these diurnal and hourly fluctuations are, however, chiefly confined to the surface soil. The following curves (Fig. 9), show firstly the daily results during a fortnight of April 1902, also certain hourly readings obtained in the same month, in this case beneath smooth, well-worked arable land. The diurnal variations die away before the depth of 3 feet is reached, nor are the hourly variations perceptible at the depth of one foot, except in the case of heavy precipitation

and a pervious soil. It will also be noticed that in the last curves, during part of the day the temperature runs up at the depth of 6 inches to a point well above the minimum required for germination, although the mean soil temperature at 9 A.M. is near that limit.

Temperatures required for Growth.

Reference has already been made to the fact that a certain temperature is necessary before the vital processes involved in growth become active; this temperature is not always the same, but may be considered to lie between 40° and 45° F. for most of the plants grown as crops in this country.

The following table shows minimum, optimum, and maximum temperatures of growth for a few plants.

	Minimum.	Optimum.	Maximum.
Mustard	32° F.	81° F.	99° F.
Barley	41	83.6	99.8
Wheat	41	83.6	108.5
Maize	49	92.6	115
Kidney Bean	49	92.6	115
Melon	65	91.4	111

The next table shows the effect of soil temperature upon the growth of the root of maize.

ROOT GROWTH OF MAIZE IN 24 HOURS.

Temperature.	Millimetres.
63° F.	1.3
79	24.5
92	39
93	55
101	25.2
108.5	5.9




FIG. 9.—Soil Temperatures at 9 A.M., Daily Readings.



The osmotic absorption of water by the roots of a plant is much affected by the temperature of the soil ; although some plants, like cabbage, will continue to take in a little water even near freezing point, others require a higher temperature ; for example, Sachs has shown that tobacco and vegetable marrow plants will wilt even at night, when transpiration is very small, if the temperature of the soil falls below about 40° F.

The connection between soil temperature and vital processes is perhaps most apparent in the case of germination, for which not only is a certain minimum temperature requisite, but for several degrees above this minimum the germination is so slow and irregular that the young plant is very liable to perish while remaining in such a critical condition. The following table shows the range of temperatures for the germination of various cultivated plants.

TEMPERATURES OF GERMINATION.

	FAHRENHEIT.		
	Minimum.	Optimum.	Maximum.
Wheat	32° to 41°	77° to 88°	88° to 110°
Barley	40°	77° to 88°	100° to 110°
Oats	32° to 41°	...	88° to 100°
Pea	38° to 41°
Scarlet Runner	49°	91°	115°
Maize	49°	91°	115°
Cucumber, Melon, etc. .	60° to 65°	88° to 99°	110° to 120°

The practical bearing of these figures is obvious ; it is necessary to sow some seeds, like the melon, in heat, and to defer the seeding of other crops, like mangolds or maize, until the ground has acquired not only the temperature necessary for germination, but one that will ensure a subsequent rapid growth of the seedling plants.

For example, turnips will germinate at almost as low a temperature as barley, but the optimum temperature is higher for turnips; they are therefore sown much later in the spring, when the ground has more nearly reached this temperature, because the seed is small and the young plant very susceptible to insect attacks, so that the turnip seed must germinate and grow away rapidly if it is to succeed.

Under ordinary field conditions much of the nutrition of the crop depends upon the activity of certain bacteria in the soil which break down organic compounds containing nitrogen, and ultimately resolve them into the nitrates taken up by the plant. Most bacteria are active within about the same limits of temperature as have been indicated above for the higher plants; the nitrification bacteria, for example, cease their work below 41°F. and above 130°F. , their optimum temperature being about 99°F.

The inadequacy of the production of nitrates for the needs of the crop due to a low temperature is often seen in spring, and may be connected with the yellow colour of the young corn during a spell of cold and drying east wind.

Radiation.

The main source of the soil warmth consists in the heat received from the sun by radiation; this, according to Langley, amounts to about 1,000,000 calories per hour per square metre of surface from a vertical sun in a clear sky. Supposing this energy were wholly absorbed by a layer of dry soil 10 cm. thick, its temperature would rise by as much as 90°F. in an hour. Of course in nature many other factors are at work to reduce this temperature; the sun is rarely vertical, the soil material does not completely absorb but reflects

some of the sun's rays unchanged ; at the same time it is always radiating in its turn rays of lower pitch than the majority of those received. The latter rays are easily caught by many substances, glass and water vapour in particular, which are transparent to the rays of higher refrangibility proceeding from the sun. A greenhouse, for example, is practically a radiant heat trap ; the temperature inside runs up because the sun's rays of light and heat can penetrate the glass, whereas the obscure heat rays radiated back again from the warmed-up surfaces inside the house are not able to pass the glass again. Just in the same way the temperature rises and the sun's heat becomes oppressive when the air is laden with water vapour, because it retains the radiations emitted by the surfaces heated by the sun. *Per contra*, the temperature of the ground falls more rapidly at night when the sky is clear and the air dry, for then there is no blanket of cloud or water vapour to arrest or reflect the radiations from the surface.

The power of soils to absorb the sun's rays depends very much upon colour : with black soils the absorption is almost complete ; it is greater for red than for yellow soils, least of all for those which look distinctly white or light coloured. It has already been shown that the colour of soils depends mainly upon humus and hydrated ferric oxide : the latter accounts for all the red, yellow, and brown shades, the former for the black coloration of the soil. Deep-seated clays are often blue or green, due to various ferrous silicates or to finely divided iron pyrites, which afterwards oxidise to brown ferric oxide. The more finely grained a soil is the more surface it possesses, and the greater amount of colouring matter that is required to produce a given colour ; a coarse sand is often quite

black though it contains but a small percentage of humus.

Though the colour of a soil affects the rate at which it absorbs heat, it does not follow that the dark soils will lose with a corresponding rapidity when radiation is taking place at night; the emissive power of the substance for rays of low refrangibility, such as are emitted at ordinary temperatures, is not affected by colour. Hence, the extra heat gained by a dark soil is retained and not lost by a corresponding increase in its radiating power.

The curves in the accompanying diagram (Fig. 10), show the temperatures of the soil at a depth of 6 inches during an April day with a bright sun and a strong drying wind. The land was a light loam of a grey-brown colour when dry; it had been cultivated, rolled, and the surface hoed over before the thermometers were inserted; on plot 1 the bare ground was left untouched, plot 2 received a dressing of soot until the surface was black, plot 3 was similarly whitened over with lime. It will be seen that the covering of soot warmed the soil until at 3 P.M., when the maximum temperature was attained, the difference was 2.4° ; this superiority is also retained during the later cooling stages; even at 9 P.M. the blackened soil was still 2.5° warmer than the bare ground. The whitening with lime had caused so considerable a reflection of the radiant heat that the soil beneath was always 2 to 3° cooler than the bare ground.

Specific Heat.

The specific heat of the substances of which soil is composed is comparatively low, ranging from 0.1 to 0.2, *i.e.*, only from one-tenth to one-fifth as much heat will be necessary to raise the temperature of




FIG. 10.—Soil Temperatures at 6 in. depth, as affected by the state of the surface. Sun with strong N.E. wind. 27th/iv/02.



1 lb. of dry soil by 1° , as would be required to produce the same rise of temperature in an equal weight of water. The humus possesses the greatest specific heat and the sand the least; against this must be set off the fact that the densities of these soil constituents vary in the opposite sense, so that the amounts of heat required to bring about a given rise of temperature to a certain depth in different soils are more nearly equal. The specific heats are, however, small in every case when compared with that of water; hence soils which retain much water will require far more heat to raise their temperature than dry soils would. In consequence, clay and humus soils are cold because the water they retain gives them a high specific heat, they require more of the sun's rays in spring to bring them up to the proper temperature for growth, while sandy and other open-textured soils are warm because of their dryness.

If the figures given by Oemler for the specific heats of various soils be combined with their approximate densities and with their minimum capacity for water, the following results are obtained for the specific heats of certain typical soils in a saturated but completely drained condition—

	SPECIFIC HEAT.		
	Equal Weights.	Equal Volumes.	
	Dry.	Dry.	Wet.
Water . . .	1.0	1.0	1.0
Humus . . .	0.21
Sandy Peat . .	0.14	0.11	0.72
Loam . . .	0.15	0.18	0.53
Clay . . .	0.14	0.15	0.61
Sand . . .	0.1	0.125	0.34

The sandy soil only requires about half as much heat to raise its temperature by a given amount as

would be needed by the peaty or clay soil, when all the soils are in a wet but thoroughly drained condition ; of course if the clay or peat were inadequately drained, so that a higher proportion of water was retained, their specific heats would approximate still nearer to that of water.

Just as a clay soil is slow to warm in the spring, its high specific heat causes it to cool correspondingly slowly after the heat of the summer. On clay soils growth will be noticed to continue later into the autumn than on the lighter lands.

Heat required for Evaporation.

The coldness of a wet and undrained soil is due, not only to its high specific heat, but to the fact that so much of the heat it receives is spent in evaporating some of its retained water without causing any rise in temperature. The evaporation of 1 lb. of water at 62° F., *i.e.*, its conversion into water vapour at the same temperature, requires as much heat as would raise the temperature of 1050 lbs. of water by 1° F., and, if there be no source of external heat bringing about the evaporation, the substance from which the water is evaporated must become cooled to a corresponding extent. The cooling effect of evaporation is well known, but its application to the soil is not always realised ; clays and even more so undrained soils are cold and late, not only because of their high specific heat, but because they retain so much water which can be evaporated. The drying winds of early spring exercise a great cooling effect whenever the soil moisture is allowed to evaporate freely, hence the importance of establishing a loose tilth, if the seed-bed is to warm up the temperatures requisite for germination.

Anything providing a little shelter to check evaporation and break the force of the wind in the spring will have a considerable effect in raising the soil temperature. The dotted curve in Fig. 10 shows the effect of enclosing a plot of the same land with a slight hedge made of spruce fir boughs about 2 feet high. In the morning the temperature of the sheltered plot was below that of the open ground because of the shading from the direct rays of the sun, but as soon as this effect was over it will be seen that the wind break, by checking evaporation, maintained the soil temperature more than 2° above that of the open ground.

Even the stones upon the surface of the land help. In the *Journal of the Royal Agricultural Society* for 1856, an experiment is described in which the flints were picked off the surface of one plot of ground and scattered over an adjoining plot, with the result that the plot with double its usual allowance of stones was three or four days earlier to harvest than the rest of the field, while the plot without stones was a week later still. It will always be noticed how the grass upon a field coated with dung starts earlier into growth, because the loose manure acts as a mulch and protects the soil from the cooling due to evaporation.

Land which is protected from evaporation, and to some extent from radiation, by a layer of vegetation, is always both warmer and less subject to fluctuations of temperature than bare soil.

The warming up of a well-tilled surface soil is increased by the fact that the conduction of heat into the soil below is much checked by a loose condition. A solid body will always conduct heat far better than the same substance in the state of powder, and the more compressed the powder is the better it will conduct, simply because there are more points of contact. Hence

a rolled and tightened soil will conduct the heat it receives more rapidly to the lower layers than one which is loose and pulverulent. King has shown that, despite the increased evaporation, there is always a higher temperature below a rolled than an unrolled surface.

A few observations may be given showing the effect of drainage in enabling the sun's heat to raise the temperature of soil. The curves (Fig. 11) show the hourly temperatures of the drained and undrained portions of a peat bog during two last days in June (Parkes, *J. R. Ag. Soc.*, 1844, 142), at depths of 7 inches and 13 inches respectively; the sudden rise of temperature between 3 and 4 P.M. on the second day was due to a thunderstorm, during which heavy rain at a temperature of 78° F. was falling.

The figures in the table below are derived from observations made by Bailey-Denton in 1857 (*J. R. Ag. Soc.*, 1859, 273) on a stiff clay soil situated on the Gault at Hinxworth, the drains being 4 feet deep and 25 feet apart in the drained part. It is noteworthy that the temperature of the air 9 inches above the surface is higher for the drained than for the undrained land, thus supplying further evidence of the cooling effect of evaporation.

MEAN TEMPERATURE °F. AT 9 A.M.

	A.—Land Drained.			B.—Land Undrained.		
	Air.	At 18"	At 42"	Air.	At 18"	At 42"
March	39.4	40.6	41.7	39	38.2	40.3
April	43	46	44.8	42.4	44	43.8
May	52.9	51	48.4	52.7	48.8	47.1
Mean excess over B. .	0.4	2.2	1.2			




FIG. 11.—Temperatures of Drained and Undrained Bog.



Effect of Situation and Exposure.

Other conditions being equal, in the northern hemisphere the soil temperatures will always be higher on land sloping toward the southern quadrant than with any other aspect. King found a difference of about 3° F. down to the third foot between a stiff red clay soil with a southern slope of 18° and the same soil on the flat; Wollny obtained a mean difference of $1^{\circ}.5$ between the north and south sides of a hill of sandy soil inclined at 15° . The chief cause of these differences is the fact that in this country the sun is never vertical, hence a beam of sunlight represented by xy , Fig. 12, is spread




FIG. 12.—Distribution of the Sun's Rays on Southerly and Northerly Slopes.

over an area represented by AB when the ground is flat; if the ground slopes to the south the same beam is spread over the smaller area represented by AC; if the ground slopes to the north, it is spread over the larger area represented by AD. During the winter half-year also, the southern slope will have a longer duration of sunlight than the northern slope.

Though in a general way the temperature both of the air and the soil decreases with elevation above

sea level, yet it is well known that the severest frosts occur locally at the bottom of valleys and hollow places. This is particularly noticeable in the sudden night frosts, characteristic of early autumn and late spring, which are so dangerous to vegetation; it is usual to find the tenderer plants of our gardens, such as dahlias, cut down by frost on the lower levels long before the gardens on the hill are affected. Spring frosts again will often nip the early potatoes in the valleys when the higher lands are untouched. Fruit plantations should not be set in the valleys, for no crop suffers more from these unseasonable snaps of cold; so clearly is this fact recognised that in some fruit-growing districts only land above a certain elevation is regarded as suitable for fruit, and commands a higher rent in consequence. Two causes co-operate in producing the excess of cold at the lower levels. The night frosts in question are always the result of excessive radiation when the sky is clear and the air still. The ground surface loses heat rapidly and cools the layer of air above; the cold air thus produced is denser, and proceeds to flow down hill and accumulate at the lower levels. There is thus a renewal of the air above the higher slopes, and the effect of radiation is mitigated by the inflow of warmer air; at the bottom no change of air is produced and the radiation proceeds to its full effect.

At the same time the vegetation in the valley is generally more susceptible to a frost; the greater warmth by day, together with the extra moisture and shelter induce an earlier and a softer growth.

The other cause that operates to produce severer frosts in the valleys arises from the fact that frosts, and radiation weather generally, accompany the distribution of pressure known as an "anti-cyclone," during






FIG. 13.—Temperatures (Maximum and Minimum) at Various Altitudes.

A = 100 feet. B = 150 feet. C = 500 feet.

which there is always a gentle downdraught of cold air from the clear sky above. But the circulation of air in an anti-cyclone is always reversed at a certain elevation, so that as one ascends, the downdraught of cold air becomes less and eventually ceases; the mean temperature at the same time rises instead of falling with the elevation.

Observations of the minimum temperature on the grass made at two stations on a gentle slope of the downs at Wye, about a mile apart and differing in level by 100 feet, showed during a period of thirty-six days in February and March 1902 (which was exceptionally calm and mild), a mean difference of 1° in favour of the upper station, but on two occasions the lower thermometer fell to $24^{\circ}.5$ and $21^{\circ}.5$, when the upper thermometer was $30^{\circ}.5$ and $29^{\circ}.5$ respectively.

The accompanying curves (Fig. 13) show the daily maxima and minima of the air temperatures at 4 feet from the ground for a few days before and after the occurrence of a disastrous late spring frost in May 1902. One station, A, was in a river meadow about 100 feet above sea-level; the second, B, was on a terrace about 50 feet higher and half a mile away; the third, C, was on the flat summit of the down 500 feet above sea-level and about $1\frac{1}{2}$ miles from the first station. It will be seen that the river-side station gave always the highest maxima during the period and the lowest minima, showing on the one occasion 11° of frost.

Early and Late Soils.

From all the considerations developed above it will be seen that an early soil is essentially a coarse-textured and well-drained one. Such a soil retains little water, thus possessing a low specific heat, and is easily warmed;

at the same time the low water content gives rise to less evaporation at the surface, and this great cause of cooling is minimised. The dryness of the soil permits of early cultivation, which, by cutting off the access of subsoil water and diminishing the conduction of heat from the surface, quickens the warming up of the seed-bed. The early aeration and warming of the soil promotes the nitrification which is also necessary to growth. If, further, the soil be stony, the conduction of heat from the surface layer into the soil is more rapid, solids being better conductors than powders. Such soils again are generally dark coloured, because on the comparatively small surface exposed by the coarse grains the same proportion of humus has a greater colouring effect.

These conditions are generally fulfilled by the alluvial soils bordering the larger rivers; in the neighbourhood of large towns, which are generally situated on a river, they form the typical market gardening soils, especially as their natural poverty can be alleviated by the large supply of dung which is easily obtainable from the town.

At the same time these soils have their disadvantages; from both their nature and their situation they are subject to rapid changes of temperature; they suffer much from night frosts both in spring and autumn, and dry out easily in the summer, so that some crops do not come to their full growth. Autumn planted vegetables grow away rapidly and are apt to become "winter proud" and killed by severe weather.

The soils naturally retentive of water are late, both because they dry slowly and are rarely fit to work early in the year, and because the high water content keeps their temperature down. Except in long-continued droughts they maintain a supply of water to the

plant, their high specific heat keeps them at a comparatively equable temperature and prevents them from cooling down so soon when the summer heats are past. In consequence the crop is neither forced early to maturity, nor is growth checked so soon in the autumn; the period of development is prolonged until in some cases the season becomes unsuitable for ripening. Many subtle differences may be noticed between the quality of produce grown upon early and late soils; for example, a comparison made by the author of the same variety of apple grown upon adjoining clay and sandy soils showed that the apples from the clay land were smaller and greener, but contained a greater proportion of sugar and acid and possessed a higher aroma than the apples grown upon the lighter and earlier soil. Wheat grown on the clays is generally of better quality and "stronger" than that yielded by the lighter soils; whereas the lighter soils yield the finer barley, in which carbohydrates and not nitrogenous materials are characteristic of high quality. On a light soil, becoming both warm and dry early in the season, the plant ceases the sooner to draw nutrient material from the soil; assimilation, however, continues after the plant has ceased to feed; finally maturation—the removal of the previously elaborated material into the seed—begins earlier and can be more thoroughly accomplished. Hence grain from an early soil is, on the whole, characterised by a higher proportion of carbohydrate to albuminoid, always provided that no excessive or premature drying out has taken place, for that ripens off the grain before the transference of starch has been completed.

CHAPTER VI

THE CHEMICAL ANALYSIS OF SOILS

Necessary Conventions as to the Material to be Analysed—
Methods Adopted—Interpretation of Results—Distinction
between Dormant and Available Plant Food—Analysis of
the Soil by the Plant—Determination of "Available" Phos-
phoric Acid and Potash by the Use of Weak Acid Solvents.

THE chemical analysis of a soil aims at ascertaining the amount which the soil contains of the various elements necessary to the nutrition of the plant, with a view of either making good the general deficiencies of the soil or of adjusting the supply of plant food to such special requirements of a particular crop as may have been indicated by previous experiment.

The analysis of plants grown under ordinary conditions shows that a comparatively limited number of elements enters into their composition; in the main they are composed of water and certain combustible compounds of carbon, hydrogen, nitrogen and sulphur. In the mineral residue that is left after the combustible material has been burnt off, will be found potassium, sodium, calcium, magnesium, and a little iron among bases, and phosphorus, chlorine, sulphur, and silicon among non-metallic elements. Manganese in very small quantities occurs in nearly all plants: other elements like lithium, zinc, copper, are found in traces under

special conditions of soil. By pot cultures in the laboratory it can be shown that of the above elements the carbon, hydrogen, and oxygen are drawn from the atmosphere or the water, and that nitrogen, chlorine, sulphur, phosphorus, among non-metals, and potassium calcium, magnesium and iron, among metals, are elements indispensable to the plant, and are derived by way of the root from the soil. In view of the above facts it is clearly unnecessary to make an ultimate determination of all the elements present in the soil, which has already been shown to consist largely of sand and various silicates of alumina, etc. These materials constitute the medium in which the plant grows, but do not themselves supply it with any food; they need not therefore be estimated chemically.

The chemical analysis of a soil then resolves itself into determinations of the nitrogen, phosphorus, potassium, calcium, and (of less importance) of sodium, magnesium, iron, aluminium, chlorine and sulphur. To these must be added the determination of the carbon compounds of the soil, which have already been touched on under the head of humus, and of the carbonates of calcium and magnesium, which in most soils constitute the bases available for neutralising any acids that may be produced. Having decided upon the elements to be determined it would then be possible to proceed as in an ordinary mineral analysis: the sample of soil would be reduced to such a state of division as would admit of drawing an accurate small sample, and then entirely disintegrated by some such reaction as fusion with ammonium fluoride. But results obtained in this way would give very imperfect information about the soil, for the procedure draws no distinction between material present in the unweathered interior of the stones and

coarser particles, which could not reach the plant for generations, and that which exists as very small particles or as a coating on the larger ones, and is therefore open to attack by the water in the soil. The nutrient material of the soil can only reach the plant in the dissolved state, and in dealing with slightly soluble substances such as constitute the soil, the amount which goes into solution is practically proportional to the surface exposed. But the surface exposed increases as the material is subdivided, one gram of soil in pieces 1 mm. in diameter would only expose one-thousandth of the surface exposed by the same amount of soil in particles 0.001 mm. in diameter, so that to all intents and purposes the stones and coarser particles contribute such a small proportion of the surface of the soil that the material dissolved from them can be neglected.

For these reasons—the small surface exposed by the larger particles and the unweathered nature of the compounds within them—the stones above a certain size are not included in the analysis, nor is any attempt made to thoroughly bring into solution even the selected material. Hence it becomes necessary in soil analysis to accept certain “conventions” as to the preparation of the soil for analysis, the nature of the acid used for solution and the duration and temperature of the attack; all of which factors so affect the mineral matter going into solution that results are only comparable when obtained in the same way. It must always be remembered that soil analysis is only a relative process, by which soils that are unknown can be compared with others whose fertility has been tested by experience: no means exist of directly translating the results into terms of the crop the soil will carry. The methods of analysis that are indicated

below are those adopted by the members of the Agricultural Education Association in this country: unfortunately, there is no uniformity in the methods pursued even among chemists in the same country, wide as are the variations introduced by the different processes in vogue. For example, an acid such as hydrochloric will dissolve very different amounts of potash from a given soil, according as the soil is treated directly with the acid or first ignited, nor is there any constant relation between the amount dissolved from ignited and from raw soil.

Method of Analysis.

The soil sample is taken, passed through the 3 mm. sieve and air-dried, exactly as previously described for the mechanical analysis. From the large air-dried sample of "fine earth" a portion of about 100 grams is drawn, and either ground in a steel mill or broken in a steel mortar till it will all pass through a sieve with round holes 1 mm. in diameter. This is done to enable the analyst to draw a fair sample weighing only a few grams: if the "fine earth" which passes the 3 mm. sieve were itself used, it would be impossible to adjust the relative proportions of coarse and fine to correspond with the bulk. It is not uncommon to find coarse particles of carbonate of lime sparsely scattered through the soil when the land has been limed; only by grinding and mixing can this matter become evenly distributed through the soil. On the ground material the following determinations are made:—

- (1) Moisture lost at 100° C.
- (2) Loss on ignition.
- (3) Nitrogen.
- (4) Earthy carbonates.

- (5) Phosphoric acid and potash soluble in strong hydrochloric acid. If necessary, soda, lime, magnesia, oxides of iron, alumina, and sulphuric acid can be determined in the same solution.

(1) About 5 grams are weighed out into a platinum dish or porcelain basin and dried in the ordinary steam oven, the temperature of which is never quite 100°C . If the soil contains much organic matter, it will be difficult to bring it to a constant weight, the material will slowly lose water for weeks. An arbitrary limit of twenty-four hours drying should be taken.

(2) The loss on ignition is determined by putting the dish that has been dried in the previous operation into the muffle and keeping it at a bright red heat for half-an-hour. In calculating the result the amount of carbon dioxide present in the soil as earthy carbonates, ascertained by operation 4, must be deducted from the loss on ignition. The weight lost in the muffle includes organic matter, water of constitution in kaolinite and similar hydrated silicates, and carbon dioxide expelled from the carbonates, but the inclusion of this last factor in the result set out would only further confuse its interpretation.

The loss on ignition is wanted as a measure of the organic matter of the soil, but we have no means of estimating the varying part, great with clay soils, that is played by the water of constitution. It is possible to get a better measure of the organic matter by estimating the total carbon in the soil and assuming that the organic matter of the original soil contained about 55 per cent. of carbon. But the combustion of a soil is rather a tedious affair even in skilled hands, and the processes of wet combustion, such as digestion with

sulphuric acid and potassium bichromate or permanganate, fail to oxidise wholly the carbon contained in a soil.

(3) The nitrogen in 10 to 20 grams of the ground "fine earth" is estimated by Kjeldahl's process. Though there is some nitrate present in the soil, no special precaution need be taken on its account, the proportion it bears to the total nitrogen is so small as to be negligible.

(4) The earthy carbonates of the soil are estimated from the quantity of carbon dioxide, which is evolved on treating the ground "fine earth" with an acid. When the proportion of calcium carbonate is high the determination can be made by the usual gravimetric methods. Scheibler's apparatus for measuring the volume of carbon dioxide evolved is suitable when the proportion of calcium carbonate does not fall below 1 per cent., below that point some other method must be employed, for all the carbon dioxide evolved goes into solution in the reacting acid. For a method of determining the small quantities of carbonates in soil—and a knowledge of the exact amount is more important with small than with large proportions—see Hall and Russell, *Jour. Chem. Soc. Trans.*, 1902. It is not sufficient in such cases to estimate the calcium dissolved by dilute acids from the soil, because there are always present other compounds of calcium, *e.g.*, silicates and sulphates, which are soluble in the acid and would be reckoned as calcium carbonate. The factor that is required is not the calcium, but the amount of carbonate which will serve as a base in the soil, and combine with the acids liberated by decay, nitrification, or from some of the artificial manures. To this end it is not necessary to discriminate between the carbonates of calcium and magnesium, accordingly

the carbon dioxide evolved is calculated back to calcium carbonate. In a few soils ferrous carbonate may be present; this is oxidised to ferric hydrate when the powdered soil is boiled with water, and may be so removed before determining the carbon dioxide. In temperate climates, however, it is only a few bog soils that need be examined for ferrous carbonate.

(5) For the determinations of soluble constituents 20 grams of the powdered soil are placed in a flask of Jena glass, covered with about 70 c.c. of strong hydrochloric acid and boiled for a short time over a naked flame to bring it to constant strength. The acid will now contain about 20.2 per cent. of pure hydrogen chloride. The flask is loosely stoppered, placed on the water bath, and the contents allowed to digest for about forty-eight hours. The solution is then cooled, diluted and filtered. The washed residue is dried and weighed as the material insoluble in acids.

The solution is made up to 250 c.c. and aliquot portions are taken for the various determinations. The analytical operations are carried out in the usual manner, but special care must be taken to free the solution from silica and organic matter. For phosphoric acid a portion of the solution is evaporated to dryness and ignited, the residue is taken up with hydrochloric acid, filtered, again evaporated to dryness, and heated in an air bath for half-an-hour at 105° . This residue is then taken up with dilute nitric acid, filtered and made up to about 50 c.c. Five grams of ammonium nitrate are added, and 50 c.c. of a solution of ammonium molybdate containing 60 grams molybdic acid per litre. The mixture is put aside in a warm place for twenty-four hours, the precipitate is filtered off, and after washing with

ammonium nitrate solution, is dissolved by ammonia into a tared porcelain basin, evaporated to dryness, and gently ignited over an argand burner. The resulting material contains 3.794 per cent. of phosphoric acid. For the determination of potash the same procedure is followed, but the residue after the second evaporation is taken up with dilute hydrochloric instead of nitric acid. To the solution 5 c.c. of a solution of chloroplatinic acid containing 0.005 gram platinum per c.c. is added, and the whole gently evaporated over a water bath till almost dry. It is then thrown on to a filter and washed with alcohol, then washed again with a solution of ammonium chloride, which has been saturated with the double chloride of platinum and ammonium, and finally dissolved off the filter paper with a little hot water in a tared basin, evaporated and weighed. A Gooch crucible is most convenient for handling both the phosphoric acid and potash precipitates.

The other determinations which may be made in this solution consist of soda, lime, magnesia, iron, alumina, and manganese among bases, and sulphuric acid, but in most cases these may be omitted. It is occasionally desirable to examine the soluble salts in the soil; about 200 grams of the fine earth should be successively washed with small portions of hot water by the aid of a filter pump. In the solution the total solids are determined; they consist, in the main, of the nitrates, sulphates, and chlorides of sodium, potassium, magnesium, and calcium, which can be determined by the usual methods. Of course the amount of soluble salts to be found in the surface soil at any time is largely regulated by the previous weather; after considerable rainfall the soluble salts are washed down into the subsoil, after long evaporation they are con-

centrated in the surface layers. The amount of nitrates that is present is further affected by the previous cropping, temperature, and working of the soil, and by the manipulation the soil receives after it reaches the laboratory. Thus the determination of the soil constituents that are soluble in water does not enter into the ordinary routine of analysis, their presence is affected by so many temporary factors which prevent the comparison of one soil with another.

As, however, the determination of the amount of nitrate present in a soil is often required for other purposes, it will be convenient here to indicate the method to be followed. In the first place the soil must be analysed immediately after it has been sampled and without any drying, for the manipulation a soil sample usually receives in the drying, sifting, and other preliminary operations will cause the production of large quantities of nitrates in ordinary soils.

A funnel with a large filtering surface, at least 2 inches in diameter, must be taken; Warington originally made use of the inverted upper portion of a Winchester quart bottle with a disc of copper gauze, 2 inches in diameter resting in the neck, but this may be replaced advantageously by a Buchner funnel 6 inches in diameter. In either case the funnel is connected with an exhaust pump, the disc is covered with a good filter paper wetted, then at least 500 grams of the soil are packed carefully into the funnel and pressed down a little, care being taken to avoid plastering if the soil is clayey. The soil sample as it comes from the field is spread out, roughly crumbled and mixed; from this the 500 grams or so are taken and weighed before putting on the funnel. Another portion is weighed out and dried in the steam oven to ascertain the proportion of water in the sample. 50 c.c. of hot distilled water are

now poured on the soil, allowed to stand a few minutes, and the pump started. When the liquid has been drawn through, successive small portions of hot water are put on, and the pump started afresh; it will be found possible to wash out practically the whole of the nitrate with 100 c.c. of water.

If the liquid shows any tendency to come through the filter turbid, this can be obviated by adding a few drops of sulphuric acid to the water. In the filtered liquid the nitrates may be determined either by Warington's indigo method, or by evaporating down, and using Schloesing's method of reduction to nitric oxide by means of ferrous chloride, or by making alkaline with caustic soda, adding a few strips of aluminium foil to reduce the nitrates to ammonia, and after a few hours, distilling off and estimating the ammonia.

The table (Appendix I) shows the analyses by the method above described of a few typical soils.

It will be seen, as a rule, that the water retained by the soil when air-dry, the loss on ignition, and the nitrogen rise and fall together, because the humus which contains the nitrogen is the most hygroscopic constituent of soils. Clay soils which tend to conserve humus also contain the most constitutional water; this further tends to increase the loss on ignition in their case.

The proportion of nitrogen found ranges from 0.5 per cent. in very rich pasture soils down to below 0.1 per cent. on light arable soils, it is rarely up to 0.2 per cent. in arable soils, and the warmer, the more open, and more worked the soil is, the less will be the proportion of nitrogen. In the fertile hop-gardens of East Kent the percentage of nitrogen is rarely as much as 0.2 per cent., despite the great dressings of nitrogenous manure that are annually applied.

The proportion of phosphoric acid in soils is not so variable as the proportion of nitrogen; it ranges from about 0.06 per cent. to 0.2 per cent.; the lower amounts occurring generally on the sands and clays, the higher on loams and soils well provided with calcium carbonate.

The proportion of potash shows extreme variations: a clay soil may yield one per cent. of potash to strong hydrochloric acid, a sand only one-tenth as much. It has already been pointed out that "clay" is chiefly the result of the weathering of felspars and kindred minerals containing potash; this weathering is never chemically complete, so that all soils containing any considerable admixture of clay are necessarily rich in potash. The amount dissolved out by hydrochloric acid is also somewhat of an accidental figure, as it depends very much on how far the previous treatment of the soil has forwarded the weathering process, for there remains in all soils rich in potash much material that will not yield potash to strong hydrochloric acid even after forty-eight hours' digestion. For example, the soil from one of the plots in the Broadbalk wheat-field at Rothamsted only yielded 0.5 per cent. of potash to hydrochloric acid, but when completely broken up by ammonium fluoride it was found to contain 2.26 per cent. of potash.

Of all the soil constituents calcium carbonate shows the widest fluctuations; it may constitute 40 or 50 per cent. of some of the thin soils resting on the chalk, or it may sink to such small proportions as only to be detected by the most refined analysis on some of the sands and clays.

The importance of the calcium carbonate lies not in the calcium that it supplies for the nutrition of plants, but in that it acts as the chief base maintaining the neutrality of the soil. Many plant diseases,

like the slime fungus which causes "finger-and-toe" in turnips, etc., are only prevalent when the soil is losing its neutral condition, and are not found when a sufficiency of calcium carbonate is present. It is for this reason always desirable to test the reaction of a soil by putting a little on litmus paper, moistening it, and after a few minutes washing away the soil. What proportion of calcium carbonate is required for fertility and health is difficult to say, probably an inferior limit of 0.5 per cent. is the lowest that is safe. In the case of soils containing about this proportion much will depend on how finely it is disseminated, 0.5 per cent. in visible pieces will not be so effective as 0.1 per cent. of the amount in particles of the same order of size as the clay or silt particles. For this reason it is advisable when analysing a doubtful soil of this kind, to make a rough separation of the finer particles, by pestling up 10 grams of the soil with water, and pouring off the supernatant liquid after one minute's standing, as in a mechanical analysis. Having washed away the finer portion of the soil two or three times in this way, the residue is dried and the carbonates which remain are estimated as before, thus a rough idea is obtained of their distribution among the finer or coarser sets of soil particles.

Interpretation of the Results of a Soil Analysis.

Though much may doubtless be learnt by a comparison of the analysis of a given soil with the analysis of others whose fertility has been proved by experience or by actual manurial experiments, there are yet many considerations which prevent too much weight being attached to the results thus obtained.

A comparison of the total amount of any of the elements of plant food in the soil with the amount that

is withdrawn by an ordinary crop shows at once that even in the poorest soils there is sufficient material for something like a hundred average crops.

The density of the surface soil has already been discussed ; it will be sufficiently accurate for our purpose if we consider that the top 9 inches of one acre of an ordinary arable field weighs 2,500,000 lbs. On this basis, and without taking into account the fact that the roots of most cultivated plants range far deeper than 9 inches, there is yet present about 2500 lbs. per acre of nitrogen, potash, and phosphoric acid in a soil containing only 0.1 per cent. of these constituents, which is about the lower limit usually found. The following table shows the amounts of these food materials—nitrogen, phosphoric acid, and potash—which are taken from the soil by an average crop grown in rotation.

Lbs. per acre.	Wheat.	Swedes.	Barley.	Clover.
Nitrogen . . .	41.7	94.0	49.0	159.3*
Phosphoric Acid . .	20.5	24.1	20.7	28.2
Potash . . .	36.5	93.5	35.7	102.4

* Partly derived from the atmosphere.

It is clear from a comparison of this table with the quantities previously specified, that even the poorest soil contains the nutrient material required by any ordinary crop many times over, yet we know that crops respond vigorously to dressings of manure which only add a fraction to the plant food already stored in the soil. For example, a wheat crop on poor soil would often be doubled by the use of 2 cwt. of nitrate of soda per acre, *i.e.*, by the addition of 35 lbs. of nitrogen in nitrate of soda to a soil that already contained in the top 9 inches more than 2000 lbs. per acre. Again, 4 cwt. per

acre of superphosphate, containing about 60 lbs. of phosphoric acid, will in the usual rotation secure a swede crop, which would be very small without this dressing, though there may be already 2000 to 3000 lbs. of phosphoric acid in the soil. We are then driven to conclude that the nitrogen, potash, and phosphoric acid are present in the soil in some other mode of combination than the form in which they exist in manures: so that although they may be in the soil they are in such a state as to be very partially of service to the growing plant. Further evidence of the enormous stores of plant food in the soil and the comparative slowness with which they can be utilised may be obtained by considering the results obtained at Rothamsted, where on one plot wheat has been grown continuously without manure for fifty-seven years (to 1900). This plot yielded an average crop of 14 bushels of grain and $12\frac{3}{8}$ cwt. of straw for the twenty-four years 1852-75, and $11\frac{3}{4}$ bushels of grain and $8\frac{3}{4}$ cwt. of straw for the next twenty-four years, 1876-99; in the fifty-seventh it was still able to grow $12\frac{1}{4}$ bushels of grain and 9 cwt. of straw. It is calculated that during the last fifty years there have been removed from this plot about 900 lbs. per acre of nitrogen, 470 of phosphoric acid, and 760 of potash, *i.e.*, about 18, 9, and 15 lbs. per acre per annum respectively; yet from analyses made by the author of a sample taken in 1893 the surface soil to a depth of 9 inches still contained 0.11 per cent. of nitrogen, 0.114 per cent. of phosphoric acid, and 0.38 per cent. of potash soluble in strong hydrochloric acid, or 2750, 2850, and 9500 lbs. per acre respectively. The soil must therefore be regarded as possessing most of its plant food in states of combination that cannot be utilised by the plant, and these forms slowly pass, by weathering and other changes, into material which is available for the crop.

The plant food of the soil represents so much capital, and, as in many another business, but a small proportion of the capital is liquid at any given time: it is largely the object of cultivation to effect such a turn over of the capital as will liquidate some of it in a form available for the nutrition of the crop.

In the old systems of agriculture, before the land was enclosed, the whole crop was grown out of capital, nothing but labour was put into the soil: in which connection it is interesting to note that the original meaning of manure was to work by hand.*

It becomes important, then, to attempt to discriminate between the various forms in which the nitrogen, potash, and phosphoric acid may be present in the soil, according as they are soluble, or likely in a short time to become sufficiently soluble to reach the crop. In the case of nitrogen we know that of the various compounds such as proteids and proteid residues, amides, ammonia salts, and nitrates which can be detected in the soil, only the latter can enter the plant, but that, by processes of fermentation, all of the other compounds will eventually pass into the state of nitrate. Of the immediately soluble nitrogen compounds—nitrates, nitrites, and ammonia—a very small amount, varying from 5 to 200 lbs. per acre, is ever present in the soil at any given time, though the proportion is constantly renewed by fermentation processes.

Phosphoric acid also exists in the soil in many distinct compounds: in combination with carbon, etc., it is found in nuclein and lecithin, which in a more or less humified condition are found among the plant and animal residues: it also occurs as phosphate of the sesquioxides of iron and alumina; as tribasic, and

* Cf. Defoe, *Robinson Crusoe* (1719)—“The ground that I had manured or dug up for them was not great.”

probably also as dibasic phosphate of lime. Of these compounds the latter are undoubtedly the most soluble in either pure water or the carbonic acid charged water of the soil, but much must depend on the physical condition, as well as on the chemical combination, in which the material exists. For example, when using tribasic phosphate of lime as a manure, the softer phosphates, such as steamed bone flour, are more effective than the chemically similar but harder material in ground rock phosphate.

It is not so easy to classify the various compounds of potash existing in the soil: we know that as felspar passes into kaolinite there are intermediate stages of weathering in which the potash is gradually becoming more soluble in soil water, but it is impossible to isolate or classify the various hydrated silicates containing potash that must exist. Potash, again, which has once been dissolved, is caught and retained by the soil in various ill-defined compounds, some of which must reach the crop more rapidly than others.

The work then of soil analysis must be extended to include some investigation of the condition of the plant food in the soil, as well as its absolute quantity: it is not enough to determine what constituents are present with the view of making good the deficiencies, because there is always more than enough for many crops, inquiry must be rather directed towards finding how much is likely to reach the crop. The attempt to discriminate between the total and what may be termed the available plant food in the soil, *i.e.*, that which is in a form the crop can immediately utilise, has been made in two ways—by using the growing plant as an analytical agent, or by attacking the soil with very dilute acids, whose action is akin to the natural solvent agencies at work when the

plant is growing. The former process proceeds upon the assumption that any given plant has a certain average composition which it will acquire when freely supplied with all the elements of nutrition; if this plant be grown upon a soil deficient in one particular, that deficiency will be reflected in the analysis of the plant when fully grown. It is thus necessary to select a standard plant and grow it under normal conditions of manuring to ascertain the proportion that nitrogen, phosphoric acid, and potash usually bear to the ash. The selected plant is then grown upon the soil in question, gathered at the appropriate stage and analysed, when the composition of the ash, as compared with its composition under normal conditions, should give indications of the state of the soil. It cannot be said that the method has yet yielded results of any wide application, for though the composition of the ash of a plant does undoubtedly vary with that of the soil in which it has been grown, various disturbing factors come into play. For example, the presence in the soil of large quantities of a non-essential material like calcium sulphate or sodium chloride would lower the proportion that potash bears to the total ash without necessarily indicating any want of potash; again, the deficiency of a substance like nitrogen would be more seen in a general stunting of the whole development of the plant than in a comparative poverty of nitrogen in the final growth.

The method which is now very largely employed to determine the mineral plant food in the soil that may be regarded as immediately "available" for the crop, consists in attacking the soil with a very dilute acid, whose action shall be comparable with the natural solution processes bringing nutriment to the plant. The mineral matter finds its way by osmosis into the plant

in two ways: either from the natural soil water, or from the more concentrated solution formed in immediate proximity to the root-hairs by the attack of the acid cell sap upon the soil particles.

The natural soil water is constantly dissolving small quantities of phosphoric acid, potash, and other materials, in which it is aided by the carbonic acid it also contains; as this water passes by osmosis into the root-hairs it will carry with it the dissolved material, with the exception of any particular ion or radicle which has already attained in the cell sap a higher concentration than it possesses in the external soil solution. But if the soil water alone brought the mineral matter with it, not enough enters the plant to account for the observed facts. For example, the growth of a crop of a ton and a half of clover hay requires the transpiration through the leaves, and therefore the absorption at the root, of about 400 tons of water (see p. 86); the crop would also contain about 50 lbs. of potash. If then the crop derives all its mineral matter by the inflow of the soil water into the root without change, the 50 lbs. of potash must have been originally dissolved in the 400 tons of water passing through the crop, which means that the soil water contained as much as 0.006 per cent. of potash, a concentration never observed in humid climates. But the particular ions or radicles concerned in nutrition enter the root faster than the water does; they diffuse through the cell wall because the sap within is maintained in a less concentrated state as far as they are concerned than the external soil water, by the living cells of the plant constantly withdrawing them from solution.

The solvent action of the soil water may also be assisted by the cell sap of the root-hairs, which is

always distinctly acid in its reaction; these root-hairs are always very closely in contact with soil particles, and some of the acid may be supposed to diffuse outwards through the cell wall. Sachs has shown that a polished slab of marble is etched wherever the fine roots of a plant came in contact with it, and on the strength of this experiment, it is supposed that the cell sap is also a factor in bringing the minerals of the soil into solution for the plant. It is impossible to settle what share should be assigned to the sap in this matter of bringing the soil minerals into solution, nor, for purposes of analysis, is it essential to do so; the desideratum is a solvent that will dissolve the class of material which is found by experience to reach the immediate crop, but which will not touch the same material should its state of combination or physical condition be such as to render it unavailable for the plant.

A variety of solvents have been proposed: for example, Dehérain showed that dilute acetic acid, while dissolving some phosphoric acid from ordinary soils, was incapable of extracting any from a particular soil which yielded very poor crops unless manured with superphosphate, though it contained 0.1 per cent. of phosphoric acid soluble in strong hydrochloric acid. Hence he concluded that dilute acetic acid forms a solvent only capable of attacking the available phosphoric acid. A solution of carbonic acid has been suggested as akin to the natural soil water; other solutions have been employed because they will dissolve certain of the compounds of phosphoric acid in the soil, but not all—the calcium phosphates, for example, but not the phosphates of iron and aluminium; other solvents, again, are recommended as akin to the acid cell sap. However, experience seems to show that the 1 per cent. solution of citric acid pro-

posed by Dyer in 1894 gives results that are most in accord with what is known of the soil, either from its past history or by cropping experiments.

The method of conducting the analysis is as follows :—200 grams of the “fine earth” that has passed the 3 mm. sieve, in its air-dried state, is placed without any further grinding in a dry Winchester quart bottle with 20 grams of pure crystallised citric acid and 2 litres of water. The bottle should either be one previously used for the storage of strong acids, or should have a preliminary soaking in dilute hydrochloric acid. The mixture of soil and dilute acid is thoroughly shaken from time to time, as often as may be convenient, during the seven days the solvent action is allowed to proceed. After seven days the solution is filtered, and two aliquot portions of 500 c.c. each are evaporated to dryness and ignited to get rid of the citric acid and other organic matter. The residues are dissolved in hydrochloric acid, again evaporated and heated for a time to 105°C . to render all the silica insoluble. In one portion the phosphoric acid, and in the other the potash, are determined by the processes previously described.

An examination of the citric acid solution seems to show that all the compounds of phosphoric acid that have been indicated as existing in the soil are more or less attacked; at any rate the resulting solution contains organic matter and salts of aluminium and iron, in addition to calcium. It has been suggested that the varying amounts of calcium carbonate contained by soils will much affect the material dissolved by the citric acid, a varying proportion of which becomes neutralised by the calcium carbonate. To some extent this is probably true, as it has been shown that the attack of the citric acid on a given soil is diminished if calcium carbonate is added to the soil before extraction. However, few soils

contain sufficient calcium carbonate to neutralise any large proportion of the citric acid (10 grams of which would require 7 grams of calcium carbonate per 100 of soil), and both the calcium citrate formed and the carbonic acid liberated have themselves a certain solvent effect. It is better to accept the variations introduced by the calcium carbonate than to attempt the addition of an extra amount of citric acid to compensate for that which has been neutralised.

The quantity of phosphoric acid or potash dissolved bears no constant relation to the total quantities that may be present in the soil. The following table shows both the total and the "citric acid soluble" phosphoric acid and potash in the soil from six of the plots of the Broadbalk Field, Rothamsted, which have been growing wheat continuously, with the same manures each year, for fifty years. It will be seen that the soil of the continuously unmanured plot, which has received nothing for the whole period, still contains 0.114 per cent. of phosphoric acid, or about half as much as the soil of the plot which has received every year $3\frac{1}{2}$ cwt. per acre of superphosphate [=64 lbs. of phosphoric acid]; in both cases the amount of phosphoric acid in the soil is enormous. When, however, the amounts of citric acid soluble or "available" phosphoric acid are compared, the continuously manured plot is found to contain six times as much as the unmanured plot; thus the latter method of analysis discriminates sharply between the two plots, and corresponds much more closely to what we should suppose from the past history of the plots would be their relative richness or poverty in phosphoric acid. As regards potash, the results are still more striking: the Rothamsted soil contains enormous reserves of potash, amounting to 2 per cent. or more, and the proportion which goes

into solution in strong hydrochloric acid (about 0.5 per cent.) is much the same for all the plots. But from the continuously manured plots the 1 per cent. citric acid solution dissolves about ten times as much as from the plot which has received no manure. The further figures in the table give two other cases examined by the author, which show how the requirements of a soil for a particular mineral manure can be more closely estimated by a consideration of the material dissolved by a 1 per cent. solution of citric acid than from the material dissolved by strong hydrochloric acid.

Plot.	Manuring.	Phosphoric Acid in		Potash in	
		Strong HCl.	1 per cent. Citric Acid.	Strong HCl.	1 per cent. Citric Acid.
3	Unmanured	0.114	0.008	0.380	0.0043
5	Minerals (64 lbs. P_2O_5 , 100 lbs. K_2O) only	0.228	0.051	0.463	0.0458
6	Minerals + 200 lbs. Ammonia Salts	0.195	0.045	0.530	0.0322
7	" + 400 lbs. "	0.191	0.040	0.500	0.0233
9A	" + 275 lbs. Sodium Nitrate	0.164	0.029	0.440	0.0272
2B	Dung	0.209	0.048	0.453	0.0400
I.	0.104	0.003	0.313	0.025
II.	0.110	0.008	0.439	0.011
C.P.	0.179	0.010

I. is a clay soil, on which field trials had shown the hop crop would respond freely to dressings of phosphoric acid but not to potash.

II. is a sandy soil on which hops showed no special response to phosphoric acid, but considerable increase of crop when potash was applied. The use of strong hydrochloric acid would indicate that both soils are about equally well provided with phosphoric acid, but

that II. is richer than I. in potash; whereas the comparative results given by the weak citric acid are in accord with the manurial experiments.

On the whole the method suggested by Dyer provides the analyst with information about the soil which is much more in accord with experience than any other, so that it may be used with a fair degree of confidence for the guidance of the cultivator in the practical question of what manures to employ.

An ordinary arable soil should show at least 0.01 per cent. of phosphoric acid and potash respectively soluble in the 1 per cent. solution of citric acid; less than this indicates the need of special mineral manuring even for crops like cereals. Of course for swedes and similar crops a much higher limit of "available" phosphoric acid is required; similarly for potash when potash-loving crops like mangolds or potatoes are to be grown. The figures marked C.P. in the preceding table give the potash in a soil which experiments showed to contain enough potash for cereal, but not for swede crops.

Some consideration must also be paid to the type of soil: for phosphoric acid at least, the limit of 0.01 per cent. is probably low for pasture and all soils rich in organic matter, and high for sandy soils.

In pastures and other soils rich in humus, there are organic compounds of phosphorus which dissolve in the citric acid, but reach the plant very slowly; in sandy soils there seems to be often a large proportion of ferric phosphate which the plant can attack better than the citric acid.

It should not be supposed that the whole of the so-called "available" phosphoric acid or potash will be removed by the crop; even the minimum suggested of 0.01 per cent. means about 250 lbs. per acre in the

surface layer 9 inches deep: and few crops will take away as much as 50 lbs. per acre of phosphoric acid or 150 lbs. per acre of potash. No crop searches the soil so thoroughly for food as is done by the solvent acid: if we assume that the roots themselves by their acid sap effect some of the solution, it is obvious that they come in contact with but a small proportion of the soil particles; nor can the soil water, limited in amount and moving slowly, attack the soil with the vigour displayed by the weak acid in the laboratory, which is continuously shaken with a comparatively small proportion of soil. Even in the case of material so essentially "available" as a manure soluble in water, the whole of the manure applied is never recovered in the crop; *e.g.*, in the experiments with wheat at Rothamsted, 95 per cent., and with mangolds 78 per cent., of the nitrogen supplied as nitrate of soda has been recovered in the crop, though there was an abundant supply of the other manurial constituents. In the same way, on the plot with an excess of nitrogen there was recovered only 36 per cent. of the phosphoric acid supplied as superphosphate, and 50 per cent. of potash supplied as sulphate of potash.

In other words, the "available" plant food in the soil represents not that which the succeeding crop will remove, but that which it can draw upon: how much it will acquire will depend on a variety of factors, such as the nature of the plant, the texture of the soil, the supply of water, and other necessities of nutrition.

No method akin to solution in dilute citric acid has yet been devised for determining what proportion of the nitrogen reserve in the soil is likely to be available. The conversion of the nitrogenous matter of the soil into soluble nitrates, in which form nitrogen enters the plant, is a biological process which is influ-

enced by a number of conditions, such as temperature, degree of moisture and aeration of the soil, the mechanical treatment it receives, all impossible to predict.

Some idea of the condition of the organic matter and the readiness with which it is likely to change, may be obtained by a determination of the humus soluble in dilute ammonia (p. 49), or again by a study of the ratio of carbon to nitrogen in the organic matter as previously indicated (p. 44). There are not, however, sufficient data to enable one to attach much weight to either of these factors.

In the analysis of a soil, without doubt the most important figure is the proportion of calcium carbonate, for on that must be based the decision not only of whether liming is necessary, but what class of artificial manures should be employed. Where the calcium carbonate is scanty, manures like superphosphate and sulphate of ammonia should never be employed, but basic slag or some neutral phosphate on the one hand, and nitrate of soda as a source of rapidly acting nitrogen on the other. The texture of the soil, the rapidity with which decay and nitrification of organic matter take place, freedom from fungoid diseases, all depend on an adequate proportion of calcium carbonate in the soil, say from half to one per cent., so that of all the determinations this is the most important.

The determinations of the loss on ignition, the nitrogen, and possibly the humus, give the analyst an idea of the reserves of organic matter in the soil; judged in conjunction with the mechanical analysis and the proportion of calcium carbonate, an opinion can be formed as to the condition of the soil and how far these reserves are likely to be brought into play by cultivation. An opinion may again be formed as to the need for organic manures to increase the humus content of

the soil, or whether fertility is likely to be maintained with purely mineral manures.

A consideration of the available phosphoric acid and potash will give the analyst an idea of the immediate need or otherwise of mineral manuring; the proportions these bear to the "total" phosphoric acid and potash give him grounds for deciding whether the lack is only temporary or real. In the former case measures may be taken to liberate some of the reserves, as by the judicious use of lime, or of organic manures which will generate carbonic and other acids within the soil.

Such further questions as the presence of harmful substances, or even of an excess of more normal constituents of the soil must be considered by the analyst, but will be dealt with in a later section.

In some cases it will be possible by a chemical analysis to pronounce a given soil to be unsuited to a particular crop: as a rule, however, it is not its chemical composition which fits the land for a particular crop, but its mechanical texture, water-bearing power, drainage, etc. In most cases the soil can be adjusted to the crop by manure, though the process may be unsound from an economic standpoint, but no expenditure can ever rectify unsatisfactory texture, *e.g.*, convert a light sand into good wheat land.

Even in considering the chemical analysis of a soil, no hard and fast rules can be laid down, the judgment and experience of the analyst must come into play in deciding how far the deficiency or excess of one constituent is likely to affect the action of some of the others: and again, how far the texture, the aspect, and other factors that can only be ascertained *in situ*, will exercise an influence upon the enormous reserves of plant food contained in every soil.

CHAPTER VII

THE LIVING ORGANISMS OF THE SOIL

Decay and Humification of Organic Matter in the Soil—Alinit—
The Fixation of Free Nitrogen by Bacteria living in Sym-
biosis with Higher Plants—Nitragin—Fixation of Nitrogen by
the Soil—Nitrification—Denitrification—Iron Bacteria—Fungi
of Importance in the Soil : Mycorhiza, and the Slime Fungus
of "Finger-and-Toe."

THE soil is the seat of a number of slow chemical changes affecting the organic material it receives: residues of an animal or vegetable nature, when applied to the soil, are converted into the dark coloured complex known as "humus," which becomes eventually oxidised to carbonic acid, water, nitric acid, and other simple substances serving as food for plants. These changes, at one time regarded as purely chemical, are now recognised as dependent upon the vital processes of certain minute organisms, universally distributed throughout cultivated soil, and subject to the same laws of nutrition, multiplication, life and death, as hold for the higher organisms with which we are more generally familiar.

The microscopic flora of the soil, roughly classed as fungi and bacteria, is vast, and has been very inadequately explored as yet: certain types of change

in the soil materials have, however, been associated with particular organisms or groups of organisms, and many of these changes are of fundamental importance in the ordinary nutrition of plants. The organisms in the soil which so far have received the chief attention are those concerned with the supply of nitrogen to the plant. Certain organic compounds of nitrogen, chiefly of a proteid nature, become gradually broken down by the action of soil bacteria into simpler compounds, *e.g.*, into amides, and then ammonia, which latter substance is seized upon by other organisms and oxidised successively to nitrous and nitric acid. As nitric acid is almost the only form in which the higher plants obtain the nitrogen they require, the fertility of the soil is wholly bound up in the maintenance of this cycle of change. Under certain conditions the work of other organisms intervenes, and the nitrogen compounds, instead of becoming nitric acid, are converted into free nitrogen gas, and are lost to the soil. *Per contra*, another group of organisms possess the power of "fixing" free nitrogen, *i.e.*, of taking the gaseous element nitrogen and combining it with carbon, hydrogen, oxygen, etc., into forms available for the higher plants. Such organisms seem to act mainly when living in "symbiosis" with plants possessing green carbon-assimilating tissue: the two form a kind of association for mutual support, the bacteria deriving the carbohydrate which they must consume from the higher plant supplied by them with combined nitrogen.

Other symbiotic processes have been traced in the soil, and may yet be made to play an important part in the nutrition of field crops. Indeed, a number of tentative trials have already been made with the view of increasing the productiveness of the soil by introducing either useful organisms that were wanting, or

improved types to replace already existing kinds of less effective character.

The Changes of Organic Matter in the Soil.

The surface layer of soil is constantly receiving additions of organic matter, either leaves and other debris of vegetation covering the ground, together with the droppings of animals consuming that vegetation, or dung and other animal and vegetable residues which are supplied as manures to cultivated land. These materials rapidly change in ordinary soil, losing almost immediately any structure they possess, becoming dark-coloured humic bodies, or even burning away as thoroughly as if placed in a furnace. That these changes are due to micro-organisms is seen by their immediate cessation if the soil be treated with anti-septics like chloroform or mercuric chloride: or if the mixture of soil and organic matter be sterilised by heating. Attempts have been made to estimate the number of bacteria contained in the soil: the prodigious numbers obtained, up to 1,000,000 or more per cubic centimetre of the upper soil, show little beyond the fact that the soil is tenanted much as any other decaying organic material would be. The soil bacteria are always associated with a certain number of fungi and yeasts, especially when the reaction of the medium is at all acid: the organisms are most numerous in the surface layer, though they are still to be found in the deepest subsoils. Below a certain depth they must disappear, because deep well water often comes to the surface in an absolutely sterile condition. The changes which organic materials undergo in the soil may be roughly grouped into two classes; according as there is free access of oxygen or not, either decay (eremacausis),

with eventual resolution into the simplest inorganic oxidised compounds, or "humification" will set in. These changes can be best illustrated by the fate of a dead branch when it falls either upon the ground or into a pond or swamp, where it becomes buried in the mud at the bottom. In the latter case the fermentation changes cause the wood to darken even to blackness, gases like carbonic acid and marsh gas are split off, so that the material becomes proportionally richer in carbon and poorer in oxygen. Eventually, however, the process slackens, the losses practically cease, and a large proportion of the original material persists. On the other hand, the branch exposed to the air, without darkening very much, becomes slowly resolved by the action of fungi and bacteria into carbonic acid and water, ammonia, nitrogen gas, and mineral salts, with much the same final result as though it had been placed in a furnace. In soil, both these types of change may go on, and the conditions of the soil as regards aeration, drainage, temperature, and cultivation, determine which will predominate.

Practically, the whole group of aerobic bacteria, *i.e.*, those which require free oxygen for their development, and fungi are capable of bringing about the oxidation changes which result in the production of carbonic acid, the combustion of some carbohydrate or other being essentially the means by which they derive their energy. As an intermediate step between the carbohydrate and the carbonic acid, a certain amount of humus is produced—"mould," or the "mild humus" of the German writers. Examples of this material can be seen in the leaf mould collected by gardeners from woods, or the fine, brown powder which can be scraped out of the inside of a hollow tree, particularly of a willow; this mould differs from the peaty humus,

to be described later, in its neutral reaction and in the readiness with which it can be further oxidised. Neutral in its reaction, it yields but little soluble "humic acid" to the attack of an alkali.

Besides carbohydrates, most aerobic bacteria require some carbon compound of nitrogen, and will begin to break down proteid and other nitrogen-containing materials. The products of their attack are successively peptones, bodies like leucin and tyrosin, eventually ammonia, and probably free nitrogen, but the ultimate production of ammonia is perhaps the most characteristic feature of the aerobic fermentation of proteid bodies. Other amides are also resolved into ammonia, of which a characteristic example is afforded by the change of urea into ammonium carbonate. This process [which is one of hydrolysis, not of oxidation, being represented in the gross by the equation $\text{CO}(\text{NH}_2)_2 + 2 \text{H}_2\text{O} = (\text{NH}_4)_2\text{CO}_3$] is brought about by more than one organism, universally distributed and abundant in such places as stables and cattle stalls. In warm weather the conversion of the urea of the urine into ammonium carbonate is very rapid, and as the resulting product dissociates into gaseous ammonia and carbonic acid, to this cause is due the smell of ammonia which is always to be noticed in such places. These changes to ammonia are the necessary preliminaries to the final oxidation process or nitrification, which, as the means by which the higher plants receive their supplies of nitrogen, will be discussed separately. The various oxidation processes in the soil are, like all other bacterial actions, promoted by a certain warmth, the optimum temperature being about 35° , by a sufficiency of moisture, and by the presence of mineral food, like phosphates and potash salts. In any great quantity, however, salts are harmful,

particularly sodium chloride; an acid reaction also diminishes considerably the rate of decay. Speaking generally, bacteria do not thrive as soon as the medium passes the neutral point, and all the decay processes must be carried out by the development of fungi when the medium is acid. The presence of chalk, or any form of carbonate of lime, by neutralising any acids as fast as they are formed, promotes the destruction of organic matter. Wollny has also shown that calcium humate will oxidise much more rapidly than uncombined humic acid placed under similar conditions. To the absence of carbonate of lime and mineral salts generally, may, perhaps, be ascribed the tendency of humus to accumulate and persist on the very light, sandy heaths, where the soil is dry and hot in summer, and also well aerated. It has already been indicated, in treating of humus, that the various organic compounds of nitrogen show very different susceptibility to the breaking-down process which eventually renders the nitrogen available for the crop—amongst the most resistant substances being the nucleoproteids in the undigested portions of food which form dung, and the humus residues from poor, cropped-out land. As in all cases much of the nitrogen of both soil and manure seems to pass into obstinately persistent compounds yielding slowly, if at all, to oxidation, and hence becomes wasted to the farmer, an attempt has been made to increase the preliminary breaking down of nitrogen compounds in the soil by the introduction of certain very active bacteria. Stoklasa has shown that various organisms—*B. megatherium*, *B. fluorescens*, etc.—when seeded into soil manured with bone meal or similar materials, increase both the nitrogen and the phosphoric acid obtained by the plant. A pure cultivation of some such organism, *B. Ellenbachensis*,

is sold commercially under the name of *alinit*, and though the power of fixing nitrogen has been claimed for it, its chief action, is probably such as is described above. It has been found to cause increased crop returns on peaty or other soils rich in humus, or where slow-acting nitrogenous manures have been applied.

The fermentation which goes on in absence of oxygen, or "putrefaction," is brought about by a large number of bacteria, some of which are only active in the absence of oxygen, others are aerobic, but will continue their work when deprived of free oxygen. Carbohydrates are decomposed with formation of carbonic acid and other gases like hydrogen and marsh gas, butyric and other fatty acids, a residue of humus being always produced at the same time. The proteid bodies readily undergo putrefactive change, with the production of tyrosin and various amido-bodies, fatty acids, ammonia, phenol and other bodies containing an aromatic nucleus, gaseous compounds of sulphur, etc. In the main, however, the putrefactive changes of organic material in the soil fall upon the cellulose and other carbohydrates; these lose carbonic acid, marsh gas, hydrogen, etc., and become humus with a gradually increasing porportion of carbon; the nitrogenous materials resist attack more than the carbohydrates, and hence tend to accumulate, so that an old sample of deep-seated peat is richer in nitrogen than a more recent sample taken from nearer the surface. Finally, the humus thus produced, which may be called peat, is essentially an acid product, and even when aerated and supplied with mineral materials will oxidise with extreme slowness.

The Fixation of Free Nitrogen.

In the earliest theories regarding the nutrition of the plant which were accepted after chemistry had become an exact science, it was considered that the plant derived its nitrogen from the humus of the soil, as, for example, in de Saussure's statement that "Plants receive their nitrogen almost entirely by the absorption of the soluble organic substances." This view was displaced by the so-called "mineral theory" of Liebig, who, in laying down the broad principle that the plant only derived certain necessary mineral constituents, its "ash," from the soil, and the whole of its carbon compounds from the atmosphere, was led to regard the nitrogen as well as the other combustible matters of the plant as due to the atmosphere. Boussingault had already shown, by weighing and analysing the crops on his own farm for six separate courses of rotation, that from one-third to one-half more nitrogen was removed in the produce than was supplied in the manure. The gain of nitrogen was little or nothing when cereal crops only were grown, but became large when leguminous crops were introduced into the rotation. Liebig, however, considered that cereals, as well as the other plants, were able to draw their ammonia from the atmosphere, and that, provided sufficient mineral plant food were forthcoming, there was no need of ammonia compounds in the manure.

This view of Liebig's, though modified later, when he admitted that cereals must obtain their nitrogen from a manurial source in the soil, led to considerable investigation of the source of the nitrogen in the plant. Boussingault himself carried out a long series of laboratory experiments, in which weighed seeds con-

taining a known proportion of nitrogen were grown in artificial soils containing no nitrogen, but supplied with the ash constituents of the plant. Care was taken to remove all ammonia from the air in which the plants were grown, and from the water and carbonic acid supplied to them; finally, after growth had ceased, the amount of nitrogen in the plant and in the soil was determined. In some cases a known quantity of nitrogenous compounds was supplied as manure; but all the results went to show that there was no gain of combined nitrogen during growth; the seed and manure at starting contained as much nitrogen as was found in the plant and soil at the end.

Similar experiments were carried out with the utmost precautions by the Rothamsted investigators, who likewise found no gain of nitrogen by the plant from the atmosphere. The following results, obtained by Lawes and Gilbert in 1858, will serve to show the agreement between the nitrogen supplied and recovered:—

	Nitrogen in Seed (Grams).	Nitrogen in Soil and Plants (Grams).	Gain or Loss.	Nitrogen in Seed and Manure.	Nitrogen in Soil and Plants.	Gain or Loss.
Wheat . .	0.0078	0.0081	+ 0.0003	0.0548	0.0536	- 0.0012
Barley . .	0.0057	0.0058	+ 0.0001	0.0496	0.0464	- 0.0032
Oats . .	0.0063	0.0056	- 0.0007	0.0312	0.0216	- 0.0096
Beans . .	0.0750	0.0757	+ 0.0007	0.0711	0.0655	- 0.0056
Peas . .	0.0188	0.0167	- 0.0021	0.0227	0.0211	- 0.0016
Clover	0.0712	0.0665	- 0.0047
Buckwheat .	0.0200	0.0182	- 0.0018	0.0308	0.0292	- 0.0016

From all these experiments the conclusion was drawn that cultivated plants were unable to "fix" atmospheric nitrogen, but obtained this indispensable element in a combined state from the soil like the ash

constituents; and such was the opinion that prevailed for something like thirty years.

Notwithstanding the conclusive nature of all the laboratory experiments, there was still a residuum of facts obtained under field conditions which were inexplicable on the theory of the non-fixation of nitrogen, and these facts were chiefly connected with the growth of leguminous crops.

Boussingault's crop statistics have already been referred to; the following table gives a short summary of the kind of results he obtained :—

Rotation.	NITROGEN. Kilos per hectare.	
	Supplied in Manure.	Removed in Crop.
Wheat, Wheat, Fallow	87.2	82.8
Potatoes, Wheat, Clover, Wheat or Turnips, Oats	202.2	268.5
Potatoes, Wheat, Clover, Wheat	182	339
Lucerne, 5 years	1035

The amount of nitrogen removed was equal to that supplied when only wheat was grown, but became progressively greater the more frequently leguminous crops occupied the ground.

At Rothamsted the following average quantities of nitrogen were removed per acre per annum in the crop, when mineral manures only were applied :—

Wheat (24 years)	22.1
Barley (24 years)	22.4
Roots (30 years)	16.4
Beans (24 years, only 21 years in Beans)	45.5
Red Clover (22 years, only 6 years Clover)	39.8

In this case also the amount of nitrogen in the

produce was much increased by the presence of a leguminous crop.

Another of the Rothamsted experiments shows still more strikingly the accumulation of nitrogen by a leguminous crop. A piece of land which had been cropped for five years by cereals, without any nitrogenous manure, was divided into two portions in 1872, one being sown with barley alone, and the other with clover in the barley. In 1873 barley was again grown on the one portion, but the clover on the other, three cuttings of clover being obtained. Finally, in 1874, barley was grown on both portions. The quantities of nitrogen removed in the crops of 1873 and 1874 are shown in the table.

NITROGEN IN CROP—LBS. PER ACRE.

1873	Barley .	37.3	1874	Barley .	39.1
"	Clover .	151.3	"	Barley .	69.4

Thus, the barley which followed clover obtained 30.3 lbs. more nitrogen than the barley following barley, though the previous clover crop had removed 114 lbs. more nitrogen than the first barley crop. An analysis of the soil was made in 1873, after the clover and barley had been removed; this showed down to the depth of 9 inches an excess of nitrogen in the clover land, despite the larger amount which had been removed.

In Soil after Barley	.	0.1416	per cent. Nitrogen.
In Soil after Clover	.	0.1566	" "

In another experiment, land which had previously grown beans and then been fallow for five years, was sown with barley and clover in 1883, the clover being allowed to stand in 1884 and 1885. At starting the soil was analysed; the surface 9 inches contained on an average 2657 lbs. per acre of nitrogen, while of

nitrogen as nitric acid the soil only contained 24.7 lbs. per acre down to a depth of 6 feet. As a result of the three years' cropping with barley and clover, and then with clover only, an average amount of 319.5 lbs. of nitrogen was removed, yet the soil contained, on analysis at the end of the experiment, 2832 lbs. of nitrogen per acre in the top 9 inches, or a gain of 175 lbs. per acre in the three years, making a total, with the crop removed, of nearly 500 lbs. of nitrogen per acre to be accounted for.

The consideration of field trials of this description led many observers to think that there still might be some fixation of free nitrogen, particularly by leguminous plants. Voelcker, in England, when discussing the power of a clover crop to accumulate nitrogen expressed the opinion that the atmosphere furnishes nitrogenous food to that plant; in France, it was maintained by Ville; Berthelot also brought evidence to show that the soil itself, by the aid of its microscopic vegetation, assimilated some free nitrogen. Even in the laboratory experiments, some of Boussingault's results, and others of Atwater, in America, showed a gain of nitrogen. But the clearing up of the whole subject came with the publication, in 1886, of the researches of Hellriegel and Wilfarth. These investigators found that when plants were grown in sand and fed with nutrient solutions, the Gramineæ, the Cruciferae, the Chenopodiaceæ, the Polygoneæ, grew almost proportionally to the amount of combined nitrogen supplied; and, if this were absent, nitrogen starvation set in as soon as the nitrogen of the seed was exhausted. With the Leguminosæ, however, a plant was observed sometimes to recover from the stage of nitrogen starvation, and begin a luxurious growth which lasted until maturity, though no com-

bined nitrogen was supplied. In such cases the root of the plant was always found to be set with the little nodules characteristic of the roots of leguminous plants when growing under natural conditions. Further experiments were made in which the plants were grown in sterile sand, but as soon as the stage of nitrogen hunger was reached, a small portion of a watery extract of ordinary cultivated soil was added; whereupon the plants receiving the extract recovered from their nitrogen starvation and grew to maturity, assimilating considerable quantities of nitrogen. The renewed growth and the assimilation of nitrogen were always found to be attendant upon the production of nodules on the roots. The nodules were found to be full of bacteria, to which the name of *B. radicicola* has been given. They could only be produced by previous infection either by an extract of the crushed nodules, or from a cultivated soil; in some cases (lupins, serradella) only by soil which had previously carried the same crop.

These results, though not at first accepted by Lawes and Gilbert, led to a repetition of their earlier experiments, which brought out the fact that the necessary inoculation had always been wanting through the great care that had been taken to prevent the entry of any accidental impurity. Eventually both at Rothamsted and by other investigators, the conclusions of Hellriegel and Wilfarth were confirmed, that when leguminous plants are grown under sterile conditions, without a supply of combined nitrogen there is very limited growth, no formation of nodules, and no gain of nitrogen. But when the culture is seeded with soil extract there is luxuriant growth, abundant nodule formation, and, coincidentally, great gain of nitrogen many times as much in the products of growth as in the seed sown. Gilbert also showed that there

is a gradual accumulation and then withdrawal of nitrogen from the nodules. Lastly, Schloesing *fls* and Laurent, by growing Leguminosæ in closed vessels, and analysing the air before and after growth, found an actual disappearance of nitrogen gas, agreeing with the amount gained by the plant during growth. Thus, a conclusion was reached that the leguminous plants can assimilate and fix the free nitrogen of the atmosphere by the aid of bacteria, living symbiotically in the root nodules,—a conclusion which served to explain, not only the discrepancies in the previous experiments, but the long accumulated experience of farmers that crops like clover and lucerne enrich the soil and form the best preparation for cereals like wheat, which are particularly dependent on an external supply of nitrogen.* The mechanism of the fixation of free nitrogen is still incompletely understood. Mazé maintains that the bacteria are able to fix free nitrogen when cultivated in media apart from the leguminous plants, but the amount fixed under these conditions is small compared with that fixed by a leguminous plant on whose roots nodules are well developed. To fix the nitrogen, some expenditure of energy must be required, which is probably derived from the combustion of carbohydrate supplied to the bacteria by the higher plant, as it has been observed that the nitrogen fixation and general growth of the Leguminosæ is stimulated by a supply of sugar, or other carbohydrate, to the soil. Much investigation has also been applied to the question of whether there is only one kind of bacterium living in symbiosis with all the Leguminosæ, or whether there are not definite races appropriate to each species of leguminous plant, and alone capable of bringing about nitrogen fixation to the full extent. The earliest

* Cf., Vergil, *Georgics*, I. 73.

investigations had already shown that lupins and serradella did not develop nodules when infected with an ordinary garden soil, but only when an extract was added from a sandy soil on which these plants had been previously grown; and Nobbe brought further evidence to show that, though there is very widely distributed in the soil an organism which will cause some nodule formation and fixation of nitrogen, yet it becomes so modified by growing in symbiosis with the different leguminous plants, that the best results are only obtained when each species is directly infected from nodules taken from the same kind of plant.

Accordingly, he proceeded to the introduction, on a commercial scale, of pure cultivations of the races of bacteria appropriate to each of the leguminous plants grown as field crops. This jelly-like material called "Nitragin" is to be dissolved in a large bulk of water and sprinkled over the seed before sowing; thus, inoculation with the appropriate organism, which might not happen to be present in the soil, was ensured, and in consequence a large increase of crop. It cannot be said that nitragin has fulfilled the expectations which were formed at its introduction; at any rate, on the British soils which have long been under cultivation, very rarely has a previous inoculation of the seed resulted in any gain of produce. Even when species of *Vicia*, etc., never previously grown on the land, have been sown with and without inoculation, or when southern plants like lucerne have been started much further north, where they have not been seen before, nodule formation has been free enough without any inoculation. Nor has there been any increase of crops from the inoculation. Cases have, however, occurred where lucerne and sainfoin grown in Scotland have failed to develop nodules, except after a previous in-

fection, brought about by mixing in the land a little soil brought from the south of England on which these crops had been regularly grown. Inoculation with the specific nitragin organism has also failed to make lupins, serradella, and similar sand-loving leguminous plants grow properly on a soil containing carbonate of lime.

Inoculation with soil from a field which has previously grown the crop about to be sown has often proved a signal success in reclaiming the poor heath lands of East Prussia, by the system of green manuring worked out by Dr Schultz at Lupitz. Very large areas of barren sandy heath land have been reclaimed and rendered fit for the cultivation of the ordinary crop by a system of growing lupins and ploughing in the green crop. Mineral manures alone are employed, latterly basic slag and the Stassfurt potash salts; the lupins accumulate nitrogen from the atmosphere, thus gradually there is built up both humus to bind together the loose sand and make it retentive of moisture, and also a store of nitrogen for the nutrition of succeeding crops. The soil of a field growing lupins every year from 1865 was found in 1880 to contain 0.087 per cent. of nitrogen in the surface 8 inches, as compared with 0.027 per cent. in an adjoining pasture. By 1891 the proportion of nitrogen had increased to 0.177 per cent., despite the annual removal of the lupin crop and the fact that the manuring had been with phosphates and potash only. It is in reclaiming these heath lands which have not previously been under cultivation, nor, in many cases, carried any leguminous vegetation whatever, that soil inoculation from land previously cultivated, or with nitragin, has given successful results. Dr Salfeld of Hanover has recorded several cases of

the successful cultivation on a large scale of various leguminous plants, beans, clover, serradella, lupins, only after previous inoculation with soil. The experiments were made on both peaty (moor) and sandy soils, on which, without inoculation, leguminous plants made but little growth and developed no nodules. Success followed when about 8 cwt. per acre of soil from a field which had previously carried the crop in question were sown broadcast over the land in April, and harrowed in just before seeding. In one case, over 7 tons per acre of green serradella were grown where the land had been treated with 8 cwt. of soil from an old serradella field, the crop failing after germination where no inoculation was practised.

Fixation of Free Nitrogen by the Soil.

As already indicated, Berthelot attributed to the soil itself the power of fixing a small quantity of atmospheric nitrogen, a power which was lost when the soil was sterilised and maintained under conditions preventing infection. This gain of nitrogen is independent of the small amount of ammonia absorbed by soil from ordinary air, which always contains a trace of ammonia; eventually it was attributed to the microscopic green algæ which clothe the surface of ordinary moist soil. The experiments of Kossowitsch, and of Krüger and Schneidewind, have, however, shown that when working with pure cultures of these algæ, their growth is dependent on a supply of combined nitrogen, and that either in its presence or absence no fixation of free nitrogen takes place. It is possible, however, that they may live in symbiosis with nitrogen-fixing bacteria and supply the carbohydrate, by the combustion of which the energy needed for the fixation of nitrogen by the bacteria is obtained. Winogradsky has isolated an

organism which, when grown under anaerobic conditions and supplied with soluble carbohydrate, breaks the latter down with the formation of butyric and other acids, and at the same time draws some of the gaseous nitrogen present into combination. It has yet to be ascertained if the direct fixation of nitrogen by bacteria plays any really important part in re-creating the store of combined nitrogen in the soil.

Nitrification.

It has long been known that any organic compound of nitrogen when applied to the soil becomes eventually oxidised to a nitrate, which is practically the only compound of nitrogen taken up by cultivated plants, the Leguminosæ excepted. The potassium nitrate collected from Indian soils, the calcium nitrate made artificially in nitre beds in Europe, owe their origin to this oxidation of organic compounds of nitrogen. That the process was a biological one was first indicated by Müller in 1873, but any widespread recognition of the fact did not take place before the work of Schloesing and Müntz in 1877. These investigators showed that the formation of nitrates in the soil ceased at temperatures below 5° and above 55°C., that it could be stopped by chloroform vapour and similar antiseptics, and that the soil lost entirely its power of nitrification if it were heated to the temperature of boiling water. The investigations of Warington confirmed these results, and brought to light the further fact that there were two stages in the oxidation process, one being the formation of a nitrite, followed by the conversion of this nitrite into the completely oxidised product. It was found possible to obtain cultures which would only push the oxidation to the nitrite stage, thus indicating that there must be at least two organisms concerned in the complete nitrification

process. The further study of the organisms was for a long time hindered by the fact that they could not be got to grow upon the gelatinous media employed in the ordinary methods of isolating specific bacteria; and though P. F. Frankland, by a dilution method, succeeded in isolating and describing a nitrifying bacterium, it was not until 1890 that Winogradsky cleared up the problem. He prepared a nutritive medium with silica in its gelatinous form as a basis and containing no organic matter, and thus was able to separate nitrifying bacteria from the large number of other species simultaneously present in the soil. Winogradsky was able to isolate two species of bacteria capable of transforming ammonia compounds into nitrites. One of these, termed *Nitrosomonas europæa*, was obtained from all the soils of the old world he examined; the other, ascribed to the genus *Nitrococcus*, was peculiar to the soils of America and Australia. The former occurs both as a single, free swimming form, and clustered together in a colony or zooglœa state.

Finally, there appears to be one type of organism only, included in the genus *Nitrobacter*, which oxidises the nitrite to nitrates. Winogradsky and other observers have worked out the conditions of life of these nitrifying organisms—the limits of temperature for their growth, 5° and 55° C., have already been given, the optimum temperature is about 37° C. Their action is much restrained by the presence of organic matter, or any quantity of alkaline carbonates or chlorides; at the same time, some base must be present to combine with the nitrous or nitric acids produced, for their activity ceases as soon as the medium becomes at all acid. Munro has shown that, while calcium carbonate is the substance which, as a rule, is effective to this end, many organic salts will also supply the

necessary base. The organisms are able to obtain the carbon necessary to their growth from carbonates in the culture medium or carbonic acid in the air; the energy necessary to decompose the carbon dioxide and fix the carbon is derived from the oxidation of the ammonia, about 35 parts of nitrogen being oxidised for each part of carbon that is fixed. The nitrifying organisms are chiefly confined to the cultivated surface layer of the soil. Warington found that, in the close-textured Rothamsted soil they were by no means uniformly distributed below the top 9 inches, and that they were never present, except accidentally, in the subsoil below a depth of 2 feet. It has been shown later that they are entirely absent from many heath and moor soils, even in the surface layer. They are abundantly found in the water of shallow wells and rivers.

Summing up the above facts, it is seen that for the active production of nitrates from the organic compounds of nitrogen present in the soil—and this is necessary if the crop is to be kept supplied with the nitrogen required for its growth—the following conditions are requisite:—The presence of the nitrifying organisms in sufficient quantities, a certain degree of temperature, darkness, sufficient moisture for the development of the bacteria, free aeration of the soil to supply the oxygen necessary, and a base to neutralise the acids as they are produced.


The scanty number of nitrifying bacteria in any subsoil below the cultivated layer helps to explain both its sterile nature when brought to the surface, and the difficulty and length of time required to develop a state of fertility, especially when dealing with a clay soil in which percolation and aeration have been deficient.

The effect of a low temperature in checking the

formation of nitrates is well seen in the way the growing corn turns yellow through nitrogen starvation whenever a cold and drying north-east wind chills the ground in spring: the bright green colour returns as soon as warmer and moister soil conditions restore the activity of the nitrifying bacteria in the surface layer. King found in the top foot of soil when oats were turning yellow only 0.026 parts of nitric nitrogen per million of dry soil, whereas in soil where the oats were green on the same date there was 0.255 parts of nitric nitrogen per million. The greater warmth of a light soil also causes it to form nitrates quickly in the spring, and so assists in producing an early growth.

But in obtaining early crops, even when the land is rich, a dressing of ready-formed nitrate is often of the greatest assistance, for the development of very early crops may easily outstrip the rate at which the nitrates they require can be formed in the still unwarmed soil. Nitrates are much more freely formed in the summer than in the winter, and as nitrates are not retained by the soil, they may easily be washed away when the crop has been removed unless weeds or a catch crop sown to that end are present to take up the nitrates and store them as organic compounds of nitrogen for the future enrichment of the land. The need for aeration in connection with the nitrifying process has already been alluded to when discussing drainage: all processes of working and cultivating the soil assist nitrification, both by the thorough aeration they effect, and by the mere mechanical distribution of the bacteria into new quarters, where there are fresh food supplies.

In some experiments of Dehérain's he found that the drainage water from pots of cultivated soil, which had been sent from a distance, and thus much knocked about in travelling and filling into the pot, contained






FIG. 14.—Nitrates per million parts Dry Soil, 1 foot deep, Cultivated and Uncultivated.

as much as 466 to 664 parts of nitrogen as nitric acid per million. The drainage water from the Rothamsted wheat plots contains only from 10 to 20 parts per million; even the cement tanks at Grignon, 2 metres cube, into which the soil had been filled, gave drainage water containing only 39 parts of nitric nitrogen per million. In another experiment a quantity of soil was thrown upon a floor, and worked about daily for six weeks; on analysis it contained 0.051 per cent. of nitric nitrogen, as against .002 per cent. of nitric nitrogen in the same soil left *in situ*. The diagram, Fig. 14, due to King, shows the dependence of nitrate production on temperature and the cultivation of the soil. The upper curves show the amount of nitric nitrogen in parts per million in dry soil in each of the top 4 feet of land, which was not being cultivated because it carried clover and oats. The lower curves show the same results obtained on well-tilled land carrying maize and potatoes. On the cultivated land the proportion of nitrates rises rapidly until the end of June, when the crop begins to draw freely upon them and reduces them to a minimum throughout August and September.

One of the best examples of the manner in which the thorough working and aeration of a warm soil promotes nitrification is seen in the management of the turnip crop as usually grown in this country. Though shallow-rooted, and taking away large quantities of nitrogen per acre, it is usually grown with but little nitrogenous manure; phosphates with a little dung, or with a comparatively small nitrogenous dressing, being sufficient. The rest of the nitrogen is due to the rapid production of nitrates, by the very thorough working of the soil in the warm season of the year that is characteristic of the cultivation of the

turnip crop. The production of nitrates by cultivation for the benefit of a succeeding crop by bare fallowing, or of an adjoining crop as in the Lois-Weedon system of alternate husbandry, has been already alluded to. At Rothamsted, nearly 60 lbs. per acre of nitric nitrogen were found in October in the top 27 inches of soil that had been fallowed, as against about half that amount in land which had been under crop. The unmanured alternate wheat and fallow plots showed in September 1878 to a depth of 18 inches 33.7 lbs. of nitric nitrogen per acre after fallow, and only 2.6 lbs. after wheat. In land occupied by cereal crops the drainage waters show that there is practically no nitrate left in the soil by May, or, at the latest, June; they reappear again towards the end of July or in August, and after harvest, if rain falls, and especially if the land be ploughed, nitrification becomes very active. King found a mean amount of 473 lbs. of nitric nitrogen per acre in the surface foot of fallowed ground, as against 11 lbs. in adjoining ground under crop. He also found that, despite the washing effect of winter rains, the nitrates persisted in the fallowed soil; the top foot of soil fallowed the previous season contained at the end of April 212 lbs. of nitric nitrogen, as against 25 lbs. only in the land which had not been fallowed. To sum up, increased nitrification, together with the conservation of soil moisture and the warming of the surface soil, are among the chief benefits derived from all forms of surface cultivation.

As so much of the fertility of a soil must depend on the number of nitrifying organisms it contains, attempts have been made to compare soils in this respect, by seeding small quantities of them into a standard solution capable of nitrification and determining the amount of nitric acid formed after a given time. Although con-

siderable differences are seen in the action of different soils, yet, as far as the author's experience goes, satisfactory quantitative results have not been obtained because of difficulties in the way of drawing strictly comparable samples of the soils.

Denitrification.

The term denitrification is most properly applied to the reduction of nitrates to nitrites, ammonia, or particularly to gaseous nitrogen, which is brought about by bacterial action under certain conditions. Of late, however, the term has been more loosely used to denote any bacterial change which results in the formation of gaseous nitrogen, whether derived from nitrates, ammonia, or organic compounds of nitrogen.

Angus Smith was the first to observe the evolution of gas from a decomposing organic solution containing nitrates, which were destroyed in the process. Other observers, particularly Dehérain and Maquenne (1882), with regard to soils, confirmed these results and showed that they were due to bacterial action. In a paper published in 1882, Warington described an experiment in which sodium nitrate was applied to a soil saturated with water, in which state it was allowed to stand for a week; the nitrate was then washed out of the soil, and found partly to have disappeared, and partly to have become nitrite. The total of both nitric and nitrous nitrogen only amounted to 20.9 per cent. of that which had been originally applied. That the nitrate had been reduced to gaseous nitrogen was seen by the development of transverse cracks filled with gas in the soil, and it was concluded that some of the nitrogen applied in manures and unaccounted for in crop and soil may well be due to the reduction of nitrates to gas, by the combustion of organic matter with the

oxygen of the nitrate, especially in ill-drained soils in wet weather. Gayon and Dupetit, in 1886, isolated two organisms from sewage, which would reduce nitrates to gas in the presence of organic matter, the action being chiefly carried on when oxygen was absent and coming to a standstill when plenty was supplied, so that the organism had no need to attack the nitrate to obtain oxygen. Both in their experiments, and in others, the presence of an abundant supply of soluble organic matter was one of the necessary conditions for the destruction of the nitrates. The denitrifying bacteria are widely distributed. Warington found, out of thirty-seven species of bacteria examined, only fifteen failed to reduce nitrate, twenty-two reduced it to nitrite, and one of them liberated gas. P. F. Frankland, again, found that fifteen out of thirty organisms derived from dust or water would reduce nitrate to nitrite. In fact, a large number of bacteria, when deprived of oxygen and in contact with abundant organic matter, will obtain the oxygen they normally require for the breaking up of the organic matter at the expense of the nitrate.

Many experiments, in which farmyard and other organic manures have been employed in conjunction with nitrate of soda and similar active compounds of nitrogen, have shown a smaller crop for the manures used together than when either is employed singly. These results were particularly apparent when large quantities of material like fresh horse-dung or chopped straw were used in pot experiments. With well-rotted dung, the effect of organic material in depressing the yield which should be given by the nitrate was not so great.

The nature of the results obtained may be seen from the following table, which gives the percentage

recovered in the crop of the nitrogen supplied in the manure, when used alone, or in conjunction with fresh horse-dung :—

PERCENTAGE OF NITROGEN RECOVERED (WAGNER).

	Per cent. recovered when used alone.	When used with Horse-dung.
Nitrate of Soda	77	52
Sulphate of Ammonia	69	50
Urine	69	40
Grass	43	20

Numbers of similar experiments in pots have been recorded. In some cases the use of fresh dung has even resulted in a smaller crop than was obtained without any manure at all; but it should be noted that very large amounts of the organic manures were used, equivalent to 100 tons or more per acre. Similar results have, however, been recorded in field trials, as in some experiments of Krüger and Schneidewind's, where fresh cow-dung was applied at the rate of 23 tons per acre, horse-dung 21 tons per acre, and wheat straw at 5.8 tons per acre, on July 10th. These three plots were in part cross-dressed with urine or with nitrate of soda, each supplying 43 lbs. of nitrogen per acre. Two successive crops of mustard were immediately grown, and the amount of nitrogen removed by the crop was ascertained. Compared with the wholly unmanured plot, the cow-dung alone slightly depressed the crop, about $1\frac{1}{2}$ lbs. per acre less nitrogen being recovered; the horse-dung produced a depression of nearly double this amount; the wheat straw produced the greatest depression, its crop containing about 18 lbs. per acre less nitrogen than that given by the unmanured plot.

Where straw was used with nitrate of soda the two gave a crop containing 23 lbs. less nitrogen per acre than the nitrate alone; where urine was used alone, the produce contained 25 lbs. more nitrogen per acre than when it was used in conjunction with cow-dung and straw.

In fine, all the results pointed to the same conclusion—that large amounts of fresh organic manure not only do not themselves help the crops, but diminish the effect of other rapidly-acting nitrogenous manures like nitrate of soda, sulphate of ammonia, or urine.

The action cannot, in the two latter cases at least, be put down to denitrification proper, unless it is supposed that nitrification and subsequent denitrification can proceed practically simultaneously in the same soil, which is hardly tenable. It must either be attributed to the fact that nitrification is very much checked by the presence of large amounts of organic matter; or to the conversion of readily available nitrogen into a comparatively insoluble albuminoid form in the actual material of the enormous numbers of bacteria that are developed by the free food supply; or, lastly, to those fermentation changes of organic nitrogen compounds which result in the liberation of free nitrogen. Several of these changes may take place together; the essential point is, that nitrification does not go forward in the presence of much organic matter, which instead favours all the bacterial processes resulting in the development of free nitrogen.

The conditions indeed which prevail in these experiments are scarcely comparable with the ordinary practices of agriculture. Enormous quantities of fresh organic manure are employed immediately before the crop is sown, the temperature of the pots, or of the ground in the field experiment quoted, is very high, so that it

is easy to see that an abnormal condition, both as regards supply of oxygen and water and nitrification must be developed.

There are not lacking both long-continued experiments and ordinary farming experience to show that nitrates and other artificial manures can be used in conjunction with dung with the best effects.

For example, the mangold crop at Rothamsted, taking the twenty-five years 1876-1900, shows the following average results in tons per acre :—

Cross-dressing.	Nothing.	400 lbs. Ammonia Salts.	550 lbs. Nitrate of Soda.
Unmanured . . .	3.8	5.6	9.75
Mineral Manures only	5.15	14.25	17.0
Farmyard Manure .	16.8	20.9	23.6

550 lbs. of nitrate of soda, when used with farmyard manure, thus produced an increase of 6.8 tons per acre of roots over the plot receiving farmyard manure alone.

Denitrification is only likely to cause rapid loss of nitrogen to the land when large quantities of nitrate are applied to undrained or sour land, or when they are used with excessive amounts of fresh dung, which has not been rotted and so deprived of much of its soluble organic matter. Of course, a further steady loss of nitrogen due to such causes as have been enumerated above must also be expected wherever large quantities of organic nitrogenous manures are accumulating in the land. If, for example, we compare 2 and 3 of the Broadbalk wheat plots at Rothamsted, the latter of which is unmanured and the former receives dung containing 200 lbs. of nitrogen per acre every year, we find that at the end of the fifty years, 1844-93, the dunged plot contained in the top 18 inches about 2680

lbs. more nitrogen than the unmanured plot, or a mean annual accumulation of 50 lbs. The excess of crop on the dunged plot would remove a further 31 lbs., thus leaving 115 lbs. per annum to be accounted for, either as nitrogen washed away in the drainage water, or lost as gaseous nitrogen by denitrification processes. As the analysis of the drainage water from the dunged plot only lead to an estimated loss of nitrates equal to 30-40 lbs. of nitrogen per acre per annum, there is still a large annual loss of nitrogen in this plot with its excessive accumulation of an organic nitrogenous manure, which loss must be set down to the bacterial processes known as denitrification.

Iron Bacteria.

Another series of bacteria playing an interesting part in certain soils, consists of those which secrete hydrated ferric oxide or bog-iron ore in undrained soils, where the soil water contains ferrous bicarbonate in solution. Winogradsky investigated four of these organisms, to whose vital processes he considered the presence of soluble ferrous salts was essential. Molisch, however, regards the secretion of ferric hydrate as, in a sense, an accidental accompaniment of their growth, much as the separation of large quantities of silica, so characteristic of the straw of cereals, is unessential to their development. It has already been noted that these iron earths do not form in soils containing calcium carbonate, which seems to prevent the formation of any soluble ferrous compounds.

Fungi of Importance in the Soil.

Allusion has already been made to the fact that a large number of fungi inhabit the soil—*Penicillium*, *Mucor*, *Aspergillus*, *Oidium*, etc.—all of which aid in breaking down the organic matter. There are, how-

ever, two special organisms which merit further consideration—the fungus which clothes the finer rootlets of many classes of plants, forming mycorhiza, and the slime fungus or *Plasmodiophora* which causes the disease known as “finger-and-toe” or “club” in turnips and other cruciferous plants.

The term “mycorhiza” is applied to the symbiotic combination of the filaments of certain fungi, whose complete development is as yet unknown, with the finest rootlets of certain plants. Sometimes the fungus forms a sort of cap on the exterior of the short rootlets, which are generally without root hairs; in other cases it penetrates the cortical tissue of the root itself, which may also be furnished with root hairs. According to the researches of Frank, the fungus of the mycorhiza lives in symbiosis with the higher plant, attacking the humus and also the mineral resources of the soil, and passing on the food thus obtained to the host plant. In some few cases the host plant possesses no green assimilating leaves, and is wholly dependent upon mycorhiza to obtain its necessary carbon from the humus. Such a case is seen in the *Neottia Nidus-avis*, or Birds'-Nest Orchis, to be found chiefly amongst beech underwood in this country.

More generally, the host plant is capable of nutrition in the ordinary way when growing in media in which nutrient salts are abundant, but becomes mycotrophic in soils and situations unfavourable to the production of directly absorbable food—as, for example, in heaths and moors, where the soil is almost wholly humus, or beneath the shade of trees, where nitrates are rarely found and where illumination is insufficient for much assimilation. Later researches, particularly those of Stahl, have shown that the symbiosis of mycorhiza, instead of being a phenomenon restricted to a few species,

is widely diffused among many classes of plants, and is indeed causally connected with other facts of wide general importance in plant nutrition. It has already been indicated that the cultivated plants give off considerable quantities of water by transpiration; the form and arrangement of their leaves are adapted to expose a large evaporating surface, the root is well developed and provided with root hairs to keep up the supply of water to the plant. There are, however, a number of plants in which transpiration is much less active, and the leaf area is restricted or otherwise arranged to diminish the loss of water, so that the proportion previously stated as existing between the dry matter produced and the water passing through the plants is greatly diminished. A diminished supply of water to the root would, however, necessitate a loss of nutriment to the plant, as both nitrates and other mineral salts enter the plant with the transpiration water. Stahl has shown that, in general, these plants with a small transpiration activity are furnished with mycorrhiza, by means of which they obtain food of all kinds from the soil; whereas, on the contrary, the plants, like the cereals, the cruciferous and leguminous plants, Solanaceæ, etc., which give off water freely, are never associated with mycorrhiza. Many of the conifers and heaths which grow on dry soils show this correlation of a low evaporation and restricted leaf development, with a root-system furnished with mycorrhiza.

Another interesting generalisation has also been brought into line with the above facts by the observations of Stahl that the mycotrophic plants with a feeble transpiration do not store starch in their leaves, but contain instead considerable quantities of soluble carbohydrates, chiefly glucose. In normal plants, though sugar is the first tangible result of assimilation, it is

rapidly removed from the sphere of action by being converted into starch, such withdrawal of the product of the reaction being necessary if a rapid rate of assimilation is to be maintained. Should, however, sugar accumulate in the cells, the concentration of the cell sap is increased, so that it parts with its water by transpiration less readily. Though many exceptions can be observed, there seems to be a very general association of the development of mycorrhiza with a diminished transpiration and the absence of starch from the leaf, especially amongst plants like the orchids, lilies, iris, etc., which often grow in dry or shady situations, such plants being further distinguishable by a shiny, glossy leaf surface. Stahl has again shown that the average proportion of ash to dry matter in the leaf is lower for mycotrophic than for normal plants; the former grow, as a rule, in situations containing but little mineral salts, particularly in humic soils, where, in addition, the plant is put into competition for whatever nutriment may be present with the mycelia of fungi, which everywhere traverse humus in its natural state. By direct experiment, it has been shown that normal plants grown in humus develop better when the humus is previously sterilised by long exposure to chloroform vapour than when it is in its fresh condition, full of living mycelia competing successfully for the nutriment. The absence in the leaf of calcium oxalate and of nitrates is particularly characteristic of mycotrophic plants.

Stahl concludes that symbiosis between the roots of plants and the mycelia of fungi is a very general phenomenon, especially characteristic of plants growing in soils subject to drought, or poor in mineral salts, or rich in humus. These mycotrophic plants are generally of slow growth, possess a feeble transpiration

and limited root development; their leaves rarely contain starch; they are also characterised by containing comparatively small proportion of mineral salts, among which calcium oxalate and nitrate are notably absent.

The existence of mycotrophy has certain interesting applications in practice; there are many plants which can only be cultivated with difficulty in gardens—for example, some of the orchids, ericas, lilies, and others, generally plants which must be grown in leaf mould, peat, or other material rich in humus. Yet humus alone has not been sufficient for the purpose, the peat or leaf mould has often to be obtained from a particular place; other materials, though equally rich in humus and possessing similar mechanical properties, prove quite unsuitable. It is easy to surmise that this effect, confined in the main to mycotrophic plants and humic soils, may easily be due to the absence of the proper fungus from the soils found to be unsuitable.

It has also been shown that the difficulty usually experienced in raising seedlings of exotic orchids, which die off in great number just after they have germinated, may, to a large extent, be obviated by mixing with the medium in which the seeds are sown a little of the material in which the parent plants are growing. The young seedling is found to develop mycorrhiza at a very early stage, and then only will grow properly.

"Finger-and-Toe."

On many soils, particularly those of a sandy nature, the turnip crop is often almost wholly destroyed by the disease known as "finger-and-toe," "club," or "anbury." Cabbages and other cruciferous crops are equally attacked; so much so, that in gardens which have become infected it is practically impossible to raise crops of this nature. The disease is caused by an organism,

Plasmodiophora brassicæ, belonging to the slime fungi, and forming spores, which may remain dormant in the soil for some time, certainly two or three years. It has long been known that the best remedy against finger-and-toe consists in the application of lime; and as far back as 1859, Voelcker showed that soils on which this disease is prevalent are deficient in lime, and in many cases in potash also. Later researches have only served to emphasise the fact that the disease is associated with soils of an acid reaction, in which calcium carbonate is wanting, or present in very small proportions. The fungus, as is generally the case with fungi, refuses to grow in a neutral or slightly alkaline medium, and the only way to get rid of the infection in the land is to restore its neutrality by repeated dressings of lime. At the same time, the land should be rested as long as possible from cruciferous crops; uneaten fragments of diseased turnips, etc., should not be allowed to go into the dung, or if they do, the dung should be used on the grass land. Manures, again, which remove calcium carbonate from the soil, like sulphate of ammonia, or acid manures like superphosphate, should not be employed; neutral or basic phosphates, with sulphate of potash on sandy soils, should be employed instead.

The following figures show the amount of lime dissolved by hydrochloric acid from soils affected with "finger-and-toe," as compared with spots in the same field where the disease was not in evidence:—

	LIME PER CENT.				
	Voelcker.	Voelcker.	Hall.	Sandy Soil.	Clay Soil.
Spots affected by disease .	.14	.084	.13	.31	.39
Spots free from disease . .	.89	.52	.43

It must be remembered that in these cases the total lime soluble in acids is given, not merely the lime present in carbonate.

Whenever a turnip crop is seen to be infected with "finger-and-toe" the land should be well dressed with 3 or 4 tons per acre of quicklime immediately the crop has been removed; as long an interval as possible should be given before again taking a cruciferous crop, substituting, for example, mangolds for turnips in the next rotation; every effort should be made to destroy even cruciferous weeds like charlock; turnip-fed dung should not be applied, and another dressing of finely divided quicklime should be put on for the crop preceding the sowing of the new turnip crop.

CHAPTER VIII

THE POWER OF THE SOIL TO ABSORB SALTS

Retention of Manures by the Soil—The Absorption of Ammonia and its Salts ; of Potash ; of Phosphoric Acid—Chemical and Physical Agencies at Work—The Non-Retention of Nitrates—The Composition of Drainage Waters—Loss of Nitrates by the Land—Time of Application of Manures.

MANY of the substances employed as manures are soluble in water, hence it becomes important to ascertain what is likely to be their fate in the soil, in case their application be followed by sufficient rain to cause percolation into the subsoil. Of substances containing nitrogen, nitrate of soda, the salts of ammonia, urea and kindred bodies, are freely soluble in water ; superphosphate alone of the compounds of phosphoric acid commonly used as manure is soluble ; but sulphate, chloride, and carbonate of potash are easily soluble.

Not long after the principles underlying the nutrition of plants had been established, Thompson and Way showed that ordinary soil possesses the power of withdrawing most of the above substances from solution, and so saving them from washing away into the subsoil or the drains. Some of the salts, like sulphate of ammonia, are decomposed, the base alone being retained and the acid draining through. Way found

that liquid manure from a dung-heap, which contains both organic and ammoniacal compounds of nitrogen, potash, and a little phosphoric acid, when filtered through a short column of soil, parted with almost the whole of its organic matter and much of its salts to the soil; compounds of calcium were, however, more abundant in the filtered liquid than before. Way's observations were extended by Voelcker, who compared the absorbing powers of different types of soils, and so obtained an idea of the method by which the absorption of each substance was effected; and later researches have only served to confirm the results then obtained. It was found that all the organic compounds of nitrogen, ammonia—either free or in combination—phosphoric acid, and potash were wholly removed from solution by ordinary soil, though some soils were more effective than others; whereas nitrates, sulphates, chlorides, and, among bases, sodium and calcium, were only slightly, if at all, retained. These results are confirmed by the analysis of the water which flows from land drains under normal conditions; this will generally be found to contain nitrates (sometimes in fair quantity), sulphates and chlorides of calcium and sodium, and considerable amounts of calcium bicarbonate, but rarely shows more than a trace of ammonia, phosphoric acid, or potash. The absorptive action of the soil is partly a chemical process, due to such substances as calcium carbonate or the hydrated silicates and oxides of the soil; and partly physical, dependent upon the extent of surface offered by the soil particles (for the surface of a solid possesses the power of concentrating molecules of any dissolved substance in the layer of solution with which it is immediately in contact). The mechanism of this physical absorption is but imperfectly understood, but

even pure sand will remove sodium chloride from solution if the filtering column be sufficiently long; it may, again, be illustrated by the phenomenon of "laking," *i.e.*, the power of certain colloid bodies, like the hydrates of iron and alumina, on precipitation, to drag down with themselves many organic substances from solution.

The absorption of the organic compounds of nitrogen by the soil seems to be a physical process of this kind, comparable to the action of charcoal in absorbing ammonia or the strongly-smelling products of putrefaction, etc. The deodorising powers of earth for fæcal and decomposing matter are very familiar; this means that fixation in a more or less insoluble and non-volatile state of various organic nitrogen and sulphur compounds is effected, and other inodorous nitrogen compounds are retained in the same way. The absorption is most marked with soils rich in humus or in clay—the soil materials which present the largest surface. The absorptive power of soil for organic compounds of nitrogen is well seen in a sewage farm, the object of which is to so far purify sewage by percolation through a few feet of soil, as to fit it to be turned into a river without danger to health. For example, on the Manchester Sewage Works, in 1900, percolation through 5 feet of soil reduced the organic nitrogen from 0.26 to 0.056 parts per million, and the free ammonia from 1.89 to 0.92. It is necessary, also, on a sewage farm to work with soils possessing but a small absorbing power; only sandy and gravelly soils will permit of rapid enough percolation, both to deal with large volumes of sewage and afterwards to aerate themselves and accomplish the destruction of the absorbed material. Stiffer soils would be far more effectual absorbents of the

sewage material, but are unsuitable because they do not admit of percolation.

Absorption of Ammonia Salts.

The absorption of free ammonia follows the lines indicated above for the absorption of the organic compounds of nitrogen; but the salts of ammonia require a preliminary chemical change before they are retained by the soil. Way and Voelcker found, that when either the sulphate, chloride, or nitrate of ammonia in solution is allowed to remain in contact with soil, the base is absorbed, but the acid portion of the salt remains in solution in combination with lime. The reaction would be a double decomposition of this type— $(\text{NH}_4)_2\text{SO}_4 + \text{CaCO}_3 = (\text{NH}_4)_2\text{CO}_3 + \text{CaSO}_4$ —then the ammonium carbonate is caught up by the clay and humus, as is the case with free ammonia (into which, and carbonic acid, it may possibly first dissociate), while the calcium sulphate remains in solution. The retention of ammonia salts is thus dependent on the presence of both calcium carbonate and of clay and humus in the soil, as may be seen in the following results obtained by Voelcker. Ammonia combined with sulphuric or hydrochloric acid, soil, and water, in the proportions roughly of 1, 1000, and 4000, were mixed for a time, and then filtered. The figures give the proportion of the ammonia retained by the various soils:—

Per cent. of Ammonia absorbed by	Ammonium Chloride.	Sulphate.
Calcareous Clay	48 per cent.	53 per cent.
Fertile Sandy Loam	54 "	56 "
Stiff Clay	56 "	50 "
Sterile Sandy Soil	11 "	22 "
Pasture	45 "	40 "

In these experiments the absorption is never complete; but the proportion the ammonia bears to the soil is far greater than would ever occur under field conditions, and the time for which the materials are in contact is limited. It must be further remembered, that as the reaction between the ammonium salts and the calcium carbonate is a reversible one, the extent to which the reaction will be completed in the sense indicated will be dependent on the mass of the calcium carbonate present. The manner in which ammonia salts will remove calcium carbonate from the soil can be strikingly seen in the present condition of the permanent wheat and barley plots on the Woburn Experimental Farm. The soil is light and sandy, containing but little lime, and the application of ammonia salts containing 50 lbs. ammonia per acre every season for twenty-four years, has rendered the land practically incapable of carrying the crops. A moderate dressing of lime, however, restores the fertility. The following crops were obtained in 1900 on the barley plots:—

	Ammonia Salts only.	Minerals + Ammonia Salts.
With no Lime	5.6	12.3
With 2 tons Lime, applied Nov. 1897	28.9	33.7

The soil had become acid to litmus paper where the lime had not been used: it is interesting to note that though barley would not grow, oats flourished freely on this sour soil.

Another example of the removal of calcium carbonate from the soil by ammonia salts is afforded by the Rothamsted soils, which are well supplied with calcium

carbonate. Analysis of the top 9 inches of the soil from the wheat plots, which had been continuously manured in the same way for fifty years, showed the following proportions of calcium carbonate :—

	Unmanured.	Minerals only.	Minerals +200 lbs. Ammonia Salts.	Minerals +275 lbs. Sodium Nitrate.
CaCO ₃ % .	3.55	3.67	2.5	4.17

200 lbs. of ammonia salts for fifty years would require 17,000 lbs. of calcium carbonate to both combine with the acids in the salts and then with the nitric acid resulting from the ammonia, whereas a reduction of 1 per cent. in the calcium carbonate content of the soil would be equivalent to a loss of about 25,000 lbs. per acre.

The Absorption of Potash.

In many respects the absorption of potash follows the same laws as that of ammonia: *i.e.*, caustic potash and potassium carbonate are absorbed directly, but sulphate, nitrate, and chloride of potash undergo a preliminary reaction with the calcium carbonate of the soil, by which the potash is retained, and calcium sulphate, nitrate, or chloride, appear in the water draining through the soil. Voelcker found in laboratory experiments with small quantities of soil that potassium carbonate was more freely absorbed than sulphate, and that clays, marls, and pasture soils were more effective in retaining potash than light loams or sands, which latter had but little absorbing power.

The following table shows some of the results obtained when potash and soda salts were compared :—

Percentage retained.	Potash.	Soda.
Chalky Loam . . .	3.6	0.8
Clay	4.0	1.1
Sandy Loam . . .	2.6	0.6
Pasture	3.8	1.0
Loam	3.4	1.0
Ironstone Sand . .	1.1	0.6

The manner in which the potash salts are retained is not entirely clear. After the reaction with the calcium carbonate, the clay appears to play the chief part in removing the potassium carbonate from solution. Probably the hydrated double silicates of the clay material are chiefly effective, taking some of the potash into loose combination by double decomposition; it is improbable that the action is wholly a physical one dependent on surface, for in that case the sodium salts would equally be retained. In some of Way's experiments with pure clays the application of potash salts was followed by the appearance of the corresponding sodium salts in the percolating water, though with most soils it is calcium that is turned out of combination. Dyer has examined the soils of the Rothamsted wheat plots which had then been continuously manured in the same way for fifty years, with the view of tracing the fate of the mineral manures applied. The following table shows a comparison of the amounts of potash soluble in strong hydrochloric acid, in lbs. per acre, found in the top 9 inches of soil from four of the plots; one (No. 11) received nitrogen and phosphates, but no potash, every year, the others were variously manured, but all received 200 lbs. per acre of sulphate of potash. Estimates are also given of the total amount of potash applied as manure and removed in the crops over the whole period, so that in the last two columns a com-

parison can be made between the actual surplus of potash in the manured over the unmanured soils, and the surplus calculated from the differences between the potash added in the manure and removed in the crops:—

Plot and Manuring, per Acre.	POTASH—LBS. PER ACRE.			SURPLUS OVER PLOT 11.	
	In top 9 inches of Soil.	Added in Manure.	Removed in Crop.	Calculated.	Found.
11, receiving no Potash .	5107	15	1190
7, receiving 200 lbs. Sul- phate of Potash .	6793	5037	2550	3662	1686
5, receiving 200 lbs. Sul- phate of Potash .	7233	5203	1136	5242	2126
13, receiving 200 lbs. Sul- phate of Potash .	7078	5287	2410	4052	1971

On the whole about one-half of the estimated surplus of potash received by the manured plots still remains in the top 9 inches of soil.

Dyer further estimated the proportions of potash in the same soils which were soluble in a 1 per cent. solution of citric acid, and found that both the surface and the subsoil down to a depth of 27 inches contained more of this readily soluble potash where it had been applied as manure, than did the companion plot receiving no potash, as will be seen from the following table:—

Plot.	LBS. PER ACRE OF POTASH, SOLUBLE IN 1 PER CENT. CITRIC ACID.			SURPLUS OVER PLOT 11.	
	First 9 inches.	Second 9 inches.	Third 9 inches.	Calculated.	Found.
11	83	75	101
7	602	374	179	3662	896
5	799	598	257	5242	1395
13	487	363	235	4052	826

These determinations show that soluble potash salts applied to the land are retained chiefly by the surface soil, as much as one-half of the estimated additions of potash during fifty years manuring being found there. Some of the potash, however, sinks further and is retained in the subsoil; in the top 27 inches a large proportion—nearly one-quarter of the whole—remains in such a loose state of combination that it is soluble in 1 per cent. citric acid, and so may be regarded as available for the plant.

Absorption of Phosphoric Acid.

The retention of soluble phosphoric acid by the soil is more easily intelligible, for there are present several substances capable of forming insoluble compounds with phosphoric acid—*e.g.*, calcium carbonate, hydrated ferric oxide, and the hydrated silicates of alumina which make up so much of clay. Sand and powdered silicates like felspar have been found to possess little or no power of removing phosphoric acid from solution, nor have either soil, clay, or peat, which have been previously washed with hydrochloric acid.

The following table shows the percentages of the total phosphoric acid supplied, which were removed from solution by various soils, after remaining in contact for the specified times, the ratio between soil and phosphoric acid being about 1000 to 1.

PERCENTAGE OF PHOSPHORIC ACID ABSORBED (VOELCKER).

	After 1 day.	After 8 days.	After 26 days.
Red Loam	60	78	95
Chalky Soil	89	99	100
Stiff Clay	51	62	86
Stiff Subsoil	48	69	74
Light Sandy Soil . .	53	59	73

In an ordinary soil containing a sufficiency of calcium carbonate, the application of soluble phosphoric acid like superphosphate, will chiefly result in the precipitation of di-calcium or "reverted" phosphate, wherever the solution meets with a particle of calcium carbonate. This di-calcium phosphate is a compound easily soluble in weak organic acids or in water containing carbonic acid: hence the great value of applications of superphosphate on soils rich in lime, for thus a readily available phosphate is very quickly disseminated throughout the ground in a state of fine division. But on soils poor in calcium carbonate the precipitation will be chiefly effected by the hydrated iron and aluminium compounds, and the resulting phosphates are practically insoluble in water containing carbonic acid, and but little in saline solutions or in weak organic acids. Hence applications of superphosphate to such soils become much less available to the crop, and should be preceded by a thorough liming of the land. Even a subsequent liming on soils containing phosphates of iron or alumina will help to bring them into a more available form, because a double decomposition resulting in calcium phosphate and aluminium or ferric hydrate, will proceed to an extent dependent on the mass of lime present in the medium. Even with chalky soils a considerable proportion of the soluble phosphoric acid applied passes into the slowly available combinations, as is seen by the following results, where the soil after absorbing phosphoric acid was treated with ammonium citrate to redissolve the more available portions of the precipitated phosphate. 100 grams of soil were left for one week in contact with 1 litre of a solution of potassium phosphate containing 0.229 grams P_2O_5 ; soil 1 was a chalky clay, well cultivated and rich in humus; 2 was the subsoil of the same; 3 was a

light loam containing about 1 per cent. of calcium carbonate.

Percentage of Phosphoric Acid.	Soil 1.	Soil 2.	Soil 3.
Absorbed and Soluble in Ammonium Citrate	30.5	35.2	35.7
Absorbed and Insoluble in " "	41.8	11.9	39.5
Not absorbed	27.7	52.9	24.8

Further evidence of the precipitation of phosphoric acid within the soil is afforded by Dyer's examination of the Rothamsted wheat soils at various depths, after fifty years' continuous manuring with and without superphosphate. By comparing the amount of phosphoric acid contained in the soil of the unmanured plot with that contained in the soils of the plots receiving superphosphate every year, and knowing also the amount removed by the successive crops in each case, it is possible to calculate the surplus that should remain in the manured over the unmanured plots, on the assumption that the soil was uniform at starting. Calculating in this way, Dyer found that no less than 83 per cent. of the phosphoric acid which six of the plots should possess after fifty years manuring was still present in the top 9 inches of soil, whereas the subsoils from 9 inches to 18 inches, and 18 inches to 27 inches, showed no accumulation of phosphates. Dyer further determined the phosphoric acid which was soluble in a 1 per cent. solution of citric acid, and found that on the manured plots the top 9 inches of soil contained about 39 per cent. of the estimated surplus of phosphoric acid so combined as to be soluble in this medium, whereas in the subsoils the "available" phosphoric acid was, if anything, less for the manured than for the unmanured plots. The

phosphoric acid had been applied as a superphosphate, about 90 per cent. of the phosphoric acid of which would be originally soluble in the citric acid solution. It is clear, then, that soils well provided with calcium carbonate, as the Rothamsted soil is, will precipitate very near the surface any soluble phosphoric acid applied, and retain it for a long time in a form easily redissolved and obtainable by the plant.

The Composition of Drainage Waters.

Further evidence of the fate of the various substances applied as manures, their retention or otherwise by the soil, can be obtained by studying the composition of the water flowing from land drains.

The drainage from the continuously manured wheat plots at Rothamsted, each of which possesses a tile drain running down the centre at a depth of 2 feet to 2 feet 6 inches, has been collected from time to time and completely analysed by Voelcker and Frankland; in addition systematic determinations of the nitrogen contents have been made for many years. In a general way, the chief constituent of the various drainage waters is lime, either as bicarbonate, sulphate, chloride, or nitrate; soda is the only other base present in any quantity, but small amounts of magnesia, potash, and ammonia pass into the drains. Of the acid ions or radicles, chlorine and sulphuric acid predominate according to the manuring, and the proportion of phosphoric acid is minute; but the amount of nitric acid varies according to the manure applied and the season at which the water is collected.

The following table shows the complete analysis of the drainage water from twelve of the plots:—

An examination of these figures shows that the amount of organic matter and ammonia reaching the drains is practically nil; the organic matter supplied as dung and the ammonia, which is employed up to 400 lbs. of mixed ammonium chloride and sulphate per acre, are wholly retained by the soil. The effect, however, of adding either organic compounds of nitrogen or ammonia salts is to increase the proportion of nitrates in the drainage water. Lime is the chief constituent of the dissolved matter in the drainage waters, the proportion is lowest for the unmanured plot (3), it rises with the application of minerals (5), and rises again with each successive application of ammonia salts (6) and (7). The formation of calcium chloride and sulphate respectively, when the corresponding ammonia salts are applied to land containing calcium carbonate, has already been discussed: it is well seen in the increased richness in lime, sulphuric acid, and chlorine of the drainage water from 6 and 7, which receive 200 and 400 lbs. respectively of ammonia salts, as compared with 5 which receives the same minerals without any nitrogen compounds. Plot 11 receives superphosphate in addition to the ammonia salts which 10 receives: the effect of the gypsum contained in the superphosphate is seen in the increased lime and sulphuric acid content of the drainage water of 11. The increase is not so great, however, as that caused by the addition of sulphates of potash and magnesia to the superphosphate and ammonia salts (plots 13 and 14), whereas sulphate of soda causes little loss of lime (12). The use of nitrate of soda on plot 9 causes no increase in the proportion of lime in the drainage water, but a large quantity is removed, chiefly as sulphate, from plot 2 receiving dung every year. The quantity of lime removed annually in this way will be very great: assuming a mean annual drainage equal to 10 inches of water, the unmanured plot will lose about 220 lbs.

per acre per annum of lime: when 400 lbs. of ammonia salts are used as manure, either alone or with minerals, the increased loss of lime amounts to 126 lbs. per acre per annum. About 186 lbs. of lime would be required to combine with all the acids of the ammonia salts, and another 186 lbs. if all the ammonia were then nitrified and the calcium nitrate produced were removed by the plant or by washing into the drains. While the drainage water shows a smaller loss of lime to the soil due to the continuous use of ammonia salts than would be deduced from their known reaction with calcium carbonate, the change in the proportion of this material in the soil after fifty years cropping gives a somewhat higher figure. The analysis previously given (p. 194) indicates that the soil of plot 6 contained in 1893 1.12 per cent. more calcium carbonate than that of plot 5: this would be equal to a difference of about 28,000 lbs. per acre, equivalent to a removal of 314 lbs. of lime in each of the fifty years the manuring with only 200 lbs. ammonia salts had then been repeated. Obviously, in view of the fact that the proportion of calcium carbonate in the soil of each plot at starting is not known, too much stress cannot be laid on these figures, but they help to demonstrate the statements already made that for each molecule of ammonium salt applied to the soil one molecule of calcium carbonate combines with the acid radicle and forms a salt which is washed out of the soil, while a second molecule is required for nitrification, and is removed in its turn either by the plant or in the drainage waters.

The amount of magnesia lost is small, 5 to 20 lbs. per acre per annum, nor is the amount reaching the drainage water much increased by its application as manure to plots 5, 6, 7, 9, and 14.

The amount of potash lost is still smaller, from 3 to 12 lbs. per acre per annum, but it is distinctly

dependent on the amount supplied as manure, being at a maximum with the dunged plot (2) and the plot receiving minerals only (5), and greater from all the other plots receiving potash than from those without it, *i.e.*, 3, 10, 11, 12, 14. The use of sulphate or nitrate of soda increases the amount of potash in the drainage water ; not so, however, the use of sulphate of magnesia. Practically all the soda, chlorine, and nearly all the sulphuric acid, that are applied in the manure pass through into the drainage water.

A comparison of the drainage waters in winter and spring shows that they are more concentrated in the winter, because the manures (excepting the nitrate of soda) have then been recently applied : the chlorides wash out first, then the sulphates, and as the season advances not only is the total amount of lime present much diminished, but it comes away chiefly as carbonate. With the growth of the crop in spring the nitrates disappear from the drainage waters.

The amount of nitrates found in the drainage water varies not only with the time of year, but also according to the interaction of temperature, growth of crop, cultivation, and percolation. Nitrates are only rapidly produced when the temperature of the soil has risen : if the percolation is not excessive the crop may remove the nitrates as fast as they are formed, but a heavy rainfall in the spring before the nitrates have been much drawn upon by the crop, or one just after the land has been broken up in the autumn and is still warm, will result in a considerable washing out of nitrates. At the same time a certain amount of moisture in the soil is necessary for the formation of nitrates, and the crop itself may so dry the soil as to reduce nitrification considerably. The following table shows the estimated loss of nitrates from






FIG. 15.—Losses of Nitrogen in Drainage from Rothamsted Wheat Plots.

Black = Losses in Summers 1879, 1880.
Shaded = Losses in following Winters.

the same wheat plots at Rothamsted as have previously been dealt with, during two years, each of which has been divided into two periods: firstly, from the date at which the nitrogenous manures were sown up to harvest; and secondly, from harvest round again to the sowing of manures in spring.

NITRIC NITROGEN IN DRAINAGE WATER.—LBS. PER ACRE.

Plot.	Manuring, per Acre.	1879-80.		1880-81.	
		Spring Sowing to Harvest.	Harvest to Spring Sowing.	Spring Sowing to Harvest.	Harvest to Spring Sowing.
3	Unmanured	1.7	10.8	0.6	17.1
5	Minerals only	1.6	13.3	0.7	17.7
6	Minerals + 200 lbs. Ammonia Salts	10.1	12.6	2.2	19.8
7	" + 400 " " "	18.3	12.6	4.3	21.4
9	" + 550 " Nitrate of Soda	45.0	15.6	15.0	41.0
10	400 lbs. Ammonia Salts alone .	42.9	14.3	7.4	35.2
11	Do. do. + Superphosphate	28.3	17.7	3.4	29.6
12	Do. do. + Sulph. Soda .	21.2	17.5	3.3	27.2
13	Do. do. + Sulph. Potash .	19.0	16.4	3.7	25.3
14	Do. do. + Sulph. Mag. .	26.0	16.8	4.2	25.9
15	Minerals + 400 lbs. Ammonia Salts in Autumn	9.6	59.9	3.4	74.9
	Estimated Drainage—inches .	11.1	4.7	1.8	18.8

The diagram (Fig. 15) shows the same results in a graphic form.

The seasons were rather exceptional, the summer rainfall and drainage in 1879 and the winter rainfall in the following year being both above the average. It will be seen that the loss was greatest from plot 9 receiving 550 lbs. of nitrate of soda, and this excess of loss was chiefly in the summer drainage water; the figures are, however, exaggerated by the fact that half the nitrate plot received no mineral manures, and therefore grew

but a scanty crop. The losses during the winter months are more nearly the same for all plots, and represent to a large degree the nitrification of the organic residues in the soil. The losses from the plots receiving minerals and varying amounts of ammonia salts (5, 6, and 7) increase with each application of nitrogen: the losses from the plots receiving ammonia and various mineral manures diminish as the mineral manure becomes a more complete plant food, because the greater growth of crop thus secured more completely removes the nitrates as they are formed, besides hindering nitrification by drying the surface soil.

The effect on nitrification of crop and surface cultivation is well seen in the following table of results obtained by Dehérain, who collected the drainage from cement tanks 2 m. cube and systematically filled with soil taken from corresponding depths in the field. The soils had been several years in the tanks, so that they had settled down into practically normal conditions, though the effect of the aeration and disturbance of the soil in filling the tanks is still visible in a rather high rate of nitrification. Each tank carried the crop indicated in the first column.

Cropping.	Drainage.	Nitrogen as Nitric Acid.
	Inches.	Lbs. per acre in Drainage Water.
Fallow, no cultivation	11.2	209.1
Rye Grass	7.8	2.55
Oats	7.3	8.25
Maize	6.9	24.2
Wheat, followed by Vetches	6.6	14.4
Wheat	7.5	33.25
Fallow, hoed	11.5	220.15
Fallow, no cultivation	11.2	176.9
Fallow, hoed and rolled	11.2	205.2
Vine	7.5	40.8
Sugar Beet	7.2	.3

The rainfall of the year in question, March 1896 to March 1897, amounted to 28.8 inches, most of which fell in the autumn. The most noteworthy result is the effect of the various crops in diminishing the loss of nitrates, which is not wholly to be attributed to the quantity taken up by the crop, because the sum of the nitrogen removed in the crop and that carried off in the drainage water is never equal to the nitrogen removed from the uncropped plots by the drainage water alone. During the comparatively dry spring months the crops leave so little moisture in the soil that nitrification is checked, and the total production of nitrates is less where there is a crop than on the moister uncropped plots.

When the wheat was followed by a crop of vetches the loss of nitrates during the comparatively wet autumn was considerably reduced. Lastly, the hoeing of the fallow plots resulted in a considerably increased production of nitrates.

Time of Application of Manures.

The facts set out above as to the retention of most of the soluble constituents of manures by the soil, while the nitrates are liable to wash out, have an important bearing on the season at which artificial manures should be sown. In the first place it is evident that there is no danger of losing phosphates, or even of their washing deep into the soil, when employed in their most soluble form as superphosphate. It is the general custom to sow superphosphate with the drill for roots at the same time as the seed: the large quantity of manure near the seedling in its early critical stages is probably valuable, and as the roots of swedes and turnips do not extend very deeply, the phosphoric

acid may be placed in the most likely place to reach them.

But for more deeply rooting crops, hops and fruit or even mangolds, it seems probable that superphosphate is often applied rather too late in the season, and that if used as a winter instead of a spring dressing it would have a better chance of getting well diffused through the soil. Basic slag and other insoluble phosphates should be used in the winter or even the autumn: there is no risk of loss, and as much rain as possible is wanted to get them distributed in the soil. As regards potash salts, Dyer's experiments go to show that they descend further in the soil, and are a little more subject to washing than the soluble phosphates: for this reason where sulphate of potash is employed, as for potatoes, it will best be sown with the seed. Where kainit is used it is best employed as a winter or autumn dressing; there will be little loss of potash, for this will get fixed chiefly in the surface soil. But the chlorides, which are present in kainit, and are sometimes not wholly beneficial in their action upon the crop, will be removed and washed out into the drains or the subsoil water by the winter rains: the magnesia salts also will be precipitated within the soil, and to a large extent removed from possible action upon the crop. Turning to the nitrogen compounds, it is necessary to keep in mind that all of them will become transformed into nitrates which are liable to be washed out. All insoluble organic manures should be put on before or during the winter: the decay processes will begin, resulting in the formation of amides, etc., which will become fixed in the soil, but the low winter temperatures will not permit of much nitrification. Liquid manure and similar materials containing such readily nitrifiable substances as urca and ammonium

carbonate, should be reserved until early spring, so that the crop may be growing whenever nitrification begins. Ammonia salts are very rapidly nitrified, so that they should only be used in spring. At Rothamsted nitrates begin to appear in the drainage water immediately after the application of the ammonia salts to the wheat plots in March if rain falls, and one of the plots which has its ammonia salts applied in autumn shows not only a considerable falling off in crop but also large quantities of nitrates in the winter drainage waters.

The following table shows the amounts of nitrates removed in the drainage water from the two plots which receive 400 lbs. per acre of ammonia salts with mineral manures, only differing in the fact that on plot 7 the ammonia salts are sown in March, and on plot 15 in October; also the average crops of grain and straw for the twenty-three years, 1875-97.

1879-1881.—LBS. OF NITRIC NITROGEN PER ACRE.

Plot.	1879-80.		1880-81.		CROP.	
	Spring Sowing to Harvest.	Harvest to Spring Sowing.	Spring Sowing to Harvest.	Harvest to Spring Sowing.	Grain.	Straw.
					Bushels.	Cwt.
7	18.31	12.63	4.29	21.38	31½	31
15	9.62	59.92	3.4	74.94	28½	26½
Drainage	11.1"	4.7"	1.8"	18.8"		

That sulphate of ammonia will to some extent persist in the soil, and become available for a succeeding crop, after even a whole year has elapsed, is to be seen from the results of the Woburn experiments upon wheat. Some of the plots at Woburn receive mineral

manures every year, but ammonia salts or nitrate of soda only every alternate year: in both cases the crop falls very much in the years of no nitrogen, but the decrease is by no means so marked with ammonia salts as with nitrate of soda, which latter seems to leave no residue whatever.

The soil at Woburn is an open sandy loam; but in the years for which the results are quoted below the rainfall was low.

Plot.	1899.	Bushels.	1900.	Bushels.
{ 8B	Minerals only . . .	20.3	Minerals + Ammonia	
{ 8A	Minerals + Ammonia		Salts	27.3
	Salts	33.1	Minerals only . . .	16.2
{ 9B	Minerals only . . .	9.8	Minerals + Nitrate of	
{ 9A	Minerals + Nitrate of		Soda	27.7
	Soda	41	Minerals only . . .	6.8
4	Minerals only, every	6.9	Minerals only . . .	5.9
	year			

The difference between the results set out above and those obtained upon the corresponding plot at Rothamsted, where the dressing of ammonia salts every other year seems to leave no residue for the following year in which it is not applied, may perhaps be set down to the different texture of the two soils. The ammonia salts are converted, which are washed down into the subsoil; at Woburn they can rise again by capillarity, so the soil though sandy is still fine in texture; at Rothamsted the soil is too close-grained to admit of any considerable movement of the subsoil water back to the surface.

The experiments recorded above and the results of the examination of drainage waters go to show that nitrate of soda should only be employed when

there is a crop in possession of the ground, and ready to seize upon the salt as soon as it becomes diffused through the soil. Only in the dryest of soils can it be safely applied even as early as the sowing of the seed; in wet climates sulphate of ammonia is the preferable manure even for top dressing, unless the nitrate can be applied more than once in comparatively small dressings each time.

CHAPTER IX

CAUSES OF FERTILITY AND STERILITY OF SOILS

Meaning of Fertility and Condition—Causes of Sterility : Drought, Waterlogging, Presence of Injurious Salts—Alkali Soils and Irrigation Water—The Amelioration of Soils by Liming, Marling, Claying, Paring, and Burning—The Reclamation of Peat Bogs.

IN discussing the question of fertility, a difficulty at the outset crops up in the definition of the term "fertility": we are dealing with something intangible and dependent upon so many varying factors that it becomes a matter of judgment and experience rather than of scientific measurement. We have to distinguish between the fertility proper, "the inherent capabilities of the soil," to use the language of the old Agricultural Holdings Act, which is the property of the landlord, and for which the tenant pays rent; and the "condition" or "cumulative fertility," the more temporary value which is made or marred by the tenant. Though in the main it is easy to feel the distinction, it is often difficult, if not impossible, to draw a line of demarcation between them. Clearly the farmer in a new country on virgin soil is dependent wholly on the inherent fertility of the land, but with much of the land in this country it is hard to say how far its value is inherent, or due to long-continued cultivation. When a tenant by many years of skilful management makes a good pasture, the improvement is rightly credited to him, as fertility

which he has accumulated: the next tenant must regard the same pasture as part of the inherent capacity of the soil. Again, a farmer working on the old four-course rotation, selling only corn and meat and purchasing neither feeding stuffs nor manures, is dependent on the fertility of the soil: another farmer, carrying on an agricultural business such as market-gardening or hop-growing, and putting more into the land every year as manure than he takes out as crop, is only using the land as he would a building, as a tool in a manufacturing process.

Fertility proper is by no means a wholly chemical question, dependent upon the amount of plant food the soil contains; in many cases the physical conditions which regulate the supply of air and water to the plant, and as a corollary, the bacterial life, are far more potent in producing a fertile soil than the mere amount of nutrient material it contains. Especially is this the case in an old settled country like England, where manure is cheap and abundant; here a fertile soil is often one which is not rich in itself, but one that is responsive to, and makes the most of, the manure applied. Clay soils are not uncommon which show on analysis high proportions of nitrogen compounds and potash, and again no particular deficiency in phosphoric acid, but from their closeness of texture they offer such resistance to the movements of both air and water as to carry very poor crops. Some light soils again, such as those on the chalk, would be regarded on analysis as rich, but they are kept so persistently dry by the natural drainage, that only in a wet season do they keep the crop sufficiently supplied with water for a large crop production. On nearly all poor soils it is impossible to effect much improvement by the use of manures; in fact, manuring will not turn bad into good land, the con-

ditions limiting the amount of crop being other than the food supply. Of course, by the continued incorporation of humus into a light soil, its physical texture may be improved at the same time as its richness, until it becomes sufficiently retentive of water for the needs of an ordinary crop, just as a heavy soil may be lightened by similar additions of humus. It has already been mentioned that many subsoils, especially of the heavier loams and clays, are extremely infertile when brought to the surface, even though they may possess a fair proportion of phosphoric acid and potash and be artificially supplied with nitric nitrogen. Some of this effect is due to texture, part to the very scanty bacterial flora they possess, but it is to be noted that in arid climates the subsoils, which are not more fine-grained than the surface soils, do not show the same infertility when brought to the surface.

The soils which show the greatest fertility are, as a rule, soils of transport, uniform and fine-grained in texture, but with particles of a coarser order than clay predominating, so that, while lifting water easily by capillarity, they are freely traversed by air and percolating water. As a rule, they also contain an appreciable amount of organic matter at all depths; in Britain they have been deposited from running water, and represent the silt from which both the coarsest sand and the finest clay particles have been sifted, together with a certain amount of vegetable debris. We have nothing comparable with the typical "black soils" of the North American prairies or the Russian steppes, which contain very large proportions of organic matter to considerable depths in the subsoil: as, for example, a soil from Winnipeg that contained 0.428, 0.327, 0.158, and 0.107 per cent. of nitrogen in the top 4 feet of soil successively. Many of these deep rich soils appear

to be wind-borne: in all cases they are of very uniform texture, and represent the accumulated residues of ages of previous vegetation in a form that is capable of decay and nitrification so as to become available for subsequent crops. In a peat bog there is equally an accumulation of organic matter and nitrogen, but the mass is infertile because of the acid character of the humus, the deficiency of mineral plant foods, and the bad mechanical condition which affects the supply of air and water. In the main, then, a fertile soil is one rich in the debris of previous vegetation, and has been so sorted out by running water, wind, the agency of worms, etc., as to possess a very uniform texture, adapted to satisfy the needs of the plant for air and water. Mechanical texture is of fundamental importance: in this country many soils owe their value to this property alone; for example, the Thanet Sand formation in East Kent (a very fine-grained sand or silt), though it contains but little plant food, yet carries some of the best fruit and hop plantations in the kingdom, and farms on it command a high rent.

Condition.

The question of condition has equally its chemical and its mechanical side; it is well known that on any but the lightest soils continued cultivation makes the texture better and renders it easier to obtain a seed bed. On clay soils the effects of bad management are very persistent; any ploughing, rolling, or trampling when the soil is wet will so temper the soil that the effect is palpable until the land has been fallowed again or even laid down to grass. Once protected from the action of frost, stiff soil which has been worked when at all wet never seems able to recover its texture, as may be seen by examining the

clods that are to be found on digging up an old post, the result of the trampling when the post was originally put in.

From the chemical side "condition" means the accumulation within the soil of compounds that will by normal decay yield sufficient available plant food for the requirements of an ordinary crop, *e.g.*, of organic compounds of nitrogen which readily nitrify, of phosphoric acid and potash compounds which readily become "available" for the plant.

The condition of land cannot be restored all at once by manuring; the residues of manures left in the soil after the first season are slow-acting, *i.e.*, only a small proportion of them becomes available year by year, so that there must be a considerable accumulation of such residues before the proportion becoming available during the period of growth is sufficient for the crop. *Per contra*, the condition can be only too easily destroyed by cropping without manure; the unexhausted residue left after each year is successively less and less active, the crop falls off rapidly, till at last a sort of stationary condition is reached, and the somewhat inert materials, still left in large quantity, liberate year by year a fairly constant proportion of active plant food. The plots at Rothamsted which have been cropped without manure for more than fifty years show but little less average production during the last twenty years than in the twenty immediately preceding. For example, the unmanured wheat plot shows the following crop in bushels of dressed grain:—

First 23 years, 1852-74.	Second 23 years, 1875-97.	1898.	1899.	1900.
14 $\frac{1}{8}$	11 $\frac{5}{8}$	12 $\frac{1}{8}$	12	12 $\frac{1}{4}$

Condition may best be regarded as a state of equilibrium when the land will continue to give a fair return in crop for the manure applied; as a rule, the crop recovered by no means contains the whole of the material applied as manure, a certain portion being retained in a comparatively inactive form. With the land in condition the remaining nutrient material required for a good crop is supplied by the dormant residues in the soil which become active: at the same time, these reserves are protected from depletion by renewal from the inactive portions of the current manuring. On the other hand, if the land is in poor condition the crop gets little or no assistance from the soil, the crop is grown from the active part only of the manure: the rest of it accumulates and begins to build up condition, which, however, does not tell on the crop for some time. As a practical consequence, it is noticed that only land in good condition yields a paying return year after year for the application of manure: yet if the experiment be made of omitting the manure on a portion of the land for one year, there is little corresponding reduction of crop, as though the manure went to keep up the "condition," and the crop was grown out of that rather than from the manure applied.

From the point of view of analysis the estimation of the "condition" of a given piece of land is a difficult matter on which light is only just beginning to be thrown by the determination of "available" plant food, such as nitrates and the phosphoric acid and potash soluble in dilute acid solvents. By considering such factors as these, and the amount of humus soluble in alkali, the ratio of the soil carbon to the nitrogen, and the proportion of calcium carbonate, the agricultural chemist may form an idea as to the immediate

state of the land. Doubtless, the prevalence and distribution of such necessary bacteria as those causing nitrification are also important factors in determining the fertility, but on this point we are without exact information. It will be seen that "condition" is one of the most valuable of the properties of the soil to the cultivator; as it may be destroyed or created by the tenant during his occupation of the land, it should be as far as possible a tenant's asset, to be bought by him on entry and valued to him on leaving. The difficulty which even an experienced man finds in putting a value on so intangible an item makes it almost impossible to assess the condition of a farm, but it is desirable in every way that the outgoing tenant should be encouraged to maintain the condition of his farm by giving him due compensation for the unexhausted value both of manures and foods used in the latter years of his tenancy.

Fairy Rings.

The significance of "condition" and its dependence upon a supply of recently decayed organic matter is well seen in the development of "fairy rings" in pastures. "Fairy rings" are circles of dark-green grass, common enough in poor pastures, which are found to extend their size every year, leaving the grass within the ring of a lighter colour and of generally poorer aspect than that outside. On examining the soil immediately outside a ring, it is found to be full of the mycelium of one or two common species of fungi, but the mycelium rarely occurs in the soil beneath the ring itself, and never in that within the ring. The ring appears to be dependent on the growth of the fungus, which starts at one point and draws upon the humus reserves contained in the soil.

Having consumed whatever humus is available, the mycelium must proceed into the annular area of soil immediately round the first patch, thus from year to year it spreads outward. After the death of the fungus, there is left behind in the soil it has just occupied a quantity of organic matter, which readily decays and becomes available for plant nutrition; thus a ring of luxuriant vegetation immediately follows the death of the fungus. In other words, the humus of the soil, slow to decay and nitrify in the usual way, is changed into material undergoing rapid change by its preliminary conversion into the tissue of the fungus. At the same time, as the supply of rapidly acting plant food has been solely derived from the soil, the ultimate result is the impoverishment of the soil within the ring by the development of the fungi and the subsequent luxuriant growth of grass.

The following figures relate to the composition of the soil (mean of five examples) within, on, and outside fairy rings.

	Carbon per cent.	Nitrogen per cent.	Nitrates per million.
Outside the ring . . .	3.30	0.281	2.44
On the ring . . .	2.99	0.266	11.46
Inside the ring . . .	2.78	0.247	1.03

It will be seen that the unchanged soil outside contains the most carbon and nitrogen; the ring itself contains an intermediate amount, and the least is contained within the ring after the luxuriant vegetation has passed away. The soil on the ring is in high condition, because the organic residues it contains are

recently formed and will change rapidly; after they have been cropped out, the land is less able to support a crop, even though there is still much plant food left in the soil. The last column in the table (the analysis of a single example only) shows the difference in available nitrogen; and though in a pasture there are never many nitrates to be detected, so rapidly are they seized upon by the crop, still the organic nitrogen compounds in the soil must be in a more nitrifiable condition on the ring to yield the results there shown.

Sterility of Soils.

Few soils occurring in this country can be described as absolutely barren, yet from time to time land is met with which yields such poor crops that it may fairly be designated as sterile. The causes of sterility are various; amongst them may be enumerated both the want and the excess of water due to texture and situation, deficient aeration, the absence of calcium carbonate, and the toxic action of certain compounds, such as the salts of magnesia, iron pyrites or ferrous salts generally, and common salt itself. An acid reaction of the soil, which is highly prejudicial to vegetation, is generally due to one or other of the causes enumerated above.

The sterility brought about by a deficiency of water is only seen in this country when the soil is so entirely composed of coarse sand that it possesses no retentive power for the rainfall; even then the absolutely bare condition does not persist long, and may be attributed as much to the lack of nutriment as to the want of water. Little by little vegetation is found to creep over recent deposits of coarse sea-sand and shingle, until a turf is established. As a rule, such deposits have permanent water at a comparatively short distance below,

and by this the vegetation is maintained; but where a coarse, open-textured sand occupies the uplands, as on the Bagshot and Lower Greensand formations of the south of England, or the Bunter beds of the Midlands, the soil is kept so poor that it has largely remained common heath land, never having been worth the expense of enclosing. Allusion has already been made, under the head of drainage, to the evils which ensue in a water-logged soil: from time to time clays are met with of so close a texture that the vegetation suffers in an analogous manner through deficient aeration. On certain areas of the Oxford Clay and London Clay, and the Boulder clays derived therefrom, pastures degenerate after a few years into a mass of creeping rooted plants like bent grass, and the land must be broken up afresh in order to aerate it before any crop can be grown.

Sterility due to chemical causes is perhaps most generally caused in this country by the absence of calcium carbonate from the soil. When this happens on light sandy land it will become evident by the tendency of black mild humus to accumulate, by the paucity of leguminous plants in the herbage, and by the prevalence of fungoid diseases like "finger-and-toe." On strong lands, and when accompanied by water-logging, black acid peat accumulates: the soil shows an acid reaction, oxide of iron forms below the surface, and the soil water contains soluble iron salts, as is seen by the iridescent scum which spreads over any water standing in the ditches.

Another source of sterility is the presence of un-oxidised iron salts in the soil: many clay subsoils are coloured dark blue or green by double ferrous silicates like glauconite, or by finely disseminated iron pyrites. Until these materials become oxidised to ferric hydrate the soil remains sterile: particularly is this the case

with iron pyrites, which in the form of marcasite easily oxidises to yield both ferrous sulphate and sulphuric acid. Voelcker has recorded three instances of soil sterile through these causes: one was land reclaimed from the bed of the Haarlem Lake, which contained 0.71 per cent. of iron pyrites and 0.74 per cent. of ferrous sulphate, as well as some insoluble basic sulphate of iron. Another example of land reclaimed from the sea contained 0.78 per cent. of pyrites and 1.39 per cent. of ferrous sulphate. Cultivation with a free use of lime and chalk is the best means of ameliorating such soils, which always show an acid reaction.

Kearney and Cameron in America have shown that salts of magnesia possess, even in solutions of great dilution, a toxic action upon plant roots, which is much diminished if calcium salts be present at the same time. Loew at the same time has indicated that a comparative excess of magnesium over calcium in certain soils results in sterility. With this may be correlated the fact that the soils resting upon the serpentine, which is a compound containing magnesia, are notoriously poor, also that certain very impoverished clays on the Wealden formation contain a high proportion of magnesia.

Sterility caused by salt is sometimes to be seen in this country in the marshes near the sea: more often a "salting," even where the sea has regular access, is clothed with vegetation which is able to endure very considerable proportions of salt. Most farm crops will grow in soil containing 0.25 per cent. of salt, and in the reclaiming of the old sea lake of Aboukir in Egypt, it was found that grasses would grow freely when there was still as much as 1 per cent. of salt in the soil, and a scrubby winter crop of barley was grown on soil containing more than $1\frac{1}{2}$ per cent. "With 2 per cent. of salt in the soil, a

fair crop of dineba, 2 feet high, can be grown; with 1 per cent. it attains its full height of 4 feet, and sells as a standing crop at from 20s. to 25s. per acre. For 'berseem,' or clover, the percentage of salt should not exceed $\frac{1}{2}$, and about the same for 'sabaini rice.'" Much, however, depends upon the relations between water supply and evaporation, as to the amount of salt in a soil which would be tolerable to vegetation. From time to time cases occur in this country of crops being destroyed, and land rendered sterile by the incursion of sea water; the effect is not always apparent at first, though sea water contains as much as 2.7 per cent. of sodium chloride and 0.5 per cent. of other soluble salts, but the permanent pasture becomes seriously injured, and for two or three years even the arable land yields very indifferent crops. Dymond has attributed this after effect to the injurious action of the sea water on the texture of the soil, due to the attack of the sodium chloride upon the double silicates of the soil, lime in particular being displaced by soda. The result is the formation of a more "colloidal" clay, which will not settle down for many weeks when suspended in water. Biological effects may also be surmised: it is always seen that the earth worms are killed in the land which has been flooded with sea water, and in view of the known unfavourable effect of chlorides on nitrification, it is possible that the rate of production of nitrates in the inundated soil is seriously lessened.

Alkali Soils.

In arid climates the rainfall is often insufficient to produce percolation through the soil and subsoil into the underground water system; in consequence, the salts produced by the weathering of the rocks tend to accumulate in the subsoil, and may be brought to the

surface by capillary rise so as to cause almost entire sterility. Such bad lands are known in America as "alkali soils," but they are well known in India and in Egypt, and indeed are common to all countries possessing a small rainfall and great evaporation. In its most aggravated form alkali land, particularly at the end of the dry season, shows an actual white efflorescence of salts at the surface; all vegetation is destroyed, except one or two plants which seem tolerant of large quantities of saline matter, such as "greasewood," *Sarcobatus* sp., or the Australian "saltbushes," *Atriplex semibaccatum*, etc. In some cases the alkali is chiefly located at a slight depth in the soil, and only effloresces on spots a little below the general level, where the subsoil water comes to the surface. A heavy rainfall may be followed by a rise of alkali, because a connection is then established between the saline subsoil water and the evaporating surface, whereupon a continuous capillary use of salts takes place, followed by their crystallisation at the surface. *Per contra*, the establishment of a soil mulch, and shading the ground with a crop, so that evaporation only takes place through the leaves, will aid in keeping the alkali down. The composition of the salts varies; as a rule, sodium chloride predominates, with some sulphates of sodium, magnesium, and calcium, in which case the material is known as "white alkali." Under other conditions the material is really alkaline, containing carbonate and bicarbonate of soda; the saline solution then dissolves some of the humus present in the soil, and also causes the resolution of the clay material into its finest particles, so that the soil forms an intensely hard black pan when dry, which is known as "black alkali." The carbonates are far more injurious to vegetation than the neutral salts; few plants can bear as much as 0.1 per cent. of sodium






FIG. 16.—Nature and Distribution of Alkali Salts (Hilgard).

carbonate, but are tolerant of 0.5 to 1 per cent. of the other salts.

Though the alkali salts are sometimes chiefly sulphates, more commonly sodium chloride is the main constituent, together with the products of its action in mass upon calcium carbonate and sulphate. The diagram (Fig. 16), due to Hilgard, shows the distribution with depth of alkali salts in this type of soil at Tulare, California; the greatest accumulation of salts takes place at a depth of 30 inches, the point to which the annual rainfall penetrates. One of the most difficult features presented by the cultivation of land in arid regions where alkali occurs in the soil, comes from the tendency of the sterile spots to spread and the alkali to be brought to the surface as soon as irrigation water is employed, for without irrigation agriculture is hardly possible. Many districts, which at first carried good crops and were even laid down in fruit or vines, have been ruined through the rise of alkali to the surface by irrigation; in fact, in all these arid regions it becomes exceedingly dangerous to raise the water table in the land anywhere near the surface, because capillarity then causes a rise of the salt charged water, and evaporation concentrates it on the top. Just as some of the worst alkali land occurs where rain falling upon the surrounding mountains finds its way by seepage through the subsoil rich in salts, and then rises to the surface in the dry basin areas below, so the introduction of irrigation canals pouring large volumes of water upon the land, may equally establish the capillary connection between the subsoil salts and the surface. The following extract from Bulletin No. 14, U.S. Dept. of Agric., Div. of Soils, dealing with alkali soils in the Yellowstone Valley, shows the evil effects of incautious irrigation:—

“Irrigation has been practised for twelve or fifteen

years. The water for the main ditch supplying the valley is taken out of the river nearly 40 miles above the town of Billings. When the country was first settled, and indeed above the ditch at the present time, the depth to standing water in the wells was from 20 to 50 feet, and there was no signs of alkali on the surface of the ground. Under the common practice of irrigation, however, an excessive amount of water has been applied to the land, and seepage waters have accumulated to such a degree that water is now secured in wells at a depth of from 3 to 10 feet in the irrigated district, while many once fertile tracts on the lower levels are already flooded, and alkali has accumulated on them to such an extent that they are mere bogs and swamps and alkali flats, and the once fertile lands are thrown out as ruined and abandoned tracts."

Nor is it necessary that the subsoil be charged with salts for irrigation to produce alkali land; the mere continual evaporation of ordinary river or spring water may cause such an accumulation of saline matter at the surface as is harmful to vegetation. This is well seen in Egypt, where perennial irrigation is practised with the Nile water, and the following quotation from Willcocks' *Egyptian Irrigation* will explain the action that takes place:—

"The introduction of perennial irrigation into any tract in Egypt means a total change in crops, irrigation, and indeed everything which affects the soil. Owing to the absence of rain, the land is not washed as it is in other tropical countries, unless it is put under basin irrigation.

"An acre of land may receive as many as twenty waterings of about 9 cm. in depth each, *i.e.*, a depth of water of 1.80 metre per annum, which is allowed to stand over the soil, sink about half a metre into

the soil, and then be evaporated. Since the Nile water, especially in summer, has salts in excess, these salts accumulate at the surface, and if not eaten down by suitable crops, soon appear as a white efflorescence. While the spring level is low, capillary attraction cannot bring up to the surface the spring water, which generally contains a fair proportion of salts, but where the spring level is high the salt-carrying water comes to the surface, is there evaporated, and tends to further destroy the soil. In old times the greater part of the cultivation land was under basin irrigation, and was thoroughly washed for some fifty days per annum ; while the rest, consisting of the light sandy soils near the Nile banks, was protected by insignificant dykes, which dykes were burst every very high flood, and thus allowed to be swept over by the Nile and washed once every seven or eight years. All this is at an end now in the tracts under perennial cultivation, and other remedies have to be found."

The only remedy for the evils attending irrigation is the introduction of drainage channels at a lower level than the canals bearing the irrigation water ; in this way the percolation through the soil, which in humid climates naturally removes the salts not taken up by the crops, is effected artificially ; there is some apparent loss of water, but this is absolutely necessary to maintain the land free from injurious salts. As an example, the following passage may be quoted from one of Major Hanbury Brown's reports on Egyptian Irrigation :—

"It has been ascertained that the blessing of improved water supply which has resulted from the barrage having been made to do its duty, has been attended in some localities with the evils due to infiltration and want of drains. The remedy, as pointed

out in last year's Report, is to remove the want of drains by digging them, and to provide the means of washing out the salt, brought to the surface by infiltration in the shape of a liberal supply of water, by which the salt would be carried away in solution along the drains, or be forced down below the surface of the soil to a depth at which it would be harmless. The liberal water supply is not to be obtained except by the construction of a storage reservoir at Aswan or elsewhere."

It was the neglect of drainage, when irrigation canals were introduced, that led to so widespread a deterioration of land in Egypt. To quote from Lord Milner's *England in Egypt*:—

"But perhaps the worst feature of all was the neglect of drainage, which was steadily ruining large tracts of country. Even where drains existed, they were frequently used also as irrigation channels, than which it is impossible to conceive a worse sin against a sound principle of agriculture. In some cases these channels would be flowing brimful for purposes of irrigation, just when they should have been empty to receive the drainage water. Elsewhere the salt-impregnated drainage water was actually pumped back upon the land.

"It was the want of drainage which completed the ruin of the Birriya, that broad belt of land which occupies the northern and lowest portion of the Delta, adjoining the great lakes. There are upwards of 1,000,000 acres of this region, now swamp, or salt marsh, or otherwise uncultivable, which in ancient times were the garden of Egypt."

It has been the business of the English irrigation officers since the occupation to restore and improve the drainage system, and to begin the reclamation of

the salted areas by cutting drainage canals and passing enough of the abundant winter flood water through the soil to wash out the salts into these drains.

Hilgard in California has also indicated that it is impossible to wash the salts from the soil, even by leaving the water to stand upon the surface for some time, unless provision is made to remove the salted water by under drainage. In the case of black alkali, however, the soil has become too impervious to allow water to percolate at all; the first remedial measure is to incorporate considerable quantities of gypsum with the soil; this will interact with the sodium carbonate, producing sodium sulphate and calcium carbonate, at the same time precipitating the humus in a flocculent form. If now underdrainage be brought into practice the soluble salts can be washed through, and a very fertile soil results, owing to the presence of the finely divided humus and calcium carbonate. Where underdrainage is hardly practicable because of the expense, irrigation water should be used in as limited amounts as possible, and every care should be taken to keep the surface tilled and under crop, so as to minimise evaporation from the bare ground. In humid countries like our own, damage due to the accumulation of salts are rare; the author has, however, seen one case where the vegetation of a lawn was destroyed during a hot dry spell of weather by continuously applying water in quantities which never washed down into the subsoil, but evaporated every day. An efflorescence practically identical with white alkali is sometimes seen on greenhouse borders, which are constantly watered, but never sufficiently to cause percolation; and gardeners again are familiar with the check of growth which sometimes occurs in the case of plants long in one pot

and constantly watered with hard water. The remedy is to water from time to time so heavily as to cause abundant percolation and thus wash all the salts out.

Amendments of the Soil.

Many soils, without being absolutely sterile, carry very poor crops until their physical character has been altered by the admixture of some considerable quantity of one or other of the constituents of a normal soil that may happen to be originally wanting. These amendments of the soil by the mixture of other soils date from the time that enclosures first began to be made; they were perhaps at their height during the early years of the nineteenth century, after the middle of which they rapidly diminished as it began to be less and less remunerative to "make" land, until at the present time the fall in the prices of produce and the rise in the cost of labour have put an end to all such operations. Among other causes of this neglect may perhaps be set down the increased use of artificial manures; men began to take too exclusively a chemical view of the functions of the soil, and shirked expenditure which did not seem to add directly any food for the plant. However, it is probable that with modern facilities for moving earth on a large scale by steam power, the improvement of much poor land might even now be profitably undertaken.

The operations which may be grouped under the head of "amendments of the soil" comprise—drainage, which has been dealt with elsewhere; the marling and claying of light sands; the reclamation of peat bogs; the improvement of clay soils by liming and chalking, or by paring and burning; and lastly, the creation of new alluvial soils by warping.

Warping.

The operation of "warping," or "colmetage," is only possible in the vicinity of tidal estuaries, where lands exist below the level of high water, and is in this country practically confined to the estuaries of the Humber and Ouse. Warping is carried out by the construction of a wide drain protected by sluices from the tidal river to the low land, which is first divided by embankments into compartments of various sizes up to 150 acres. When the embankments have become consolidated the flood tide, heavily charged with suspended matter which is really fine earth brought down by the river, is admitted into the compartment, where it deposits most of its silt and is allowed to run off when the level of the water in the river has fallen during the ebb. The operation is repeated until a layer of silt has formed 1 to 3 feet thick over the land, which is then dried and brought under crop. As the chief deposit is always near the mouth of the drain, where the velocity of the silt-bearing current is first checked, the position of the inlet must be shifted about to secure a uniform deposit all over the land, and to distribute the valuable fine silt which settles furthest from the inlet. In some cases the sluice gates are automatic, and water is admitted and drawn off at every tide, but in others only every other tide is admitted, thus giving time for the deposit of the finer particles, and greatly improving the character of the resulting land. As a rule, only the spring tides are utilised, because the suspended matter is then at its maximum, and the process is confined to the summer months, to avoid danger from flooding when there is much land water about. In exceptional cases land

may be warped 2 or 3 feet deep in one year—from January to June—in other cases, where the water is less charged with sediment, or the land is at a higher level, an efficient warping, which should not be less than 18 inches deep, requires three or four years. When finished, the land is allowed to dry and consolidate, drainage grips are then thrown out, and a light crop of oats, in which are sown clover and ryegrass, is taken; after the seeds have been down two years the land is generally ready to carry wheat. Warp soils are, as a rule, fertile, and noted for growing seed corn of high quality; they are to all intents and purposes artificial alluvial soils, composed entirely of the finer sands and silts without much clay material, and are comparatively rich in organic debris and other plant food, except perhaps potash. The fertilising of the Egyptian land by the red Nile flood water, the formation and improvement of river meadows by winter flooding, are both analogous to the process of "warping."

Marling and Claying.

Many light and blowing sands, almost too pure to permit of any vegetation, have in their immediate neighbourhood a bed of marl or clay which can be easily incorporated, practically creating a soil where there was none before. Among the New Red Sandstones of Cheshire and the Midland Counties beds of true marl occur and were at one time enormously worked, so that every farm and almost every field shows its old marl pit; the sandy Lower Greensand soils in the Woburn district have been extensively marled from the adjoining Oxford Clay, and many of the Norfolk soils have been made out of blowing sands, by bringing up the clay which immediately underlies them. The

earlier volumes of the *Journal of the Royal Agricultural Society* contain numerous accounts, showing how much land was brought into cultivation by these means in the first half of the nineteenth century.

“He that marls sand may buy the land,
He that marls moss shall suffer no loss,
But he that marls clay flings all away.”

The usual practice in Norfolk was to open pits down to the marl or clay, dig and spread it at the rate of 50 to 150 loads to the acre on a clover ley or turnip fallow. In some cases trenches were opened all along the field, and the clay thrown out on either side. By the action of the weather, drying and wetting followed by frost, the clay comes into a condition to be harrowed down, after which it can be ploughed into the ground.

The effect of marling or claying is more evident after a year or two than at once, because the fine particles become each year more thoroughly incorporated with the soil. The effects are to be seen in increased crops, the production of better leys and pastures, greater resistance to drought, and particularly an increased stiffness in the straw where manures are used to grow the crop.

Marl containing carbonate of lime is always far more valuable than clay; pure clay is so little friable, and so sterile itself, that it effects an improvement only slowly; marl not only ameliorates the texture but adds at once a supply of carbonate of lime, potash compounds, and in some cases phosphoric acid also. Clay and marl both have a tendency to sink and eventually require renewing, but if well done will last for thirty to fifty years, because the accumulation of humus and fibrous root-remains, due to the increased crops, itself binds the soil together.

At the present day the need of marling or claying on a small scale is often seen in old gardens, particularly in old town gardens which are situated upon gravel soils, initially very short of the finer soil particles. The constant breaking of the surface by cultivation, and the use of large quantities of stable manure, which decays and leaves the soil open, result in a continual washing down of the finest particles, until the remaining soil loses all power of cohesion and of resisting drought, falling into a dusty powder immediately on drying. A coating of clay in the early autumn, or, better still, of good marl, is the only method of giving consistency to such a soil, and soon remedies its worst defects, such as susceptibility to drought and rapid fluctuations of temperature, and tendency to produce soft vegetation, very liable to disease.

Reclamation of Peat Land.

One of the earliest methods of bringing peat land in the Fens and similar districts into cultivation was to dry the land by means of open drains and break up the surface with the breast plough; the clods were then gathered together, and burnt when dry, afterwards the ashes were spread and a crop of rape taken. The fire was never allowed to burn too fiercely, the object being to obtain charred residues rather than white ashes. The effect of burning the peat was to provide a certain amount of ash rich in saline matters and particularly in alkaline carbonates, thus correcting the two great faults of the remaining peat, its deficiency in mineral matters, and its sour reaction. At the same time the weeds and other coarse vegetation occupying the surface were destroyed, and a clean seed-bed prepared for the crop. However, the process of burning is a

very wasteful one, involving the loss of the combined nitrogen contained in the accumulated organic matter, and after a few repetitions the land was found to be seriously depleted of its reserves of humus. Burning became replaced in the Fens by a marling process, especially where the peat was of a sandy nature ; trenches were opened to the bed of marl or clay always found beneath the peat, and the clay thrown out and spread at the rate of 100 loads or so per acre, the burning process being reserved for the first reclamation, when a mass of surface vegetation had to be got rid of. In other districts, where marl is less available, peat has to be brought into cultivation by draining the land with open cuts, allowing some considerable time to elapse during which the peat dries, shrinks, and consolidates, and then correcting the acidity with lime. It is desirable to use large dressings of mineral manures like basic slag and kainit to compensate for the deficiency in mineral matter, especially where the peat is initially of an acid character. In the Fens the peat is sometimes found to be mild humus containing lime ; this does not respond to liming, and gives better crops with superphosphate than with basic slag.

Paring and Burning.

When the poorer clay soils were first taken into cultivation, a beginning was generally made by "paring" the surface with the breast plough, and "burning" the clods as soon as they were sufficiently dry. The clods were made up into heaps a yard or so in diameter with the brushings of the hedges and all the rough surface vegetation, together with as much clay as was judged prudent. Each heap was then allowed to burn slowly and char the clay, without permitting the heat to rise

sufficiently to vitrify the clay or dissipate such valuable material as the alkalis of the ash. The resulting ashes effected a great improvement in the soil: the clay was partially dehydrated, or at least coagulated, thus providing a certain amount of coarse material to ameliorate the texture; in the charred clay also, some of the potash was rendered more available, while the plant residues provided mineral salts and alkalis to promote nitrification. The drawback to the process is the inevitable loss of nitrogen to the soil; but any one who has noticed how freely crops grow on the patches of arable land where couch heaps have been burnt the season before, will see that, for the time being, the fertility of the soil is increased by the process. Other advantages of burning lie in the destruction of weeds and insect life of all kinds, and although it has been almost wholly discontinued at the present day, the older writers on agriculture are unanimous as to its beneficial effects in bringing poor clay land into cultivation.

A variation on the old process of "clod burning" consists in "border burning," in which clay is dug from one corner of the field and burnt by means of the couch and other weeds cleaned off the land, the hedge trimmings, etc.; the burnt clay is then spread over the surface to improve the texture of the soil. Without doubt the latter process might still be profitably adopted where heavy clay land is under the plough; if every year some clay were added to the fires made from the weeds and hedge trimmings, valuable material for lightening the soil would be obtained without wasting too much soil nitrogen.

Of course the incorporation of any large-grained material will improve the texture of clay soils; in some cases sand has been dug and spread with advantage;

road scrapings, town refuse, and even coal ashes help to lighten the soil, though, in the case of gardens, coal ashes should be avoided.

Liming and Chalking.

Of all the methods of improving the soil, other than actual manuring or cultivation, none is more important than the incorporation of lime or chalk. It has already been indicated that many soils exist, chiefly clays and sands, containing less than 1 per cent. of carbonate of lime; on all such land liming produces very pronounced effects, both on the physical texture of the soil and on the character of the resulting vegetation.

It is on the clays and other strong soils that lime produces the greatest alteration in texture; its effect in coagulating and causing the finer particles to form into aggregates, which remain loosely cemented by the carbonate of lime, has already been discussed. The soil becomes much less retentive of water, percolation is increased so that the limed land is drier and warmer, admits of cultivation at an earlier date in the spring, and is far more friable when dry. In fact, the liming gives a coarser texture to the clay soil, and all the effects pertaining to the coarser texture, such as diminished capacity for retaining water and consequent greater warmth, less shrinkage and tendency to cake on drying, are all manifest after the application of lime. It does not, however, follow that though the season is made earlier through liming the crop will mature more readily; in many cases in dry seasons crops upon clay ripen prematurely, because the drying up and shrinkage of the impervious clay cut the roots off from all access of moisture. The liming, by opening up the soil to the motion of water by surface tension, keeps the plant growing for a longer

period ; at the same time, the increased amount of plant food rendered available also tends to prolong the duration of growth. On very light soils the addition of lime acts to a certain extent as a binding material, and increases the cohesion and water-retaining power of the soil, but it is not so effective in this respect as humus. Besides its physical effect upon the texture of stiff soils, lime has a very powerful chemical effect, liberating freely the reserves of plant food of all kinds in the soil and rendering them available to the plant ; so that on soils naturally deficient in carbonate of lime, manures of all kinds can only find their proper value if lime be also used from time to time. On soils that have been under intensive cultivation for a long time immense reserves of plant food have been accumulated, which only require the addition of lime to bring them into action. As an example may be quoted the result of applying lime to an old hop garden at Farnham, Surrey, where the soil consisted of an alluvial loam, very deficient in carbonate of lime, and heavily dressed with organic manures for many years previously. The plots chosen for comparison received a complete artificial manure with or without 1 ton of lime per acre ; the figures for the crops in the following table have been reduced to percentages to eliminate the great fluctuations due to season.

Year.	ARTIFICIAL MANURES.	
	With Lime.	Without Lime.
1895	100	70
1896	100	84
1897	100	80
1900	100	81
1901	100	90

Of course, as lime itself supplies no food to the plant, but only sets in action the dormant residues already present in the soil, the forcing of crops by the aid of lime alone soon results in the exhaustion of the land. Hence the old saw :—

“Lime, and lime without manure,
Will make both land and farmer poor.”

The exact effect of lime in promoting fertility depends upon the plant food in question. We have already seen that all the decay processes which result in the oxidation of the humus are promoted by the presence of a base to combine with the organic acids produced by the decay, and, in particular, that the presence of an easily attacked base is necessary for nitrification. As a nett result, the oxidation of the humus and the formation of nitrates is much increased by a dressing of lime, which, indeed, is the first indispensable step towards rendering available the rich organic residues accumulated in a sour soil. As regards the mineral constituents, lime has a very marked power of bringing potash into a soluble state; the double hydrated silicates of potash and alumina, etc., which result from the partial breaking down of feldspars and are the sources of the potash of our soils, are decomposed, lime being substituted for the potash going into solution. It is a case of mass action, where the addition of one soluble constituent to the soil will increase the amount that goes into solution of all the other constituents which are capable of being replaced by the base added; the extent of the action is therefore dependent upon the amount of lime used. The fact that more potash has been rendered available in limed soils is clearly seen in the character of the vegetation, *e.g.*, in an increased proportion of

clovers in the herbage of pasture or hay land. The action of lime as a liberator of potash is illustrated by the effect of a dressing of chalk applied in 1881 to part of the permanent grass plots at Rothamsted; by 1884 differences began to be manifest, the chalk caused a change in the herbage of those plots which had been receiving potash each year for twenty-five years previously, increasing the production as a whole, and particularly increasing the proportion of leguminous plants in the herbage. On the plots, however, which had been receiving no potash, and therefore contained no recently accumulated reserves of this material, the chalk had practically no effect, either in the weight or character of the crop.

To some extent lime seems able to act as a liberator of phosphoric acid in the soil. As pointed out by Thénard, lime is able to act upon the very insoluble phosphates of aluminium or iron which are present in many soils, and, by converting them into phosphate of lime, renders the phosphoric acid more available for the plant.

Besides its specific actions in thus rendering more soluble the soil constituents which nourish the plant, lime exerts a very beneficial action by maintaining the neutral reaction of the soil; it neutralises the acids produced by the decay and nitrification (see p. 160) of the organic matter in the soil, or those due to the oxidation of materials like iron pyrites in other soils (see p. 222). Again, as has been shown already, it is necessary as a base to satisfy the requirements of artificial manures like sulphate of ammonia, superphosphate, and kainit (see p. 192), or to prevent the soil being invaded by such organisms as the destructive fungus causing "finger-and-toe" (see p. 187). It must, however, be clearly realised that lime is wanted as a

base, not as a compound of calcium, necessary though calcium itself may be to the economy of the plant; and that only carbonate of lime (chalk, limestone, etc.) or quicklime and slaked lime, which promptly become carbonate of lime when incorporated with the soil, are capable of acting as the required base. Other calcium compounds, as superphosphate of lime or sulphate of lime (gypsum), or phosphate of lime in bones, etc., are either acid or neutral, and do not supply the base required to effect the beneficial actions set out above; they cannot replace lime or chalk—in fact, they do not contain any “lime” in the farmer’s sense. Unfortunately, it has been too often supposed that the use of artificial manures, such as superphosphate of lime, removed the necessity of a periodical liming of the soil, and some of the neglect into which this all-important operation has fallen may be set down to the unfortunate confusion hanging round the word lime. However, as will have been gathered from a consideration of the effects of sulphate of ammonia in depleting the Woburn soil of carbonate of lime, the use of artificial manures generally demands an increased rather than a lessened attention to the periodical liming of the land.

The method of liming which was formerly in vogue consisted in applying very large quantities of quicklime at comparatively long intervals, 100 to 150 bushels per acre (=2 to 4 tons) every eight or ten years, or an initial dressing of 100 bushels, with a further dressing of 50 bushels per acre every third year. The reason for this interval lies in the fact that the best effects of lime are to be seen after the lapse of a year or two; the material becomes carbonate, which, being insoluble, is incorporated with the soil and passes into solution as bicarbonate but slowly. The immediate effect of lime may even be a diminution of the crop

if it be used on very rich land, or in actual contact with fresh dung; under these conditions there appears to be some loss of ammonia by volatilisation. Of course the effect of lime is not very persistent, and the dressing must be repeated; as the farmers say, the "lime sinks in the land," *i.e.*, carbonate of lime is removed from the surface soil by solution as bicarbonate.

In carrying out the operation of "liming," the aim should be to ensure as fine a division as possible, so as to incorporate the material intimately with the soil. In some cases the lime is thrown out in heaps on the stubbles in autumn, and slaked by pouring on water, the hot slaked powder into which the quicklime falls being immediately spread over the land. This method only answers with "fat" limes, which slake and fall readily to a dry powder; a better method is to lay up the quicklime in heaps and cover the heaps with soil, in which case the lime slakes gradually to a fine powder that can be spread before the plough. It is not wise to spread the quicklime over the land, as much of it, after slaking and becoming carbonated, remains in lumps which cannot be reduced to a powder.

The expense of liming in this fashion is considerable, and as the action is not immediate, owing to the difficulty of getting the material mixed with the soil, it is desirable to replace it, if possible, by a cheaper process. This has been attained by the use of ground lime, which is at the present time prepared by most lime works for the use of builders; 5 cwt. of ground lime per acre, distributed by a manure barrow or by one of the artificial manure distributors now manufactured, will be found more effective for one or two seasons than ten or twelve times as much applied in the old-fashioned method. Of course such a small dressing of ground lime requires renewing more fre-

quently ; but, as the expense is comparatively trifling, both for labour and material, as compared with the older process, it may be hoped that on many soils this all-important operation will assume its old prominence in the routine of farming.

Considerable differences are to be seen in the character of lime made from the various calcium carbonate rocks burnt for lime in the British Islands ; in the main a distinction may be drawn between the white "fat" limes made from the white chalk, the mountain limestone and other comparatively pure deposits of calcium carbonate, and the "thin" grey or stone limes made from less pure and more argillaceous limestones. The "fat" limes are the purer, slake readily and swell considerably in the act, forming afterwards a bulky white powder ; the "poor" or "thin" limes slake with comparative difficulty and do not increase much in bulk. The "thin" limes partake somewhat of the nature of a cement, setting after mixture with water, and are more esteemed by builders than the "fat" limes, which harden with extreme slowness and are chiefly employed for plastering and kindred work. Naturally the "fat" limes are preferable from an agricultural point of view, both for their purity and the finer condition into which they fall ; unfortunately few of the lime works grind the white lime in the ordinary course of trade, as they do the builders' lime.

The lime made by burning the magnesian limestone which occurs in Durham, Yorkshire, Derbyshire and Notts, is disliked by farmers and regarded as injurious rather than beneficial to the land. It contains 50 to 80 per cent. of lime and 4 to 40 per cent. of magnesia, which latter constituent may be the cause of the ill effects.

The following analyses show the mean composition

of several samples of "fat" and "poor" lime, being "white" and "grey" lime respectively, made from the Upper and Lower Chalk of the North Downs:—

	White Lime.	Grey Lime.
Caustic Lime	90.20	74.00
Carbonate of Lime	2.40	2.66
Magnesia	0.35	0.38
Oxide of Iron	0.52	1.00
Alumina	1.70	7.60
Silica as Soluble Silicates	2.60	8.60
Insoluble Residue25	.94
Water, Alkalis, etc.	1.98	4.82
	100.00	100.00

In place of lime, chalk may often be used with advantage when it is readily accessible; for example, on one side of the Chalk formation the Gault and the upper beds of the Lower Greensand, and on the other side the London Clay and the Bagshot Sands, are generally in need of lime, and are never very remote from the outcrop of the chalk. The superficial clays and sands lying on the Chalk itself are often deficient in lime, and may be readily chalked by sinking shallow pits. It must be remembered that much larger quantities of chalk than of lime are needed to produce a given effect; not only is the chalk equivalent chemically to about half its weight of lime, but in practice it can never be reduced to so fine a state of division as lime obtains by careful slaking. In chalking, it is desirable to obtain the soft upper white chalk from a pit, so that it is saturated with quarry water; if then spread over the land in autumn it gets frozen while still full of water, and becomes reduced to a comparatively fine powder which

can be ploughed in if on arable soil, or spread with a harrow on the pastures. Very large quantities of chalk are used, up to 100 loads to the acre ; naturally the effect of such treatment is more permanent than the usual liming.

Chalk is perhaps more suited than lime to very light sandy soils like the Lower Greensand or the Bagshot beds, for on such dry, hot soils the application of quicklime is apt to result in too rapid a decay of the organic reserves of the land ; on clay soils, however, quicklime is preferable, as it is a much more effective agent in coagulating and improving the texture of the clay.

CHAPTER X

SOIL TYPES

Classification of Soils according to their Physical or Chemical Nature—Geological Origin the Basis of Classification—Vegetation Characteristic of Various Soil Types: Physical Structure, Chemical Composition, Natural Flora and Weeds characteristic of Sands, Loams, Calcareous Soils, Clays, Peat, Marsh, and Salt Soils—Soil Surveys, their Execution and Application.

PERHAPS the question of the greatest practical importance in connection with the scientific study of soils is their classification into certain types defined by their physical or chemical properties, and the allocation of these types to their appropriate areas, so as to obtain a soil map of any given district. Despite disturbing factors, to which allusion will be made later, certain types of soil persist over wide stretches of country, and are characterised not only by a general resemblance in chemical or physical constitution, but by a corresponding similarity in the natural flora they bear, and their appropriateness to certain crops. The constancy of the soil types is the result of a common origin from the same kind of rock, and the difficulty lies less in recognising the types than in drawing boundary lines, so imperceptibly does one class shade off into another. The only classification that can be at all general, is one based upon the physical structure

and texture of the soil, viz., into sands, loams, and clays, with subdivisions dependent on the presence or absence of calcium carbonate, and upon the situation, as causing the accumulation or otherwise of humus.

In attempting to review the vegetation appropriate to different types of soil it will be found that two distinct factors must be taken into account—the relations of the soil to water, and its chemical constitution—which factors often interact in a complex fashion, different causes producing the same effect. A plant, for example, may be found upon sand because of its dryness, or, because of the absence usually associated with sand of calcium carbonate; another plant, having adapted its structure to use very small quantities of water, may equally well be found on a dry sand, or on a clay which holds so much water as to be injurious to the ordinary plant.

Plants have adapted themselves to conditions of dryness in very diverse ways; in some cases, as in gorse or broom, the leaf surface is much restricted; in others, the thickness of the cuticle has been increased, or the surface of the leaf is thickly clad with hairs; in other cases the leaves possess special tissues for storing water. Such plants are known as “xerophytes,” and are found on soils which appear to differ very much from one another, for a soil may contain plenty of water and yet be physiologically dry, because of the presence of some other constituent hindering the absorption of water by the plant.

The areas on which xerophytic plants are found include not only the true desert areas, where great heat and intense illumination occur during the larger part of the year, but also the pervious sandy soils retaining very little moisture—sand dunes, shingle flats, and the like. Again, the plants of alkali soils and of

salt marshes invaded by the sea, develop a xerophytic structure, because they would be injured if they absorbed large amounts of saline soil water. Peaty areas also act in the same way, for it is found that the humic acids in such soils withhold the water from the plant very obstinately. Exposed elevated regions with a low temperature, by reducing the power of the roots to absorb moisture, render it necessary that the plant should lose little by transpiration; hence we see certain conifers flourish both on dry sandy soils and wet elevated moors.

As regards the chemical side of the question, the most important soil constituent affecting vegetation is calcium carbonate; a large number of plants seem absolutely intolerant of lime in the soil, while others are rarely seen off limestone and chalk areas. Even among the humus-loving plants a different flora is found on the acid peaty areas from that prevalent on the mild humus areas where the soil water contains calcium bicarbonate in solution.

But, however characteristic the general aspect of the vegetation may be upon the different types of soil, it is rare to find cases of plants entirely intolerant of a different kind of soil from that which they habitually frequent; many plants show a preference for one soil or other without being exclusively confined to it. For example, the common primrose is undoubtedly a clay lover, yet it will be found widely distributed over all the English soils; the beech and the yew are typical trees of the chalk, good oak and hornbeam of the clay; Spanish chestnut, and many conifers like the Scotch fir, are sand lovers; yet each of these trees will be found commonly enough on other kinds of soil.

Sands.

The typical sandy soils of this country are either alluvial flats in the lower levels of our rivers, passing into dunes where the sand accumulates near the sea, or are directly derived from some of the many coarse-grained sandy formations developed in England. The Bagshot beds and the Lower Greensand form wide areas in the south-east; the sandy beds of the Oolite produce similar soils in Northamptonshire and the East Midlands; further west and northward the Bunter beds give rise to other very coarse-textured soils, as does the Millstone Grit in more elevated areas in the North.

As these coarse-grained sands have been laid down in rough water, they consist in the main of silica, which alone is able to resist the degree of weathering and attrition to which the original material has been subjected. In consequence, the rock is initially without much calcium carbonate or other material which will yield soluble salts on further weathering; the open texture of the material also results in a very free movement of soil water, and this continues the removal of anything soluble. Occasionally a sandy rock is found which has been largely formed by the disintegration of shells, so that it is rich in calcium carbonate; but, as a rule, sandy soils are characterised by poverty in this material. Most soils of this sandy type seem to possess considerable amounts of oxide of iron; the actual proportion present may not be so large as in ordinary soils, but, being spread over the comparatively small surface offered by the large grains, it is more in evidence. The phosphoric acid, which is rarely present in any quantity, generally about 0.1 per cent., is chiefly combined with the oxides of iron,

Because of the general lack of finer particles—in the main clay derived from the weathering of felspar—soils of this type are notably deficient in potash.

Despite their warmth and free aeration, sandy soils often accumulate considerable amounts of humus, an effect probably due to the absence of calcium carbonate. Where depressions occur in the general level of the ground, a layer of impervious ferric hydrate or "pan" forms below the surface and holds up the drainage water, which waterlogged condition is at once followed by an accumulation of peat.

On these sandy areas cultivation is a very artificial affair, and the soil has practically to be created. The first necessity is a supply of lime and mineral salts, to remedy the lack of nutriment; then as much humus as possible must be obtained, by turning in or folding green crops, or even from their roots and stubble only. The humus binds the soil together, creates a reserve of manurial material, and much increases the retentive power of the soil both for water and mineral salts.

Being so dry, the specific heat of sandy soils is exceptionally low; in consequence these soils are early, and as they also recover quickly from rain, so that cultivation is not forced to wait much on the season, but can be proceeded with very readily, they are especially suited to market gardening, wherever situated sufficiently near to a large town to enable large quantities of manure to be obtained cheaply. Where the water table is close to the surface, sandy soils can become very fertile, roots range freely in them, and applications of manure have their full effect. Like all light soils, they are apt to become very weedy. Of the crops suitable to soils of this type, spring wheat is often better than the autumn-sown variety; the quality of wheat

is, however, generally inferior on sandy soils; barley is better than oats, and maize is worthy of attention as a fodder crop. Swedes, cabbages, and the cruciferous crops generally, are subject to "finger-and-toe," in consequence of the poverty of the soil in lime and soluble mineral constituents.

With certain exceptions, leguminous plants do not grow well on sandy soils, and require considerable supplies of lime and mineral manures; there are, however, some leguminous plants which are characteristically *calcifuges* — *i.e.*, intolerant of lime in the soil — lupins, serradella, and gorse belong to this class. Allusion has already been made to the reclamation of sandy land in Prussia by means of lupins, and probably more use might be made of the crop in this country on similar soils. Experiments made with gorse on the coarse sandy soil of the Royal Agricultural Society's farm at Woburn, indicate that it may become a profitable fodder crop on such soils.

Potatoes are perhaps the best crop on the sandy soils, but require considerable expenditure of manure, including large dressings of potash, to do well. Carrots are another crop particularly appropriate to sandy soils, as they need a deep, fine tilth.

The manuring of sandy soils must be based upon a liberal use of lime, frequently renewed because of the ease with which water percolates and removes the calcium carbonate. Marling and chalking, wherever such materials are available, are better for the land than the use of quicklime, which is apt to induce too rapid an oxidation of the organic matter. Nitrogen is best supplied in its organic forms, as in well-rotted dung, the guanos, fish or meat manure, rape cake, etc.; nitrate of soda is apt to induce too rapid a growth, and also to be washed away. Sulphate of ammonia is unsuitable

owing to the lack of lime in the soil. Of phosphatic manures, superphosphate is unsuitable owing to its acid nature. Basic slag is also unsuitable as a rule, owing to the small quantities of water retained by the soil, but it answers well on sands where the water table is near the surface; on the whole, neutral easily-available phosphates like phosphatic guano and steamed bone flour give the best results on these soils. Potash manures are much needed, and either kainit or sulphate of potash may be used. Gypsum is often used with good effect on such soils in the Wealden area, acting as a liberator of what little potash may be in the soil.

The natural flora of the sandy soils is of a double character—in part *xerophytic*, and associated with the prevailing dryness of these soils; in part *calcifuge*, and dependent on the absence of calcium carbonate. Plants with mycorrhiza are abundant, owing, as already explained, to the comparative poverty of these soils, both in water and soluble salts.

The characteristic sand trees are the Spanish chestnut, birch, holly, and many conifers; of these the Spanish chestnut and some of the firs, like *Pinus pinaster*, are particularly intolerant of calcium carbonate.

Many of the Ericaceæ, such as common heather and the heaths, cultivated species like the rhododendrons and azaleas of our gardens, are similarly intolerant of lime and associated with sandy soils; at higher levels various species of *Vaccinium* and kindred plants are common. Gorse (*Ulex europæus* and *U. nanus*), broom (*Cytisus scoparius*), *Genista anglica*, *Ornithopus*, and several vetches like *Vicia cracca*, are characteristic leguminous plants of sandy soils. The foxglove (*Digitalis purpurea*), sorrel (*Rumex Acetosella*), and in undrained

situations the sundews (*Drosera* sp.) are intolerant of lime and are common plants on sandy soils, as also are the common bracken (*Pteris aquilina*), wavy hair grass (*Aira flexuosa*).

Characteristic weeds of sandy soils are, spurrey (*Spergula arvensis*), and sandwort-spurrey (*Spergularia rubra*), corn marigold (*Chrysanthemum segetum*), and knawel (*Scleranthus annuus* and *perennis*); *Papaver dubium* and *Centaurea cyanus* are also common on such soils. The bulbous buttercup (*Ranunculus bulbosus*) is very frequent on dry pastures, whether sandy or chalky, as is the small bindweed (*Convolvulus arvensis*) of similar soils under cultivation; the silverweed (*Potentilla anserina*), though generally indicative of winter flooding, is to be found on all kinds of poor, light land.

The Loams.

The sandy soils pass by imperceptible stages into the loams—free-working soils containing enough sand to be friable and to admit of percolation, yet retaining sufficient water near the surface to withstand short spells of dry weather. If the sandy fractions of the loam are mainly fine grained, the soil is apt to run and become very sticky in wet weather, afterwards drying to hard clods; an admixture of coarser sand results in a better texture. The loams are typical soils of arable cultivation and are suitable to all crops; their manurial requirements vary with the origin of each soil, and are largely conditioned by its poverty or richness in calcium carbonate. While no special flora can be associated with the loams, there are several weeds generally taken as indicative of good fertile soils of this class; such are chickweed (*Stellaria media*), groundsel (*Senecio vulgaris*), fat hen (*Chenopodium*

album), stinking mayweed (*Anthemis Cotula*), and the Sow thistle (*Sonchus oleraceus*). Other weeds of cultivated land, which only occur when the soil is capable of carrying fair crops, are goose grass (*Galium aparine*), the speedwells (*Veronica agrestis*, etc.), pimpernel (*Anagallis arvensis*), henbit (*Lamium amplexicaule*), wild poppy (*Papaver rhæas*), and the small spurges like *Euphorbia Peplus*. The alluvial soils which border the rivers and pass into considerable marshes at their mouths, must, by their texture, be classed among the loams and present no specific features, except where they are waterlogged and marshy, or near the sea where the subsoil water becomes so rich in salt as to alter the character of the vegetation. The marshy patches accumulate, as a rule, what has already been described as "mild humus," owing to the presence of bicarbonate of lime in the soil water; it is generally accompanied by deposits of pulverulent ferric hydrate. The presence of rushes, of sedges like the carnation grass, or orchids like *O. maculata* and *O. latifolia*, are characteristic of these spots requiring drainage. Lousewort (*Pedicularis palustris*) is said only to occur in marshes where the water contains lime.

The salt marshes possess a characteristic vegetation of what are termed halophytes, plants capable of resisting a considerable quantity of salt in the medium in which they grow. Among cultivated plants, mangolds, asparagus, and crucifers like cabbage, are most tolerant of salt, and the two former are true halophytes.

Many halophytes live by acting as xerophytes, and taking very little water up; they are also able to store away in their tissues quantities of saline matter which would be toxic to the majority of plants. The

ash of *Armeria maritima* shows 12 to 15 per cent. of chlorine in the ash; in *Aster Tripolium* the proportion rises to over 40 per cent. in the ash of the leaves, and to 50 per cent. in that of the stem; yet although the plants habitually contain these large amounts of salt, they will grow perfectly well in ordinary soil where they can get but little.

The Australian salt-bush (*Atriplex semibaccatum*), which has already been mentioned as tolerant of a large amount of alkali in the soil, also removes much soluble matter—the dry plant containing as much as 20 per cent. of ash, so that the salt content of the soil may be materially reduced by cropping with this plant. The halophytes seen in the salt marshes of this country consist of various species of *Atriplex*, *Beta* (the source of the cultivated beets and mangolds), and other *Chenopodiaceæ*, *Statice armeria*, *Aster Tripolium*, *Frankenia*, and a number of cruciferous plants like *Crambe*, and *Cakile*, with umbellifers like *Crithmum*. Some plants show a great dislike to salt, even in small proportion, *e.g.*, the *Rosaceæ*, *Orchidaceæ*, and the *Ericaceæ*.

Calcareous Soils.

It is difficult to draw an exact line of demarcation between the loams and calcareous soils, so variable is the proportion of carbonate of lime, owing to its continual removal by the percolation of water containing carbonic acid. Even on the chalk and limestone, where the thickness of the soil layer is to be measured in inches, the surface soil may have its calcium carbonate almost wholly removed, and, again, where the deeper soils of calcareous origin accumulate in the valleys, there is nothing to distinguish them from ordinary

loams. However, the general aspect of the calcareous soils containing from 5 to 60 per cent. of calcium carbonate is characteristic, and the natural flora always indicates the presence of much lime. The texture of the calcareous soils may vary within any limits, according to the formation from which they have originated. On the one hand, extremely fine-textured heavy marls exist; for example, the soils derived from the strata at the base of the Chalk and upper beds of the Gault in the south and east of England; on the contrary, fairly coarse sand may form a considerable proportion of the soil, rendering it light in texture, as is the case with many of the soils resting on the chalk of the North Downs. In all cases these calcareous soils are typically sticky when wet, and easily cake on the surface when dried. Such soils, again, lose their organic matter very rapidly by decay; in farming them it is desirable to use every means to increase the proportion of humus by adding farmyard manure, by folding roots on the land, or by ploughing in green crops. Slowly-acting nitrogenous manures, like rape dust or shoddy, are valuable; again, there is always enough calcium carbonate present naturally to render to sulphate of ammonia its full value as a source of nitrogen. The lighter calcareous soils require a free use of nitrogenous manures to get good crops. Calcareous soils are generally well provided with phosphoric acid, owing to the organic origin of the calcium carbonate; the rule is, however, by no means universal, the upper Chalk, for example, yields soils with less than 0.1 per cent. of this constituent. Superphosphate is undoubtedly the best source of phosphoric acid for such soils, basic slag is almost without action. The proportion of potash present in these soils is generally reflected in their texture; if light and near the unaltered rock,

they are, as a rule, very deficient in this constituent, and require its addition for the growth of any of the root crops. Salt is generally beneficial as an addition to manures on the calcareous soils.

The calcareous soils are generally warm, dry, and healthy for stock; when deep and sheltered they are extremely fertile; the thinner soils are rather subject to certain insect pests, like the turnip flea. The abundance of worms in chalky pasture is worthy of note. The lighter calcareous soils are notoriously weedy. In addition to the usual weeds of light land, Fumitory (*Fumaria officinalis*), *Geranium molle* and kindred species, are almost confined to soils with a considerable proportion of calcium carbonate. Two crops are very characteristic of calcareous soils wherever the climate will admit of their growth, viz., sainfoin and lucerne, which flourish excellently and provide abundant and valuable fodder even on the driest chalk soils.

The natural flora of these calcareous soils includes the beech, yew, and wild cherry, among trees; the juniper, box, mealy guelder rose (*Viburnum Lantana*), beam tree (*Pyrus Aria*), dogwood (*Cornus sanguinea*), and *Clematis vitalba*, among shrubs.

The vegetation is characteristically rich in flowering plants: amongst the Leguminosæ, the horse-shoe vetch (*Hippocrepis comosa*), bird's-foot trefoil (*Lotus corniculatus*), kidney vetch (*Anthyllis Vulneraria*), are everywhere abundant; milkwort (*Polygala*), bladder campion (*Silene inflata*), *Spiræa filipendula*, burnet (*Poterium sanguisorba*), wild parsnip (*Pastinaca sativa*), sheep's scabious (*Scabiosa Columbaria*), chicory (*Cichorium Intybus*), and certain of the Gentianaceæ, as *G. amarella*, and *Chlora perfoliata*, the viper's Bugloss (*Echium vulgare*), and a number of labiates like *Ori-*

ganum, are characteristic of the pastures and waste places on chalk and limestone. Amongst grasses, *Avena pubescens*, *A. flavescens*, *Bromus erectus*, and *Brachypodium pinnatum*, are common.

While it has been indicated that many plants are intolerant of lime, others show the effect of any excess in the soils by a stunted development of the plant, often accompanied by a reduced size of the leaf, and a sickly yellow or even white colour. This unhealthy condition of "chlorosis" is particularly noticeable on the stiff marls, which are but little aerated but contain much calcium carbonate; on the Continent it often affects vines, particularly when grafted on American stocks.

Clay Soils.

It has already been indicated that clay soils are those in which the finer fractions of sand, silt, and clay predominate; the presence of any considerable proportion of coarse sand causes the soil to become friable, and would class it with the loams. The texture of clay soils naturally varies very much; the heaviest clays occur in dry climates, where the percolation has not been sufficiently great to wash away many of the finer particles; in the east and south-east of England the Oxford and the London Clay, with the Boulder clays derived therefrom, give rise to the most stubborn and intractable clays. On these soils the old practice of an occasional bare fallow is still carried out, and is almost necessary to maintain the soil in good cultivation. As a rule, the strong clay soils have of late years been laid down to permanent pasture; the cost and the difficulty of arable cultivation (for much wet weather in autumn or spring may render it impossible to put horses on the land

for long periods), and the great fall in prices of both wheat and beans, the staple crops of such land, have rendered it necessary to resort to a cheaper method of farming.

Most clays carry good permanent pasture, because the soil retains enough water to keep the grass growing through any but the longer periods of drought; in very dry years, however, clay suffers severely from the drought; the surface cracks and the subsoil dries through the cracks; the resistance also offered by the close texture of the soil to the capillary rise of soil water renders the winter rainfall less available to the crop than on soils of lighter texture. The benefits accruing from drainage, in making the soil dry more quickly after rain and more resist drought better, have already been discussed. Certain clay soils may be found too close textured to carry good pasture; the soil sets so firmly that aeration becomes very defective, and the vegetation degenerates into surface-rooting, stoloniferous grasses like *Agrostis alba*.

Owing to their fine division, their origin from the compound silicates of primitive rocks, and the reduced percolation which they permit, all clays are comparatively rich in soluble mineral salts. Many of them show crystals of selenite ($\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$) in the subsoil comparatively near to the surface; magnesium sulphate is often abundant, and strongly impregnates the water obtained from the wells or the occasional springs to be found in the clays. In the Weald of Kent the shallow wells in the clay yield water that is almost undrinkable, containing, as it does, from 150 to 450 parts of dissolved matters per 100,000, consisting chiefly of the sulphates (with some chlorides) of magnesium and calcium. The sulphates often originate from the oxidation of finely-divided iron pyrites. The presence of ferrous salts

and other unoxidised iron compounds has already been alluded to as a source of sterility in clay soils, particularly where the subsoil has been incautiously brought to the surface. In the cultivation of all land it is important to keep the surface soil on the top, and to attempt to deepen the staple with care; but this is particularly the case with clays, where the land may easily be injured for years by over-deep ploughing. No soils show more marked change than the clays do in passing from soil to subsoil, both in chemical composition and physical texture.

Many clay soils, especially when undrained, possess a great tendency to accumulate hydrated ferric oxide some few inches below the surface, at about the level to which the soil is ordinarily aerated. This deposit sometimes forms a continuous layer or "pan"; in drier climates it becomes a kind of "crowstone" gravel, made up of little nodules of hydrated oxide of iron, containing also manganese. This material frequently forms a serious obstacle to cultivation, and requires to be broken up with a crowbar or a subsoil plough before any deep-rooting crop can be properly grown. Its origin is perhaps not entirely explained as yet; the respective shares of the iron bacteria of Winogradsky, or the purely chemical actions of solution and reduction by the organic matter and carbonic acid followed by re-deposit on evaporation, are matters requiring further investigation. The formation of the material is only noticed in clays very poor in calcium carbonate and liable to waterlogging through insufficient percolation.

Owing to their coolness, their retention of moisture, and comparative impermeability to air, humus tends to accumulate in the clay soils; both arable and pasture soils show a higher proportion of organic matter and of humus than is found, as a rule, on the lighter

lands; the effect of manures like farmyard manure is also more lasting. The use of more slowly-acting nitrogenous manures is therefore not so desirable on the clay soils; on the other hand, sulphate of ammonia is often unsuitable because of the want of calcium carbonate, and nitrate of soda, which often gives the best returns, is apt to injuriously affect the texture by keeping the surface damp for some time after its application.

The clays are very generally deficient in calcium carbonate, often to an extreme degree, much to the detriment of the texture of the soil. The use of lime is of the utmost value to all clay soils, improving the texture, making them drier and therefore warmer and earlier, and rendering available the supplies of nitrogen and potash with which they are often liberally endowed. The excess of magnesia and unoxidised iron compounds which also characterise many clays is corrected by the use of lime.

Many clay soils also show a considerable deficiency of phosphoric acid, and respond freely to dressings with manures containing this substance. Superphosphate may be used with advantage wherever there is enough calcium carbonate in the soil, but basic slag is the typical phosphatic manure for the strong soils which retain sufficient water to render the phosphates active. While supplying phosphoric acid, it also contains free lime in a fine state of subdivision, and so liberates in a soluble state the reserves of nitrogen and potash in the soils. It should, however, not be forgotten that as the basic slag only supplies one element of plant food, the phosphoric acid, the soil may easily be exhausted by continual cropping and manuring with basic slag alone.

Potash is always present in large amounts in clay

soils, 0.5 per cent. soluble in strong hydrochloric acid is often to be found, while the proportion which can be extracted after completely breaking up the soil with hydrofluoric acid may rise to 2 per cent. Clay soils are late, and their crops grow slowly and ripen tardily except in specially dry seasons, when the clay shrinks so much as to cut off all access of moisture from the subsoil, and prematurely ends the period of growth; on the other hand, the quality of crops grown on the clay is often high. The typical crops of strong land are wheat, beans, and mangolds; owing to the closeness of the texture of the soils, weeds are much less in evidence on the clays than elsewhere, though some few are exceedingly troublesome.

On the poorer pastures the spiny form of rest harrow (*Ononis arvensis*), the wild teasel (*Dipsacus sylvestris*), *Ranunculus arvensis*, and *Genista tinctoria*, are characteristic and often troublesome weeds; on cultivated land the "black-bent" grass (*Alopecurus agrestis*), and field mint (*Mentha arvensis*) are difficult to deal with. Other plants characteristic of strong soils are the primrose (*Primula vulgaris*), and the wild carrot (*Daucus Carota*).

Peaty Soils.

The accumulation of humus to form peaty soils has already been discussed, and is associated with water-logging, which cuts off the access of air and so sets up an anaerobic fermentation of the residues of the vegetation growing upon the surface. There is always a deposit of ferric hydrate accompanying the accumulation of peat, as explained before. As the reclamation of peaty soils has already been dealt with, it will be sufficient here to indicate that their great characteristic is a deficiency in soluble mineral constituents,

notably salts of lime and potash. It has also been mentioned that, as a consequence of the acid nature of the medium, the bacteria of nitrification are absent or few in number. All attempts at the cultivation of peaty soils begin with drainage, and must then proceed on the basis of neutralising the organic acids with lime, and providing a sufficiency of mineral food for the plant, thus also inducing nitrification to render available the large quantities of nitrogen which have accumulated. Of the common crop plants, oats and potatoes are perhaps the most tolerant of extreme amounts of acid humus. The normal vegetation of peaty soils is a mixture of xerophytic and calcifuge forms; the Conifers, the Ericaceæ, *Drosera*, *Rumex Acetosella*, *Pedicularis sylvatica*, Sphagnum moss, and many sedges and rushes, are characteristic of sour peaty soils. Other characteristic plants are more properly Northern or Arctic species, and, occurring only in the uncultivated uplands, need not be considered here.

Soil Surveys.

To render the scientific study of soils properly available for the service of the agriculturalist, more is required than the examination of single samples of soil, representing, at the best, only the land dealt with by one person. Over any wide district, not only would such work become expensive and practically endless, liable also to many sources of error through local and accidental variations of the soil on the spot from which the sample was drawn, but each analysis would lose the greater part of its value if it could not be co-ordinated and brought into line with others drawn from soils of the same type. A general soil survey of a district, so as to be able to lay down a plan of the

distribution of the various soil types, accompanied by a discussion of the broad characteristics of each, should be the basis upon which the interpretation of the analysis of the soil of any particular field should be founded. Only by comparison with the type can the analysis of any particular soil be properly interpreted—*e.g.*, the fact that a soil from a given arable field contains 0.15 per cent. of phosphoric acid takes a very different aspect when it is known that the soils of the same type contain as a rule 0.18 to 0.20 per cent. of phosphoric acid, particularly if, also, the response of that kind of land to phosphatic manures is known by field trials, or from the accumulated experience of farmers. The first question which requires settlement is how far a soil survey is possible; to what extent can the boundaries of soil types be traced; are the various types sufficiently constant over a wide area to render this mapping feasible? In many cases there seems to be little but confusion, even in the soils on a single farm; field differs from field, and great variations may be manifest even within the confines of a single field. But, in the main, each soil type has a well defined area, within which it presents a reasonably constant composition and texture, and though the boundaries cannot be laid down with the precision of the outcrop of a stratum, the zone of transition from one type to the other may be indicated with approximate accuracy.

The basis upon which any soil survey must be constructed is the origin of the soils; each geological formation, for example, will give rise to a distinct type of soil if it has been formed *in situ*; should the weathered material have further undergone transport by water, two or more types may have been constructed by the sorting action of the water. It is also well known that a geological formation may change very

considerably in lithological character in passing from the lower to the upper portions of the bed. For example, stiff as the London Clay is, the upper beds become increasingly sandy in character, so that it is not easy to draw a line of demarcation between the soil arising from these beds and these due to the Bag-shot Sands above. The lower beds of the Gault Clay are also very pure, and give rise to a stiff clay deficient in calcium carbonate; the upper beds become marly, and form soils indistinguishable from those due to the contiguous Chalk Marl. Similarly, a geological formation may show a progressive change of character in passing into a different area, which change will be reflected in the soils derived from them. For example, the Great Oolite limestones of the Cotswolds shade off into sandstones in Northamptonshire, and the Hythe beds of calcareous sandstone in East Kent become pure coarse-grained sandstones in West Surrey. However, in the main, geological origin may be taken as the basis of a soil survey, to which must be added the further subdivisions due to the causes enumerated above, or to the local movements of rain-wash or ill-defined drift, that may alter the character of the soil without being of any particular geological importance.

A soil map will consist of a "drift" map, with some further details showing the superficial formations occupying the surface of the ground, and notes regarding the local variations in the type of soil derived from each particular stratum. The aim of a soil survey is to carry further the work of the geological survey as regards the superficial formations; the only classification which can be adapted will be one based upon the physical texture of the soil, and indicated by such conventional terms as clays, clay loams, sandy loams, marls, etc. At the same time, the map must indicate

the various origin of the different loams which may be found in the area under survey, and, by reference to the accompanying text, should give those details of physical structure and chemical constitution which characterise the soil, but which cannot be set out except by an over elaborate classification.

The field portion of the work of a soil survey consists in the exploration of the subsoil by means of an auger, aided by any natural sections which may be displayed. The boundary between two soil types may generally thus be laid down by the aspect of the soil and subsoil; from time to time, however, samples must be retained for more detailed examination in the laboratory, whenever the look and touch of the material are not sufficient for a decision *in situ*. An immediate examination with the microscope, the behaviour of the soil with acid, or a rough sifting in a stream of water, will, as a rule, be sufficient to refer a given example of subsoil to one type or another. Complicated cases arise from time to time, especially in the river valleys, where alluvium of varied epochs and rain-wash of not very different origin may be hopelessly intermingled. In many cases, however, where the outcrop of the originating formations is broad, and where the gradients of the country are slight, the soil may be extremely constant in composition over a wide area, so that the survey has only to notice such minor variations as the grading from a lighter to heavier type as one descends a slope, or the occasional influx of drift material by creeping from a neighbouring area. The further work of a field survey will be the selection of typical samples of soil and subsoil for detailed examination and analysis in the laboratory, the collection of such data as the distance to, and nature of ground water, and any particulars which may be

available locally, as to special features in the working of each type of soil, or in the growth of its crops; the nature and character of such deposits as "brick earth" in each district can also be reported. The samples for detailed analysis should be taken where a general survey of the district indicates the soil as most likely to be typical of the formation and free from admixture with drift and other accidental intrusions. At the same time, since the soil in the main will by no means be so pure as the typical samples, a much larger number of samples should be taken and subjected to a less detailed examination, by way of ascertaining within what limits the normal variation of the soil is confined.

The number of type samples to be taken must be entirely decided by an examination of the circumstances; in continental areas, where deposition has been very uniform over wide districts, one or two samples may be sufficient to characterise an extensive soil type; in other cases the local variations may be so much in evidence that the "typical soil" can only be constructed by putting together the results of many separate determinations.

But the practice of constructing a typical soil for analysis by mixing together equal fractions of many samples drawn in the area in question, is not to be recommended. Not only may an entirely foreign or accidentally impure sample be introduced without detection, but, further, the limits of variation normally to be expected in individual soils of the same type is just as important as the composition of the type itself. Again, the existence of unsuspected systematic variations is entirely obscured by any process of mixing samples. The character of the information which should accompany the soil maps must largely depend

on the purpose of the survey, whether it is concerned with the agriculture of an old and settled country, or whether it partakes of the nature of an exploration, and aims at showing the capacities of the land for new crops and industries. In the United States, for example, the latter form of soil survey is exemplified; in many parts of the country agriculture is so recent that there is no accumulation of experience as to the crops most suited to each kind of land; hence the survey, by comparisons of the texture of the soil, the climatic conditions, and the depth to ground water, with the conditions prevailing in better known areas, can directly tell the settler with what crops he is most likely to succeed. The cultivation of special crops like tobacco and sugar beet, to take two examples of special interest at the present time in the United States, can be extended into new districts possessing suitable soils, with a minimum of the risk which must always attend the introduction of a novel form of culture. The suitability of other classes of land for irrigation, the nature and extent of already existing alkali patches, and the most promising methods of reclamation, are also prominent features in the work of the United States soil survey. As the crops in a new country of this kind are in the main grown by the aid of the natural fertility of the soil alone and fertilisers are little used, the chemical examination of the soil becomes of less importance than the mechanical.

In a settled country like our own, the character of the information to be derived from a soil survey is of a different order; the land has been under cultivation so long that a great mass of local information, based upon experience, exists as to the character even of individual fields.

Hints as to the cultivation, based upon the texture

of the soil as determined by analysis, would be too general to be of any service; indeed, it is rather to be hoped that by collating many mechanical analyses with information derived from men possessing long experience of the soil, further light can be shed upon the connection between physical structure and the finer points of tillage. The suitability of the different types of soil to new crops—as, for example, the extension of the area under fruit—can be ascertained, and many expensive mistakes due to planting on unsuitable land could be saved to the farmer. Suggestions can also be made as to the amelioration of the soil by drainage, or by the incorporation of materials like clay, chalk, or marl, occurring in the vicinity. Fifty years ago, no department of British agriculture was more carefully attended to than the improvement of the texture of the soil, and great tracts of what is now fertile land were practically created; lower values to-day have caused this important matter to be almost entirely neglected.

But the chief application of a soil survey in this country lies in the information that can be afforded as to the use of manures; enormous economies might be effected in the bills of almost every farmer using artificial manures, if the latter were properly adapted to his soils and crops. Farmers are often recommended to carry out manurial trials upon their own farms until they have ascertained the peculiarities and specific requirements of the soil, but advice of this kind treats altogether too lightly the somewhat delicate business of conducting field experiments. Putting aside the mechanical difficulties attending a trial of this kind, and the overpowering effect of minor inequalities of the ground and other accidental conditions which so often nullify the experimental treatment, it is rarely that

the farmer will be found able to arrange a scheme of experiment likely to give information of permanent value. If one may judge from the published accounts of many field experiments carried out in this country even by public bodies which so often show a misapprehension of the points really at issue, there is every probability that the individual farmer will be as often misled as guided by the results of his own experiments. The design and conduct of field experiments must be left to the expert, who surveys the subject from a wider standpoint, who can compare various trials, and is in a position to continue them for a period of years, rejecting at any early stage a considerable proportion which are inevitably vitiated by some concealed local peculiarity. A body of experts conducting a soil survey and field experiments simultaneously in the same area and co-ordinating their results, can give advice of the most definite character as to the scheme of manuring to be adopted for each soil type. The fundamental factor requiring consideration in this matter, and brought out in the soil survey, is the proportion of lime normal to each soil type; knowing this factor, and the retentivity of the soil for moisture under ordinary conditions of rainfall, one can decide upon the character of the manures for most loamy soils. Soils of more specific character, like the sands or clays, present more characteristic deficiencies of some of the manurial constituents, so that for many crops the use of manures like phosphates and potash is wholly determined by the soil and not the crop.

It is not too much to say that the information as to the manuring which is being accumulated at many experimental centres throughout the country can only be rendered properly available by the execution of a soil survey in the district under consideration. In

many countries a soil survey has been made part of the national service for the agriculturist; the magnificent publications of the Division of Soils of the United States Department of Agriculture form a case in point. In Prussia, the maps and reports of the *Laboratorium für Bodenkunde* at Berlin may be consulted as models of the thoroughness and refinement to which work of this kind can be pushed; the Gembloux Station in Belgium is executing a systematic chemical survey of the Belgian soils. In France, the work rests with the local authorities of each Department, but in parts is being carried out, as witness the beautiful maps due to the single-handed work of M. Gaillon, Director of the Station Agronomique de l'Aisne at Laon. In Britain the great initial want is the publication of drift maps of the geological survey on the 6-inch scale; the 1-inch to the mile survey, which alone has been published, or even executed in most districts, is too small to admit of necessary detail. It is also very often laid down on an early cadastral survey, which makes the identification of the modern boundaries a matter of difficulty. If the country were in possession of a series of "drift" maps on the scale of 6 inches to the mile, the work could be rapidly supplemented by soil surveys and analyses executed by the local agricultural colleges and research institutions, until every farmer could be put in possession of that exact knowledge of the soil which is fundamental to all farming operations.



APPENDICES

APPENDIX

CHEMICAL ANALYSES

PERCENTAGES ON THE

NUMBER . . .	1	2	3	4	5	6
FORMATION . . .	London Clay.		Gault Clay.		London Clay.	
NATURE . . . {	Heavy Clay.	Subsoil of 1.	Heavy Clay.	Subsoil of 3.	Clay Loam.	Subsoil of 5.
TILTH . . .	Arable.	..	Pasture.	..	New Pasture.	..
Hygroscopic Moisture	6.48	6.25	4.37	3.74	3.91	2.94
Loss on Ignition	9.08	7.33	7.79	6.66	4.38	3.88
Nitrogen	0.276	0.138	0.226	0.112	0.187	0.064
Potash	1.13	1.63	0.968	1.21	0.33	0.675
Potash, soluble in 1 per cent. Citric Acid	0.026	...	0.0294	...	0.017	...
Lime as Carbonate	0.35	0.13	0.04	0.16	0.065	0.084
Magnesia	2.02	...	0.009	...	0.35	...
Alumina	9.34	...	7.49	...	4.14	...
Oxide of Iron	6.16	...	4.42	...	2.47	...
Oxide of Manganese	0.15	...	0.07	...	0.712	...
Phosphoric Acid	0.12	0.097	0.092	0.072	0.065	0.032
Phosphoric Acid, soluble in 1 per cent. Citric Acid	0.008	...	0.14	...	0.0145	...
Sulphuric Acid	0.07	...	0.081	...	0.036	...
Chlorine	0.009	...	0.011	...	0.012	...

DIX I

OF TYPICAL SOILS

FINE EARTH—AIR-DRIED

7	8	9	10	11	12	13	14
Chalk.		Millstone Grit.	Red Sandstone.	Hythe Beds.	Thanet Beds.	Lower Greensand.	Bagshot Beds.
Calcareous Loam.	Subsoil of 7.	Light Loam.	Sandy Loam.	Light Loam.	Sandy Loam.	Sand.	Barren Sand.
Arable.	..	Arable.	Arable.	Arable.	Arable.	Arable.	Waste.
2.93	2.35	2.38	2.66	4.24	1.62	1.67	1.03
5.06	5.56	5.66	6.83	6.32	3.46	3.15	4.4
0.194	0.13	0.171	0.207	0.18	0.12	0.11	0.08
0.46	0.435	0.207	0.295	0.64	0.354	0.22	0.032
0.015	...	0.0124	0.021	0.032	0.19	0.013	0.01
3.70	14.90	0.26	0.96	3.54	0.32	0.2	nil
0.64	0.26
3.60
2.44
0.023
0.094	0.097	0.088	0.059	0.21	0.095	0.15	0.013
0.012	...	0.0122	0.023	0.058	0.02	0.027	0.003
0.04
0.012



APPENDIX II

BIBLIOGRAPHY

The following short list of references will take the student to some of the more important original sources of information on each of the subjects treated of in this book. They have been selected from among the great mass of papers that exist, not because they are necessarily the most important, but as suggestive in themselves and likely to lead the student to make further acquaintance with the methods as well as with the results of research. Several of the papers also contain a series of references to other workers in the same field.

THE ORIGIN OF SOILS.

1. RISLER, E.—*Géologie Agricole*, 4 vols., Paris, 1884-97.
2. MERRILL, G. P.—*Rocks, Rock Weathering, and Soils*, New York, 1897.

ANALYSIS AND COMPOSITION OF SOILS.

3. LAUFER AND WAHNSCHAFFE.—*Mit. a. d. Laboratorium für Bodenkunde*, B. III., h. 2, Berlin.
4. PETERMANN.—*Recherches de Chimie, &c.*, III., Brussels, 1898.
5. HILGARD, U.S. Dep. of Agric., Div. of Chem., Bull., 38, 1893.
6. HILGARD, U.S. Dep. of Agric., Div. of Soils, Bull., 4, 1896.
7. LAWES AND GILBERT.—*Rothamsted Memoirs*, V., No. 19.
8. DYER.—*J. Chem. Soc.*, 1894, 65, 115.
9. DYER.—*Phil. Trans.*, 194, B. (1901), 235.
10. DYER.—U.S. Dep. of Agric., Bull., 106, 1902.
11. HALL AND PLYMEN.—*J. Chem. Soc.*, 1902, 81, 117.
12. TOLLENS' "Soil Analysis by the Plant," *Exp. Sta. Rec.*, 13 (1901), 207.

SOIL PHYSICS.

13. WARINGTON.—*Physical Properties of Soils*, Oxford, 1900.
14. KING.—*Physics of Agriculture*, Madison, Wis., 1901.
15. HILGARD.—U.S. Dep. of Agric., Weather Bureau, Bull., 3, 1892.
16. WHITNEY.—U.S. Dep. of Agric., Weather Bureau, Bull., 4, 1892.
17. HELLRIEGEL.—*B. z. d. nat. Grundlagen des Ackerbaues*, Braunschweig, 1883.
18. LAWES AND GILBERT.—*Rothamsted Memoirs*, Vol. III., No. 11; Vol. V., No. 5.
19. BRIGGS.—U.S. Dep. of Agric., Year-Book, 1900, 397.
See also Wollny, No. 20.

SOIL ORGANISMS.

20. WOLLNY.—*Zersetzung der Organischen Stoffe*, Heidelberg, 1897.
21. OMELIANSKY.—*Compt. Rend.*, 121 (1895), 653; 125 (1897), 970.
22. WINOGRADSKY.—*Compt. Rend.*, 121 (1895), 742.
23. EMMERLING.—*Zersetzung Stickstofffreier Organischer Substanzen durch Bakterien*, Braunschweig (1902).

FIXATION OF NITROGEN.

24. LAWES AND GILBERT.—*Phil. Trans.*, 11., 1861, 431; B. 180, 1889, 1.
25. LAWES AND GILBERT.—*J. R. Ag. Soc., E.*, 3rd s., 2, 657, 1891.
26. HELLRIEGEL AND WILFARTH.—*Zeit. d. Vereins f. d. Rüben-
zucker Industrie*. 1888.
27. NOBBE AND HILTNER.—*D. Land. Vers. Stat.*, 1899, 52, 455.
28. WINOGRADSKY.—*Compt. Rend.*, 118 (1894).
29. MAZÉ.—*Ann. de l'Inst. Pasteur*, 11 (1897).
30. JACOBITZ.—*Cent. für Bakt.*, 11., F. 783.

NITRIFICATION.

31. SCHLOESING AND MÜNTZ.—*Compt. Rend.*, 80 (1877), 1250.
32. WARINGTON.—*J. C. S.*, 1878, 1879, 1884, 1891.
33. LAWES, GILBERT, AND WARINGTON.—*J. R. Ag. Soc., E.*, 2nd s., 19 (1883), 331.

34. WINOGRADSKY.—*Compt. Rend.*, 113 (1893), 116.
35. DEHÉRAIN.—*Ann. Agron.*, 19, 409.
36. KING.—Wisconsin Ag. Exp. Station, Annual Reports, 17 (1900), 18 (1901).

DENITRIFICATION.

37. GAYON AND DUPETIT.—*Compt. Rend.*, 95 (1882), 644.
38. WAGNER.—*D. Landw. Presse*, 1895, 123.
39. WARINGTON.—*J. R. Ag. Soc., E.*, 3rd s., 8, 577.
40. STOKLASA.—*Cent. f. Bakt.*, 7 (1901), 260.

MYCORHIZA.

41. STAHL.—*Jarhb. f. wiss. Botanik.*, 34.

ABSORPTION OF SALTS BY SOIL.

42. WAY.—*J. R. Ag. Soc., E.*, 1st s., 11, 323 ; 13, 123.
43. VOELCKER.—*J. R. Ag. Soc., E.*, 1st s., 21 (1860), 93 ; 25 (1864), 333.
44. VOELCKER.—*J. R. Ag. Soc., E.*, 2nd s., 10 (1874), 132.
45. LAWES, GILBERT, AND WARINGTON.—*J. R. Ag. Soc., E.*, 2nd s., 17 (1881), 241 ; 18 (1882), 1.

ALKALI SOILS.

46. HILGARD.—U.S. Dep. of Agric., Year-Book, 1895, 103.
47. HILGARD.—Univ. of California, Ag. Exp. Sta. Bull., 128 (1900).
48. WILLCOCKS.—*Egyptian Irrigation*, 2nd ed.

SOIL SURVEYS, ETC.

49. SCHIMPER, A. F. W.—*Pflanzen Geographie*, Jena, 1898.
 50. U.S. Dep. of Agric., Div. of Soils, "Field Operations," 1901.
 51. WHITNEY.—"Tobacco Soils," U.S. Dep. of Agric., Bull., 11, 1898.
 52. VEITCH.—"Maryland Soils," Maryland Ag. Exp. Sta., Bull., 70, 1901.
 53. HALL AND PLYMEN.—"Soils of Kent and Surrey," S.E. Agric. Coll., Wye, 1902.
- See also Nos. 3 and 4.



INDEX

- ABSORPTION of salts by soil, 189.
 Acid soils, 193, 222.
 Aerobic bacteria, 157.
 Alinit, 160.
 Alkali soils, 223.
 Alluvium, 12.
 Alluvial soils, 254.
 Altitude, effect on temperature, 124.
 Ammonia, absorption by soil, 192 ;
 formation from urea, 158 ; salts,
 removal of lime by, 193.
 Anaerobic bacteria, 160.
 Analysis, available constituents, 147 ;
 chemical, 128 ; mechanical, 32,
 48, 53 ; of soil by plant, 144.
 Anbury in turnips, 186.
 Angus Smith on denitrification, 177.
 Apatite, 24.
 Arid soils, characteristics of, 27, 44.
 Atwater on fixation of nitrogen, 165.
 Augite, 21.
 Autumn cultivation, gain of water
 by, 90.
 Available plant food in the soil,
 142.
 BACTERIA in soil, 154 ; denitrify-
 ing, 178 ; nitrifying, 171 ; iron,
 182 ; nitrogen fixing, 166, 170.
 Bailey Denton on effect of drainage
 on temperature, 122.
 Bare fallows, 105.
 Basalt, weathering of, 21.
 Beaumont, E. de, on antiquity of
 soil, 29.
 Berthelot on fixation of nitrogen,
 165, 170 ; and André on nitrogen
 in humus, 45.
 Black soils, 2, 214.
 Bog iron ore, 25.
 Boussingault on source of nitrogen
 in plants, 161.
 Brick earth, 7, 15.
 Brown on energy absorbed in assimi-
 lation, 85.
 CALCAREOUS soils, 255.
 Calcifuges, 251.
 Calcium carbonate, 22 ; aids decay of
 organic matter, 159 ; determina-
 tion of, 133 ; diminishing propor-
 tion in subsoil, 29, 41 ; in soils
 subject to "finger-and-toe," 187.
 Capacity of soil for water, 64, 77.
 Capillarity, 68 ; supply of water to
 crop by, 94.
 Carbon to Nitrogen in soils, Ratio
 of, 44.
 Carbonic acid in soil gases, 13 ; and
 water, action on rock minerals,
 19, 22, 24.
 Catch crops, 104.
 Chalk, "pipes" in, due to weather-
 ing, 23 ; soils, 55, 255.
 Chalking, 245.
 Chemical analysis of soil, 128.

- China clay, 19.
 Chlorosis, 258.
 Clay, colloid, 35; flocculation of, 38; impermeability to water, 67; origin of, 19, 30, 34; shrinkage on drying, 34, 80; soils, 258.
 Claying, 232.
 Cleopatra's Needle, weathering of, 11.
 Club root in turnips, 183, 186.
 Coagulation of clay, 38.
 Cohesion due to surface tension, 79.
 Colloid clay, 35.
 Colmetage, 231.
 Colour of soils, 26, 126; and temperature, 117.
 Condensation of water by soil, 83.
 Condition of land, 212.
 Conventions necessary in chemical analysis of soil, 130.
 Cultivation, effect of, on water content of soil, 90, 92.
- DANBRÉE on size of sand grains not rounded by running water, 17; weathering of felspar, 19.
 Darwin on action of earthworms, 15.
 Defoe on definition of manure, 142.
 Dehérain on available phosphoric acid in soils, 146; nitrates in drainage waters, 206; nitrification, 174.
 Dehérain and Maquenne on denitrification, 177.
 Denitrification, 177.
 Density of soils, 60.
 Drainage, 87; warms the land, 122; waters, composition of, 200.
 Drain-gauges, 75; flow greater than rainfall, 83.
 Drift, glacial, 16; maps, 265, 271; soils, 8.
 Drought, of 1870 at Rothamsted, 102; susceptibility of different soils to, 94.
- Dyer on determination of available phosphoric acid and potash, 147; potash and phosphoric acid retained by Rothamsted soils, 195, 199.
- EARLY and late soils, 125.
 Ebelmar on weathering of basalt, 21.
 Egypt, irrigation in, 226.
 Evaporation, cooling effect of, 120; losses of water by, 92.
- FAIRY rings, 218.
 Fallows, bare, 105.
 Felspar, 18.
 Fen land, potatoes from the black soils of, 2; reclamation of, 234.
 Fertility, 212.
 Film of water surrounding soil particles, 70.
 "Finger-and-toe" in turnips, 183, 186.
 Fixation of nitrogen, 161; by the soil, 170.
 Flint, 18.
 Flocculation of clay, 38.
 Flow of water through soils, 67.
 Forfarshire, potatoes grown on the "red lands" of, 1.
 Frank on mycorhiza, 183.
 Frosts in valleys, 124.
 Fruit trees in grass land, 105.
 Fungi in the soil, 182.
- GAYON and Dupetit on denitrification, 178.
 Germination, temperatures of, 115.
 Glacial drift, 16.
 Glauconite, 25.
 Gravel, 7, 15.
 Green manuring, 169.
 Greensand, Lower, soils on, 53, 221, 249.
 Greenstone, weathering of, 21.
 Grey wethers, 17.

Gypsum, 24, 252.

HALOPHYTES, 254.

Hanamann on weathering of basalt, 22.

Heavy soils, 61.

Heinrich on hygroscopic moisture, 81.

Hellriegel on fixation of nitrogen, 165 ; on optimum proportion of water for growth, 66 ; on water transpired, 84.

Hilgard on alkali soils, 225, 229 ; on Californian soils, 83 ; on mechanical analysis of soils, 48 ; on method for determination of water capacity, 64.

Hilgard and Jaffa on nitrogen in humus, 44.

Hoeing, 97.

Hornblende, 21.

Humic acid, 42, 158.

Humus, 41, 157, 183, 254, 262.

Hygroscopic moisture, 81.

Hythe beds, soil on, 265 ; transition of rock into soil and subsoil, 7.

INOCULATION of soil, 169.

Irrigation, 225.

Iron bacteria, 182.

Iron pan in soils, 25, 260.

Iron pyrites, 25 ; causing sterility, 222.

JOLY on power of salts to coagulate clay, 39.

KAOLINITE, 19, 34, 36.

King on area of surface of soil particles, 63 ; on bare fallows, 105 ; on effect of cultivation on water content of soil, 91, 96, 98, 101 ; on effect of slope on temperature of soil, 123 ; on flow of water through sand, 67 ; on ni-

trates in soil, 175 ; on pereolation, 73 ; on transpiration water, 84 ; on water in soils too dry for growth, 82.

Kossowitsch on fixation of nitrogen, 170.

LAKING, 191.

Langley on solar radiation, 116.

Late soils, 126.

Laurent on fixation of nitrogen, 167.

Lawes and Gilbert on fixation of nitrogen, 162 ; on ratio of carbon to nitrogen in soils, 44 ; on transpiration water, 84. (*See also* Rothamsted.)

Leguminous plants, fixation of nitrogen by, 163 ; green manuring with, 169.

Liebig, mineral theory of, 161.

Light soils, 61.

Lime, effect on temperature of soil, 118 ; composition of, 244 ; for "finger-and-toe," 188 ; in drainage waters, 202 ; removal from soil by use of ammonia salts, 193.

Liming, 237.

Limonite, 24.

Loams, 30, 253.

Loess deposits, 10.

London clay, soils on, 55, 258.

Lysimeter, 75.

MAGNESIA in drainage waters, 203 ; in soils, 222, 224, 259.

Manures, absorption of, by soil, 189 ; original signification of, 142 ; time of application of, 207.

Marcasite, 26.

Marls, 30, 256.

Marling, 232.

Mazé on fixation of nitrogen, 167.

Mechanical analysis of soil, 32, 48, 53.

- Mica, 20.
 Minerals, composition of rock-forming, 16.
 Molecular forces, 68.
 Molisch on iron bacteria, 182.
 Mulches, 97.
 Müller on nitrification, 171.
 Munro on nitrification, 172.
 Mycorrhiza, 183.

 NITRAGIN, 168.
 Nitrates, determination of, 136; formation of, 171; in drainage waters, 204; in soil, effect of cultivation on, 175; produced by bare fallow, 106.
 Nitrification, 171.
 Nitrogen, determination of, 133; fixation of, 161; proportion recovered in crop, 179, 181.
 Nobbe on nitragin, 168.

 OEMLER on specific heat of soil, 119.
 Olivine, 22.
 Optimum proportion of water in soils, for growth, 66; temperatures for growth, 114.
 Osborne on mechanical analysis of soils, 48.
 Osmosis, entry of plant food by, 145.

 PAN, iron, in soils, 25.
 Paring and burning, 235.
 Parkes on temperatures of drained and undrained land, 122.
 Peat, origin of, 30, 42, 160; reclamation of, 234; soils, 262.
 Percolation, 72; through gauges at Rothamsted, 75.
 Phosphoric acid, determination of, 134, 147; retention by soil, 197.
 Pipes in chalk rock, 23.
 Plasmodiophora brassicæ, 183, 186.

 Pore space, 57.
 Potash, determination of, 135, 147; retention by soil, 194.
 Potatoes grown on different soils, value of, 1.
 Putrefaction, 160.

 QUALITY of produce from early and late soils, 127.
 Quarry water, 11, 244.
 Quartz, 17.
 Quincke on range of molecular forces, 68.

 RATIO of Carbon to Nitrogen in soils, 44.
 Red lands of Forfarshire, value of potatoes from, 1.
 Richtofen on loess deposits, 10.
 Rolling, effect of, 100.
 Roots, weathering action of, 14.
 Rothamsted, available constituents in soil of, 149; bare fallows at, 108; composition of drainage waters at, 200; drain gauges at, 75; drought of 1870 at, 102; investigations on fixation of nitrogen at, 162; lime in soil of, 194; losses of nitrogen in manure at, 181; method of sampling soils at, 46; nitrates in soil at, 176; phosphoric acid in soil of, 199; potash in soil of, 195; weights of soil at, 62.

 SACHS on temperature and transpiration, 115; on water in soil when plants wilt, 81.
 Salfeld on soil inoculation, 169.
 Salt, causing sterility, 222; marshes, vegetation of, 254.
 Sampling of soils, 45.
 Sand, origin of, 17, 30, 33; velocity of current required to carry, 33.
 Sandy soils, 249.

- Saussure on theory of nutrition, 161.
 Schloesing on colloid clay, 35 ; on mechanical analysis of soils, 48.
 Schloesing and Müntz on nitrification, 171.
 Schloesing *filis* on fixation of nitrogen, 167.
 Schneidewind on denitrification, 179 ; on fixation of nitrogen, 170.
 Schultz on green manuring, 169.
 Sedentary soils, 7.
 Selenite, 24.
 Senft on decomposition of felspar, 19.
 Serpentine, 22.
 Sewage farms, crops on, 87 ; purification of, by soil, 191.
 Shingle, growth of vegetation on, 10.
 Shrinkage of clay on drying, 34, 80.
 Silica, 18.
 Soil, alkali, 223 ; analyses of, Appendix I. ; mechanical analyses of, 53 ; description of, 7 ; drift, 8 ; gases, 13 ; inoculation, 169 ; of transport, 8 ; relation to subsoil, 26 ; sedentary, 7 ; worn-out, 27.
 Soot, effect on temperature of soil, 118.
 Specific heat of soils, 118.
 Spring cultivation, gain of water by, 92 ; frosts, 123.
 Stahl on mycorrhiza, 183.
 Sterility of soils, 220.
 Stoklasa on alinit, 159.
 Stones, reputed growth on arable land, 12 ; retention of moisture by, 100 ; warming effect of, 121.
 Subsoil, description of, 7, 27 ; as regulator of water supply, 95.
 Surface of soil particles, area of, 63 ; retention of salts on, 190.
 Surface tension, 68 ; cohesion due to, 79 ; variations in, 78.
 Surveys, soil, 263.
 TALC, 22.
 Temperature, effect of colour on, 117 ; effect of exposure on, 123 ; required for growth, 114 ; weathering due to alternations of, 9.
 Texture of soil, 57.
 Thanet sand, soils on, 54.
 Thompson on absorption of salts by soil, 189.
 Tilth, 93, 97.
 Transpiration, 84, 184.
 UREA, conversion into ammonia, 158.
 VELOCITY of currents carrying sand grains, 33.
 Ville on fixation of nitrogen, 165.
 Vineyards, stones on surface of, 100.
 Voelcker on absorption of manures by soil, 190 ; an analysis of drainage waters, 200 ; on fixation of nitrogen, 165 ; on "finger-and-toe" in turnips, 187.
 WAGNER on denitrification, 179.
 Warington, on determinations of nitrates in soils, 130 ; on denitrification, 177 ; on nitrification, 171 ; on wetness of land in February, 83.
 Warp soils, 231 ; growth of potatoes on, 2.
 Water capacity of soil, 64, 77.
 Water table, 74.
 Way on absorption of salts by soil, 189.
 Weathering, 7 ; due to alternations of temperature, 9 ; due to frost, 11 ; due to water and carbonic acid, 13 ; due to roots, 14 ; of granite, 19 ; of basalt, 21.

- Weight of a cubic foot of soil, 61.
Wilfarth on fixation of nitrogen, 165.
Wilting of plants in soils containing water, 81.
Wind, transport of soil by, 10.
Winogradsky on iron bacteria, 182 ; on nitrification, 172 ; on nitrogen fixing bacteria, 170.
Woburn, lime in soil at, 193 ; residues left by ammonia salts at, 210 ; weight of cubic foot of soil at, 62 ; Fruit Farm, growth of trees planted with grass, 105.
Wollny on composition of soil gases, 13 ; on effect of slope on temperature, 123 ; on oxidation of humic acid, 159 ; on water required by crops, 84.
Worms, fine soil brought to surface by, 15.
Worn-out soils, 27.
XEROPHYTES, 247.



PRINTED BY
OLIVER AND BOYD
EDINBURGH



Telegraphic Address—
GUIDEBOOK, LONDON

MR. MURRAY'S
CATALOGUE OF
EDUCATIONAL
WORKS

LONDON
JOHN MURRAY, 50A, ALBEMARLE STREET, W.
1903

BOYLE, SON & WATCHURST,
PRINTERS,
3, 4 AND 5, WARWICK SQUARE E.C.

MR. MURRAY'S CATALOGUE OF EDUCATIONAL WORKS.

MR. MURRAY'S HOME AND SCHOOL LIBRARY.

Edited by LAURIE MAGNUS, M.A.,
MAGDALEN COLLEGE, OXFORD.

This Library, which will ultimately cover, in convenient and attractive volumes, a wide field of human knowledge, is intended "A" for the general reader "B" for the special student of Literature or Technology. The line of demarcation is not absolutely rigid, for all the volumes in the Library have an educational aim, and many are adapted to definite examinations. But while the "A" Series will be found of service to the general reader, for the purpose of self-information, as well as to the special student of the subject which it treats, the "B" Series is designed more strictly for use in schools and classes.

The volumes are illustrated by maps, diagrams, &c. The following are now ready:—

"A" SERIES.

FIRST MAKERS OF ENGLAND. Julius Cæsar, King Arthur, Alfred the Great. By Lady MAGNUS, Author of "Boys of the Bible," etc. With Illustrations. F'cap 8vo. 1s. 6d.

This volume is based on the recommendations for history teaching made by Professor Withers at the invitation of the School Board for London.

"In her hands the old legends lose nothing of their beauty in force or power of inspiration. . . . Cannot fail to interest both the children for whom it is primarily intended and children of a larger growth. The moral teaching which forms the basis of the work, though not obtruded, is beyond praise."—

Educational Times.

HOME AND SCHOOL LIBRARY—*continued.***A SHORT HISTORY OF COINS AND CURRENCY.**

By Lord AVEBURY, F.R.S., &c. With many Illustrations.
F'cap 8vo. 2s.

"... a treatise as fascinating as a romance."—*Outlook.*

PLATO'S 'REPUBLIC.' By Prof. LEWIS CAMPBELL, Hon. Fellow of Balliol College, Oxford. With Illustrations. F'cap 8vo. 2s.

"Professor Campbell has done good service in writing this excellent book."—*Spectator.*

"An excellent addition to the Home and School Library. . . . The sketch of the purpose and development of Plato's work is admirable."—*Morning Post.*

INTRODUCTION TO POETRY. (Poetic Expression, Poetic Truth, the Progress of Poetry.) By LAURIE MAGNUS, M.A. F'cap 8vo. 2s.

"... from beginning to end it is excellent, and the delightful style, the breadth and incisiveness of view, the delights which it opens upon life and thought, and the frequently deep philosophy which is attractively veiled in the Author's persuasive rhetoric, make it at times fascinating."—*School World.*

"He has brought to the task a critical taste and judgment almost as refined and often as illuminating as that of Ruskin."—*Yorkshire Post.*

HEROES OF THE WEST, A BIOGRAPHICAL SKETCH OF MODERN HISTORY, by the Rev. A. J. and Mrs. CARLYLE and F. S. MARVIN, M.A. 2 vols.

Vol. I. With four Illustrations. F'cap 8vo. 2s.

THE FACE OF NATURE. Popular Readings in Elementary Science. By the Rev. C. T. OVENDEN, D.D., Canon of St. Patrick's, Rector of Enniskillen. With numerous Illustrations. F'cap 8vo. 2s.*IN ACTIVE PREPARATION.***MUSIC.** By A. KALISCH, B.A.**INTRODUCTION TO PHILOSOPHY.** By S. RAPPOPORT, Ph.D.**TENNYSON'S 'ÆNONE.'** By LAURIE MAGNUS, M.A.**ANIMAL LIFE.** By W. B. BOTTOMLEY, Professor of Botany at King's College, London University, and Professor of Biology at the Royal Veterinary College.**PLANT LIFE.** By W. B. BOTTOMLEY.**ARCHITECTURE.** By CECIL HEADLAM, Author of "Nuremberg" and "Chartres," in the *Medieval Towns* Series, etc.

HOME AND SCHOOL LIBRARY—*continued.*

"B" SERIES.

ALGEBRA. Part I. By E. M. LANGLEY, M.A., Senior Mathematical Master, Modern School, Bedford, and S. R. N. BRADLY, M.A., Mathematical Master, Modern School, Bedford. F'cap 8vo. 1s. 6d.

This volume is specially adapted to the requirements of the First Stage of the Directory of the Board of Education, South Kensington.

Professor JOHN PERRY, of the Royal College of Science, South Kensington, writes:—"I never do praise a book unless I believe it to be good. Your Algebra (regarded as a book for beginners) pleases me very much indeed. I cannot imagine an Algebra prepared for schools in general, and especially for use by teachers in general, which would come nearer to my notion of what an Algebra ought to be, than yours."

A FIRST COURSE OF PRACTICAL SCIENCE, with full directions for experiments and numerous Exercises. By J. H. LEONARD. B.Sc. Lond. With a Preface by the late Dr. GLADSTONE, F.R.S. F'cap 8vo. 1s. 6d.

"This is an admirable little book. . . . The great point of Mr. Leonard's book is that he writes, as do too few instructors, for the absolutely ignorant pupil, and that unfortunate being is the one who is too often not considered. In all the experiments he gives the reason why. . . . Such books as the one before us should be scattered broadcast."—*The Lancet*.

"The author evidently understands the difficulties which assail a young boy who is starting on a course of experimental Science."—*Journal of Education*.

A FIRST COURSE OF CHEMISTRY. By J. H. LEONARD, Author of "A First Course of Practical Science." With numerous Diagrams. F'cap 8vo. 1s. 6d.

" . . . An excellent little book for young students . . . expounded with admirable simplicity and good order . . . a valuable introduction to experimental knowledge of the constitution of things."—*Scotsman*.

ELECTRIC WIRING. A Primer for the use of Wiremen and Students. By W. C. CLINTON, B.Sc. (Lond.), Demonstrator in the Pender Laboratory, University College, London. With 80 Illustrations and a selection of worked examples. F'cap 8vo. 1s. 6d.

Written with particular reference to the requirements of the examinations of the City and Guilds of London Institute.

"It is written in simple and comprehensive language, free from technicalities, except such as are duly explained in the course of the text . . . the section on jointing being exceptionally good . . . this little work is replete with useful information to those engaged in electrical wiring."—*Electricity*.

GEOMETRY. An Elementary Treatise on the Theory and Practice of Euclid. Having in view the New regulations of the Oxford and Cambridge Local, the London Matriculation, The Board of Education, and other Examinations. By S. O. ANDREW, M.A., Head Master of Whitgift Grammar School, Croydon. F'cap 8vo. 2s.

IN ACTIVE PREPARATION.

TELEGRAPHS AND TELEPHONES. By Sir W. H. PREECE, K.C.B., etc., sometime President of the Institute of Civil Engineers.

THE CALCULUS FOR ARTISANS. By Prof. O. HENRICI, F.R.S., etc.

ALGEBRA. Part II. By E. M. LANGLEY and S. R. N. BRADLY

MR. MURRAY'S NEW SERIES OF SECONDARY EDUCATION TEXT-BOOKS.

EDITED BY LAURIE MAGNUS, M.A.,
Magdalen College, Oxford.

COMMERCIAL FRENCH. In Two Parts. By W. MANSFIELD POOLE, M.A., Instructor in French to the Channel Squadron, formerly Assistant-Master at Merchant Taylors' School, AND MICHEL BECKER, Professor at the Ecole Alsacienne, Paris; Author of "L'Allemand Commercial," and "Lectures Pratiques d'Allemand Moderne." With a Map in each Volume. Crown 8vo. 2s. 6d. each.

"... a most careful piece of work ... an excellent book ... we warmly recommend to all who have to teach Commercial French."

—*Educational Times.*

"The good opinion formed by us on seeing Part I. is confirmed by the second instalment, really an admirable piece of work. We know of no better book to serve as an introduction to the more strictly technical study of Commercial French."—*School World.*

BRITAIN OVER THE SEA. A Reader for Schools. Compiled and edited by ELIZABETH LEE, Author of "A School History of English Literature," etc.; Editor of "Cowper's Task and Minor Poems," etc. With Four Maps of the British Empire at different periods. Crown 8vo. 2s. 6d.

MR. P. A. BARNETT (H.M. Inspector of Training Colleges).—"I congratulate you on the production of a very excellent piece of work. I hope the schools will use it; but it is almost too good for them."

COMMERCIAL KNOWLEDGE. A Manual of Business Methods and Transactions. By ALGERNON WARREN. Crown 8vo. 2s. 6d.

"The book should be used in every senior class both of our board and private schools, and as an introduction to business life it should prove of great value."—*Statist.*

INTERMEDIATE FRENCH GRAMMAR AND OUTLINES OF SYNTAX, with Historical Notes. By G. H. CLARKE, M.A., of Hymers College, Hull, and L. R. TANQUEREY, B.ès.L. Crown 8vo. 3s. 6d.

"... In short, we like it much, for it is full without confusion, correct without pedantry, and modern without vulgarity."—*Guardian.*

ARITHMETIC MADE EASY. Lectures on method, with Illustrations for Teachers and Pupils. By MABEL A. MARSH. Crown 8vo. 2s.

This manual applies the heuristic method to arithmetic-teaching, and is especially recommended for use in Training Colleges and for all members of the teaching profession.

SECONDARY EDUCATION TEXT-BOOKS—

continued.

COMMERCIAL GERMAN. In Two Parts. By GUSTAV HEIN, University of Berlin, and Lecturer in German (Honours) to the University of Aberdeen, and MICHEL BECKER, Professor of Modern Languages in the Ecole Alsacienne, Paris.

PART I. with a Map. Crown 8vo. 3s. 6d.

This manual is uniform with the first part of *Commercial French* by Poole and Becker, and is specially adapted for the use of students in commercial classes and continuation schools.

PART II. *In the Press.*

FRENCH COMMERCIAL CORRESPONDENCE. By Professor CHARLES GLAUSER, and W. MANSFIELD POOLE, M.A. Crown 8vo. 4s. 6d.

"Both as a handbook and as a work of reference, the work seems well calculated to supply the needs of advanced students, and to be of extreme utility to persons already engaged in the practice of commercial pursuits."—*Guardian*.

CHRONIQUE DU RÈGNE DE CHARLES IX. By PROSPER MÉRIMÉE. Prepared and Edited for the use of Schools by Professor ERNEST WEEKLEY, M.A., University College, Nottingham. With Historical and brief Grammatical Notes, and a Critical Essay. Crown 8vo. 2s. 6d.

This volume which will be followed by a School edition *Le Gendre de M. Poirier*, by the same editor, and by other French and German texts, is prepared according to the most approved methods of modern language-teaching, and may confidently be recommended to the attention of masters and mistresses.

GRAMMAIRE FRANÇAISE. By W. MANSFIELD POOLE, M.A., Instructor in French to the Channel Squadron, formerly Assistant Master at Eton. Crown 8vo.

ENGLISH COMPOSITION AND ESSAY WRITING. By L. COPE CORNFORD.

THE SOIL. By A. D. HALL, M.A., Principal of the South Eastern Agricultural College. Crown 8vo. With Diagrams, etc. 3s. 6d.

This volume, by the Principal of the County Council College at Wye, is the first of a group of text-books intended for the use of students in Agriculture. Other volumes, which will be duly announced, will deal with "Plant Physiology," "Manures," etc. *[In the Press.]*

ELEMENTS OF POLITICAL ECONOMY. By JAMES BONAR, M.A., LL.D., Author of "Malthus and his Work," "Philosophy and Political Economy," &c. *[In the Press.]*

THEORIES OF TAXATION. By G. ARMITAGE SMITH, M.A., Principal of the Birkbeck Institute. *[In the Press.]*

MERCANTILE LAW. By SIDNEY HUMPHRIES, B.A., LL.D., Principal of the City of London College. *[In the Press.]*

BOTANY. By WILLIAM CROSS. *[In the Press.]*

OTHER VOLUMES TO FOLLOW.

MURRAY'S HANDY CLASSICAL MAPS.

A NEW SYSTEM.

Edited by G. B. GRUNDY, M.A.,

BRASENOSE COLLEGE, OXFORD.

These Maps have been recognised as the best and most convenient in existence for the use of scholars and students at the universities and upper classes of schools.

The old method of engraving and hatching the mountain ranges has been exchanged for that of colouring the contours with flat brown and green tints, which is now recognised as the best and most intelligible way of denoting the configuration of the land. A separate Index is included with each Map.

LIST OF MAPS IN THE SERIES:

GRAECIA	{ Northern Greece South and Peloponnesus }	Two sheets in one case, 3s. cloth; 1s. 6d. net, paper. [NOW READY.
GALLIA	- - - - -	One sheet, 2s. cloth; 1s. net, paper. [NOW READY.
BRITANNIA	- - - - -	One sheet, 2s. cloth; 1s. net, paper. [NOW READY.
HISPANIA	- - - - -	One sheet, 2s. cloth; 1s. net, paper. [NOW READY.
ITALIA	{ Northern Italy South and Sicily. }	Two sheets in one case, 3s. cloth; 1s. 6d. net, paper. [NOW READY.
GERMANIA, RHAETIA, ILLYRIA, MOESIA, etc.	}	One sheet, 2s. cloth; 1s. net, paper. [NOW READY.
PALESTINE, SYRIA, and part of MESOPOTAMIA, and a Map showing St. Paul's Voyages	}	Three Maps on one sheet, 2s. cloth; 1s. net, paper. [NOW READY.
THE ROMAN EMPIRE (at different epochs)	}	Two Maps on one sheet, 2s. cloth; 1s. net, paper. [JUST OUT.
The EASTERN EMPIRES including EGYPT	}	Two Maps on one sheet, 2s. cloth; 1s. net, paper. [JUST OUT.
* ASIA MINOR and MARE AEGAEUM	}	Two Maps on one sheet, 2s. cloth; 1s. net, paper. [NEARLY READY.

An Index is bound in each case.

"... are admirable, and will prove of great assistance to students of ancient history. We have before warmly praised the colour-system of the maps and we need only say of this one (Graecia) that it will help those that use it to realize the relations and circumstances of the Ancient Greek States far better than any other map with which we are acquainted."—*Educational Times*.

* The preparation of this Map has been undertaken by Mr. J. G. C. Anderson, Christ Church, Oxford.

THE PROGRESSIVE SCIENCE SERIES.

Large 8vo, cloth extra, 6s. per volume.

NOW READY.

THE STUDY OF MAN: AN INTRODUCTION TO ETHNOLOGY. By PROFESSOR A. C. HADDON, D.Sc., M.A., M.R.I.A. Illustrated.

THE GROUNDWORK OF SCIENCE. By ST. GEORGE MIVART, M.D., Ph.D., F.R.S.

EARTH SCULPTURE. By PROFESSOR GEIKIE, LL.D., F.R.S. Illustrated.

RIVER DEVELOPMENT. As Illustrated by the Rivers of North America. By PROFESSOR I. C. RUSSELL. Illustrated.

VOLCANOES. By PROFESSOR BONNEY, D.Sc., F.R.S. Illustrated.

BACTERIA. ESPECIALLY AS THEY ARE RELATED TO THE ECONOMY OF NATURE, TO INDUSTRIAL PROCESSES, AND TO THE PUBLIC HEALTH. By GEORGE NEWMAN, M.D., F.R.S.E., D.P.H., Demonstrator of Bacteriology in King's College, London. With over 90 other Illustrations.

Corrected (2nd) Edition, and with an added Chapter on Tropical Diseases, an Account of Malarial Infection by Mosquitoes, and other Subjects.

A BOOK OF WHALES. By the Editor of the Series, F. E. BEDDARD, M.A., F.R.S. With 40 Illustrations by SIDNEY BERRIDGE.

THE COMPARATIVE PHYSIOLOGY of the BRAIN AND COMPARATIVE PSYCHOLOGY. By PROFESSOR JACQUES LOEB, M.D., Professor of Physiology in the University of Chicago.

THE STARS: A STUDY OF THE UNIVERSE. By PROFESSOR NEWCOMB. Illustrated.

EXPERIMENTS ON ANIMALS. By STEPHEN PAGET, F.R.C.S.

IN COURSE OF PRODUCTION.

HEREDITY. By J. ARTHUR THOMSON, M.A., F.R.S.E. Illustrated. Author of "The Study of Animal Life," and co-Author of "The Evolution of Sex." With numerous Diagrams and Illustrations.

PROGRESSIVE SCIENCE SERIES—*continued.**IN COURSE OF PRODUCTION.*

THE ANIMAL OVUM. By F. E. BEDDARD, M.A., F.R.S. (the Editor). Illustrated.

THE REPRODUCTION OF LIVING BEINGS; A COMPARATIVE STUDY. By MARCUS HARTOG, M.A., D.Sc., Professor of Natural History in Queen's College, Cork. Illustrated.

METEORS AND COMETS. By PROFESSOR C. A. YOUNG.

THE MEASUREMENT OF THE EARTH. By PRESIDENT MENDENHALL.

EARTHQUAKES. By MAJOR DUTTON.

PHYSIOGRAPHY; OR, THE FORMS OF LAND. By PROFESSOR DAVIS.

THE HISTORY OF SCIENCE. By C. J. PIERCE.

RECENT THEORIES OF EVOLUTION. By PROFESSOR BALDWIN.

LIFE AREAS OF NORTH AMERICA: A STUDY IN THE DISTRIBUTION OF ANIMALS AND PLANTS. By DR. C. HART MERRIAM.

PLANETARY MOTION. By G. W. HILL, Ph.D.

INFECTION AND IMMUNITY. By GEORGE S. STERNBERG, M.D., Surgeon-General of the U.S. Army.

AGE, GROWTH, SEX, AND DEATH. By PROFESSOR CHARLES S. MINOT, Harvard Medical School.

Other Volumes will shortly be announced, and the Series in its entirety will comprise volumes on every branch of Science.

MR. MURRAY'S STUDENT'S MANUALS.

Several years have passed since the death of Sir William Smith, and the publisher of his famous dictionaries, manuals, and educational works of all kinds is now engaged in the necessary task of revision and republication. Modern scholarship has reinforced the results of previous research, and modern methods of teaching have improved the old tradition. In accordance with these new requirements, the services of competent teachers and writers have been requisitioned in order to maintain the high level of accuracy, attractiveness, and usefulness which has already raised these books to the rank of standard school classics. No pains are spared to preserve for the name of Sir William Smith the place which it has held unchallenged throughout the schools of Great Britain for more than a generation; and the publisher is confident that masters and pupils, and the general reader too, will continue to recognise the unique position which it occupies in the educational world.

The series of Student's Manuals, Ancient and Modern, issued by Mr. Murray, and most of them edited by Dr. William Smith, possess several distinctive features which render them singularly valuable as Educational Works. They incorporate, with judicious comments, the researches of the most recent historical investigators, not only into the more modern, but into the most remote periods of the history of the countries to which they refer. While each volume is

thus, for ordinary purposes, a complete history of the country to which it refers, it also contains a guide to such further and more detailed information as the advanced student may desire on particular events or periods. At the end of each book, sometimes of each chapter, there are given copious lists of standard works which constitute the "Authorities" for a particular period or reign.

Before the publication of these STUDENT'S MANUALS there had been established, by the claims of middle class and competitive examiners, a large annual demand for text-books that should rise above the level of mere schoolboys' epitomes, and give to those who would master them some shadow of a scholarly knowledge of their subjects. Such books were very hard to find. Mr. Murray's Manuals, however, are the most suited for this purpose. They are most fit for use in the higher classes of good schools, where they may be deliberately studied through with the help of a teacher competent to expand their range of argument, to diversify their views by the strength of his own reading and reflection, and to elicit thought from the boys themselves upon events and the political changes to which they have led. The mature scholar also may be glad to have on his shelves these volumes, from which he can at a glance refresh his memory as to a name or date. And he will not use them for reference alone: he will assuredly be tempted to read them for the clearness of statement and the just proportion with which there is traced in each of them the story of a nation.

MURRAY'S STUDENT'S MANUALS.

A Series of Class-books for Advanced Scholars.

FORMING A CHAIN OF HISTORY FROM THE EARLIEST AGES
DOWN TO MODERN TIMES.

English History and Literature.

THE STUDENT'S HUME: A HISTORY OF ENGLAND, FROM THE EARLIEST TIMES TO THE REVOLUTION IN 1688. By DAVID HUME. Incorporating the Researches of recent Historians. Revised, corrected, and continued to the Treaty of Berlin in 1878, by J. S. BREWER, M.A. With Notes, Illustrations, and 7 Coloured Maps and Woodcuts. Crown 8vo. 7s. 6d.

*** Also in Three Parts. 2s. 6d. each.

I. FROM B.C. 55 TO THE DEATH OF RICHARD III., A.D. 1485

II. HENRY VII. TO THE REVOLUTION, 1688.

III. THE REVOLUTION TO THE TREATY OF BERLIN, 1878.

*** Questions on the "Student's Hume." 12mo. 2s.

STUDENT'S CONSTITUTIONAL HISTORY OF ENGLAND. FROM THE ACCESSION OF HENRY VII. TO THE DEATH OF GEORGE II. By HENRY HALLAM, LL.D. Crown 8vo. 7s. 6d.

STUDENT'S MANUAL OF ENGLISH LITERATURE. A History of English Literature of the chief English Writers founded upon the Manual of THOMAS B. SHAW. A new Edition thoroughly revised. By A. HAMILTON THOMPSON, B.A., of St. John's Coll., Cambridge, and Univ. Extension Lecturer in English Literature. With Notes, etc. Crown 8vo. 7s. 6d.

STUDENT'S SPECIMENS OF ENGLISH LITERATURE. Selected from the BEST WRITERS, and arranged Chronologically. By T. B. SHAW, M.A. Crown 8vo. 5s.

MURRAY'S STUDENT'S MANUALS—*continued.**Scripture and Church History.*

STUDENT'S OLD TESTAMENT HISTORY. FROM THE CREATION OF THE WORLD TO THE RETURN OF THE JEWS FROM CAPTIVITY. With an Introduction to the Books of the Old Testament. By PHILIP SMITH, B.A. With 40 Maps and Woodcuts. Crown 8vo. 7s. 6d.

STUDENT'S NEW TESTAMENT HISTORY. WITH AN INTRODUCTION, CONTAINING THE CONNECTION OF THE OLD AND NEW TESTAMENTS. By PHILIP SMITH, B.A. With 30 Maps and Woodcuts. Crown 8vo. 7s. 6d.

STUDENT'S MANUAL OF ECCLESIASTICAL HISTORY. A History of the Christian Church to the Reformation. By PHILIP SMITH, B.A. 2 Vols. Crown 8vo. 7s. 6d. each.

PART I.—A.D. 30—1003. With Woodcuts.

PART II.—A.D. 1003—1614. With Woodcuts.

STUDENT'S MANUAL OF ENGLISH CHURCH HISTORY. By G. G. PERRY, M.A., Canon of Lincoln. 3 Vols. 7s. 6d. each.

1st Period. From the Planting of the Church in Britain to the Accession of Henry VIII. A.D. 596—1509.

2nd Period. From the Accession of Henry VIII. to the Silencing of Convocation in the EIGHTEENTH CENTURY. A.D. 1509—1717.

3rd Period. From the Accession of the House of Hanover to the Present Time. A.D. 1717—1884.

Ancient History.

STUDENT'S ANCIENT HISTORY OF THE EAST.

FROM THE EARLIEST TIMES TO THE CONQUESTS OF ALEXANDER THE GREAT, including Egypt, Assyria, Babylonia Media, Persia, Asia Minor, and Phœnicia. By PHILIP SMITH, B.A. With 70 Woodcuts. Crown 8vo. 7s. 6d.

STUDENT'S HISTORY OF GREECE. FROM THE

EARLIEST TIMES TO THE ROMAN CONQUEST. With Chapters on the History of Literature and Art. By SIR WM. SMITH, D.C.L. Thoroughly revised and in part rewritten by G. E. MARINDIN, M.A. With many new Maps and Illustrations. Crown 8vo. 7s. 6d.

STUDENT'S HISTORY OF ROME. FROM THE EARLIEST

TIMES TO THE ESTABLISHMENT OF THE EMPIRE. With Chapters on the History of Literature and Art. By DEAN LIDDELL. New and Revised Edition, incorporating the results of Modern Research, by P. V. M. BENECKE, M.A., Fellow of Magdalen College, Oxford. With Coloured and other Maps and numerous Illustrations nearly all prepared specially for this Edition. Crown 8vo. 7s. 6d.

MURRAY'S STUDENT'S MANUALS.—*continued.*Ancient History—continued.

STUDENT'S HISTORY OF THE ROMAN EMPIRE.
FROM THE ESTABLISHMENT OF THE EMPIRE TO THE ACCESSION OF
COMMODUS, A.D. 180. With Coloured Maps and Numerous Illustra-
tions. By J. B. BURY, Regius Professor of Modern History at
Cambridge. Crown 8vo. 7s. 6d.

STUDENT'S GIBBON. A HISTORY OF THE DECLINE AND FALL
OF THE ROMAN EMPIRE. Abridged from the Original Work by
SIR WM. SMITH, D.C.L., LL.D. A New and Revised Edition
in Two Parts. Crown 8vo. 5s. each.

PART I.—FROM THE ACCESSION OF COMMODUS TO THE DEATH
OF JUSTINIAN. By A. H. J. GREENIDGE, M.A., Lecturer and
Late Fellow of Hertford College, Lecturer in Ancient History at
Brasenose College, Oxford.

PART II.—FROM A.D. 565 TO THE CAPTURE OF CONSTANTINOPLE
BY THE TURKS. By J. G. C. ANDERSON, M.A., late Fellow of
Lincoln College, Student and Tutor of Christ Church, Oxford.
With Maps and Illustrations.

Europe,

STUDENT'S HISTORY OF MODERN EUROPE.
FROM THE CAPTURE OF CONSTANTINOPLE BY THE TURKS, 1453,
TO THE TREATY OF BERLIN, 1878. By RICHARD LODGE, M.A.,
Brasenose College, Oxford, Professor of Modern History, University
of Edinburgh. 4th Edition, thoroughly revised. Crown 8vo. 7s. 6d.

**STUDENT'S HISTORY OF EUROPE DURING THE
MIDDLE AGES.** By HENRY HALLAM, LL.D. Crown 8vo.
7s. 6d.

France.

STUDENT'S HISTORY OF FRANCE. FROM THE EARLIEST
TIMES TO THE FALL OF THE SECOND EMPIRE. By W. H. JERVIS,
M.A. A New Edition, thoroughly revised, and in great part re-
written, by ARTHUR HASSALL, M.A., Censor of Christ Church,
Oxford. With a Chapter on Ancient Gaul by F. HAVERFIELD,
M.A., Student of Christ Church, Oxford. Coloured Maps, and
many new Woodcuts. Crown 8vo. 7s. 6d.

Geography.

STUDENT'S MANUAL OF ANCIENT GEOGRAPHY.
By CANON BEVAN, M.A. 150 Woodcuts. Crown 8vo. 7s. 6d.

STUDENT'S GEOGRAPHY OF BRITISH INDIA.
POLITICAL AND PHYSICAL. By GEORGE SMITH, LL.D. With
Maps. Crown 8vo. 7s. 6d.

SIR WM. SMITH'S SMALLER MANUALS.

These Works have been drawn up for the Lower Forms, at the request of several teachers, who require more elementary books than the STUDENT'S HISTORICAL MANUALS.

SMALLER HISTORY OF ENGLAND. FROM THE EARLIEST TIMES TO THE YEAR 1887. Revised and enlarged. By Prof. RICHARD LODGE, M.A. With Coloured Maps and 68 Woodcuts. Crown 8vo. 3s. 6d.

SMALLER HISTORY OF GREECE. FROM THE EARLIEST TIMES TO THE ROMAN CONQUEST. With Coloured Maps, Plans, and Illustrations. Thoroughly revised by G. E. MARINDIN, M.A. Crown 8vo. 3s. 6d.

"Most excellently suited to its purpose; distinguished above all things by its lucidity. Altogether the book is excellent."—*Guardian*.

SMALLER HISTORY OF ROME. FROM THE EARLIEST TIMES TO THE ESTABLISHMENT OF THE EMPIRE. Thoroughly revised by A. H. J. GREENIDGE, M.A., Fellow of Hertford College, Oxford. With a Supplementary Chapter on the Empire to 117 A.D., by G. MINDLETON, M.A., under the Direction of Prof. W. M. RAMSAY, M.A., D.C.L. With Coloured Map, Plans, and Illustrations. Crown 8vo. 3s. 6d.

The "Smaller History of Rome" has been written and arranged on the same plan, and with the same object, as the "Smaller History of Greece." Like that work it comprises separate chapters on the institutions and literature of the countries with which it deals.

SMALLER HISTORY OF ENGLISH LITERATURE. Giving a Sketch of the Lives of our Chief Writers. By JAMES ROWLEY. Small Crown 8vo. 3s. 6d.

SMALLER SPECIMENS OF ENGLISH LITERATURE. Selected from the Chief Authors and arranged chronologically. By JAMES ROWLEY. With Notes. Small Crown 8vo. 3s. 6d.

While the "Smaller History of English Literature" supplies a rapid but trustworthy sketch of the lives of our chief writers, and of the successive influences which imparted to their writings their peculiar character, the present work supplies choice examples of the works themselves, accompanied by all the explanations required for their perfect explanation. The two works are thus especially designed to be used together.

SMALLER CLASSICAL MYTHOLOGY. With Translations from the Ancient Poets, and Questions on the Work. With 90 Woodcuts. Small Crown 8vo. 3s. 6d.

This work has been prepared by a lady for the use of schools, and young persons of both sexes. In common with many other teachers, she has long felt the want of a consecutive account of the heathen deities, which might safely be placed in the hands of the young, and yet contain all that is generally necessary to enable them to understand the classical allusions they may meet with in prose or poetry, and to appreciate the meanings of works of art.

A carefully prepared set of QUESTIONS is appended, the answers to which will be found in the corresponding pages of the volume.

SIR WM. SMITH'S SMALLER MANUALS

—continued.

SMALLER SCRIPTURE HISTORY OF THE OLD AND THE NEW TESTAMENT. IN THREE DIVISIONS:—I. Old Testament History. II. Connection of Old and New Testaments. III. New Testament History to A.D. 70. Edited by SIR WM. SMITH. With Coloured Maps and 40 Illustrations. Small Crown 8vo. 3s. 6d.
 "This book is intended to be used with, and not in place of, the Bible. The result is most satisfactory,"—*The Standard*.

SMALLER ANCIENT HISTORY OF THE EAST. FROM THE EARLIEST TIMES TO THE CONQUEST OF ALEXANDER THE GREAT. By PHILIP SMITH, B.A. With 70 Woodcuts. Small Crown 8vo. 3s. 6d.

SMALLER MANUAL OF ANCIENT GEOGRAPHY By CANON BEVAN, M.A. With Woodcuts. Small Crown 8vo 3s. 6d.

MRS. MARKHAM'S HISTORIES.

HISTORY OF ENGLAND. FROM THE FIRST INVASION BY THE ROMANS TO 1878. With Conversations at the end of each Chapter. 100 Woodcuts. 3s. 6d.

HISTORY OF FRANCE. FROM THE CONQUEST OF GAUL BY JULIUS CÆSAR TO 1878. Conversations at the end of each Chapter. 70 Woodcuts. 3s. 6d.

HISTORY OF GERMANY. FROM ITS INVASION BY MARIUS TO 1880. 50 Woodcuts. 3s. 6d.

LITTLE ARTHUR'S HISTORIES.

HISTORY OF ENGLAND. By LADY CALLCOTT. From the Roman Invasion down to 1878. With 36 Woodcuts. 16mo. 1s. 6d.
 "I never met with a history so well adapted to the capacities of children or their entertainment, so philosophical, and written with such simplicity."—Mrs. MARCETT.

HISTORY OF FRANCE. FROM THE EARLIEST TIMES TO THE FALL OF THE SECOND EMPIRE. With Map and Illustrations. 16mo. 2s. 6d.

"The jaded schoolboy, surfeited with tales and the 'over-pressure' arising from long attention to lives and adventures, will, towards the latter part of his holiday, turn with some relief to this book, and begin feasting afresh. Those who know what 'Little Arthur's England' did to popularise the subject among little folks, will know what to expect in this 'France.' The book is capitally illustrated, and very wisely the compiler does not reject the exciting and legendary parts of the subject."—*Schoolmaster*.

HISTORY OF GREECE. By A. S. WALPOLE, M.A. With Map, Plans and Illustrations. Fcap 8vo. 2s. 6d.

SIR WM. SMITH'S BIBLICAL DICTIONARIES.

DICTIONARY OF THE BIBLE: COMPRISING ITS ANTIQUITIES, BIOGRAPHY, GEOGRAPHY, AND NATURAL HISTORY. By Various Writers. With Illustrations. 3 vols. Enlarged and revised Edition. Medium 8vo. £4 4s.

Complete sets of the above work may be purchased through any Bookseller at reduced rates.

CONCISE DICTIONARY OF THE BIBLE. Condensed from the larger Work. For Families and Students. With Maps and 300 Illustrations. Medium 8vo. 21s.

A Dictionary of the Bible, in some form or another, is indispensable for every family. To students in the Universities, and in the Upper Forms at Schools, to private families, and to that numerous class of persons who desire to arrive at *results* simply, this **CONCISE DICTIONARY** will, it is believed, supply all that is necessary for the elucidation and explanation of the Bible.

SMALLER DICTIONARY OF THE BIBLE. Abridged from the larger Work. For Schools and Young Persons. With Maps and Illustrations. Crown 8vo. 7s. 6d.

"An invaluable service has been rendered to students in the condensation of Dr. Wm. Smith's Bible Dictionary. The work has been done as only a careful and intelligent scholar could do it, which preserves to us the essential scholarship and value of each article."—*British Quarterly Review*.

The two following Works are intended to furnish a complete account of the leading Personages, the Institutions, Art, Social Life, Writings, and Controversies of the Christian Church from the time of the Apostles to the Age of Charlemagne. They commence at the period at which the "Dictionary of the Bible" leaves off, and form a continuation of it.

DICTIONARY OF CHRISTIAN ANTIQUITIES. The History, Institutions, and Antiquities of the Christian Church. Edited by SIR WM. SMITH, D.C.L., and ARCHDEACON CHEETHAM, D.D. With Illustrations. 2 Vols. Medium 8vo. £3 13s. 6d.

"The work before us is unusually well done. A more acceptable present for a candidate for holy orders, or a more valuable book for any library, than the 'Dictionary of Christian Antiquities' could not easily be found."—*Saturday Review*.

DICTIONARY OF CHRISTIAN BIOGRAPHY, LITERATURE, SECTS, AND DOCTRINES. Edited by SIR WM. SMITH, D.C.L., and HENRY WACE, D.D. 4 Vols. Medium 8vo. £6 16s. 6d.

"The value of the work arises, in the first place, from the fact that the contributors to these volumes have diligently eschewed mere compilation. In these volumes we welcome the most important addition that has been made for a century to the historical library of the English theological student."—*Times*.

SIR WM. SMITH'S CLASSICAL DICTIONARIES.

"I am extremely glad of the opportunity of expressing to you the strong sense of obligation which I, in common with all teachers and lovers of classical literature, feel to you for your admirable Dictionaries."—Rev. Dr. HAWTREY, late Head Master of Eton College.

DICTIONARY OF GREEK AND ROMAN ANTIQUITIES. INCLUDING THE LAWS, INSTITUTIONS, DOMESTIC USAGES, PAINTING, SCULPTURE, MUSIC, THE DRAMA, ETC. Edited by SIR WM. SMITH, LL.D., Hon. D.C.L., Oxford, Hon. Ph.D., Leipzig; WILLIAM WAYTE, M.A., Late Fellow of King's College, Cambridge; G. E. MARINDIN, M.A., Late Fellow of King's College, Cambridge. Third Revised and Enlarged Edition. With 900 Illustrations. 2 Vols. Medium 8vo. 3rs. 6d. each.

CONCISE DICTIONARY OF GREEK AND ROMAN ANTIQUITIES. Based on Sir Wm. Smith's larger Dictionary, and Incorporating the Results of Modern Research. Edited by F. WARRE CORNISH, M.A., Vice-Provost of Eton College. With over 1,100 Illustrations taken from the best examples of Ancient Art. Medium 8vo. 2rs.

SMALLER DICTIONARY OF ANTIQUITIES. Abridged from Sir Wm. Smith's larger Dictionary. With 200 Woodcuts. Crown 8vo. 7s. 6d.

DICTIONARY OF GREEK AND ROMAN BIOGRAPHY AND MYTHOLOGY. By Various Writers. Edited by SIR WILLIAM SMITH, D.C.L., LL.D. Illustrated by 564 Engravings on Wood. In 3 Vols. Medium 8vo. 84s.

CLASSICAL DICTIONARY OF MYTHOLOGY, BIOGRAPHY, AND GEOGRAPHY, compiled from Sir Wm. Smith's larger Dictionaries. In great part re-written by G. E. MARINDIN, M.A., late Fellow of King's College, Cambridge, some time Assistant Master at Eton College. With over 800 Woodcuts. Thoroughly Revised Edition. 8vo. 18s.

SMALLER CLASSICAL DICTIONARY. Abridged from the above Work. With 200 Woodcuts. In great part re-written by G. E. MARINDIN, M.A., some time Assistant Master at Eton College. Crown 8vo. 7s. 6d.

DICTIONARY OF GREEK AND ROMAN GEOGRAPHY. Illustrated by 534 Engravings on Wood. 2 Vols. Medium 8vo. 56s.

SIR WM. SMITH'S LATIN DICTIONARIES.

"I consider Dr. Wm. Smith's Dictionaries to have conferred a great and lasting service on the cause of classical learning in this country."—Dean LIDDELL.

"I have found Dr. Wm. Smith's Latin Dictionary a great convenience to me. I think that he has been very judicious in what he has omitted, as well as what he has inserted."—Dr. SCOTT.

COMPLETE LATIN-ENGLISH DICTIONARY. BASED ON THE WORKS OF FORCELLINI AND FREUND. With Tables of the Roman Calendar, Measures, Weights, Money, and a DICTIONARY OF PROPER NAMES. By SIR WM. SMITH, D.C.L., LL.D. Medium 8vo. 22nd Edition. 16s.

"This work aims at performing the same service for the Latin language as Liddell and Scott's Lexicon has done for the Greek. Great attention has been paid to Etymology, in which department especially this work is admitted to maintain a superiority over all existing Latin Dictionaries.

SMALLER LATIN-ENGLISH DICTIONARY. WITH A SEPARATE DICTIONARY OF PROPER NAMES, TABLES OF ROMAN MONEYS, &c. Thoroughly revised and in great part re-written. Edited by SIR WM. SMITH and T. D. HALL, M.A. The Etymological portion by JOHN K. INGRAM, LL.D. Square 12mo. 7s. 6d.

This edition of Dr. Smith's 'Smaller Latin-English Dictionary' is to a great extent a new and original Work. Every article has been carefully revised.

COPIOUS AND CRITICAL ENGLISH-LATIN DICTIONARY. Compiled from Original Sources. By SIR WM. SMITH, D.C.L., and T. D. HALL, M.A. Medium 8vo. 16s.

It has been the object of the Authors of this Work to produce a more complete and more perfect ENGLISH-LATIN DICTIONARY than yet exists, and every article has been the result of original and independent research.

Each meaning is illustrated by examples from the classical writers; and those phrases are as a general rule given in both English and Latin.

SMALLER ENGLISH-LATIN DICTIONARY. Abridged from the above Work, by SIR WM. SMITH and T. D. HALL, M.A., for the use of Junior Classes. Square 12mo. 7s. 6d.

"An English-Latin Dictionary worthy of the scholarship of our age and country. It will take absolutely the first rank, and be the standard English-Latin Dictionary as long as either tongue endures. Even a general examination of the pages will serve to reveal the minute pains taken to ensure its fulness and philological value, and the work is to a large extent a dictionary of the English language, as well as an English-Latin Dictionary."—*English Churchman*.

MR. MURRAY'S CLASS BOOKS.

Languages.

FRENCH STUMBLING BLOCKS AND ENGLISH STEPPING STONES. By FRANCIS TARVER, M.A., late Senior French Master at Eton College. Fcap. 8vo. 2s. 6d.

Mr. Francis Tarver's skill as a teacher of French to Englishmen is well known. His thorough knowledge of *both* languages, and his thirty years' experience as a master at Eton, have afforded him exceptional opportunities of judging what are the difficulties, pitfalls, and stumbling-blocks which beset the path of an Englishman in his study of French.

THE TECHNICAL SCHOOL FRENCH GRAMMAR. By DR. W. KRISCH, sometime Teacher of Latin and Greek at the Birmingham Midland Institute, Examiner in Modern Languages to the Midland Counties' Union of Educational Institutions. Crown 8vo. 2s. 6d.

A CHILD'S FIRST LATIN BOOK. COMPRISING NOUNS, PRONOUNS, AND ADJECTIVES, WITH THE VERBS. With ample and varied Practice of the easiest kind. Both old and new order of Cases given. By T. D. HALL, M.A. Enlarged Edition, including the Passive Verb. 16mo. 2s.

TRANSLATION AT SIGHT; OR, AIDS TO FACILITY IN THE TRANSLATION OF LATIN. Passages of Graduated Difficulty, carefully selected from Latin Authors, with Explanations, Notes, &c. By PROFESSOR T. D. HALL, M.A. Crown 8vo. 2s.

GREEK GRAMMAR ACCIDENCE AND SYNTAX FOR SCHOOLS AND COLLEGES. By JOHN THOMPSON, M.A., late Scholar of Christ's College, Cambridge; Senior Classical Master, High School, Dublin. Crown 8vo. 6s.

One of the chief objects of this book is to bring within the reach of the younger generation of students and schoolboys some of the results of the linguistic discoveries of the present day. It is therefore written in accordance with the philological views of the *Grundriss der Vergleichenden Grammatik* of Professors Brugmann and Delbrück, of P. Giles' *Manual of Comparative Philology*, of G. Meyer's *Griechische Grammatik* and of other scholars. Use has also been made of the Third Edition, revised by Drs. Blass and Gerth, of Kühner's *Ausführliche Grammatik der Griechischen Sprache*, and of several school Greek Grammars in use in Germany.

The Grammar consists of two parts in one volume, Part I. containing the Accidence, and Part II. the Syntax. The forms and spelling in use in Attic Greek are given according to the latest authorities, and there are special notes on Homeric peculiarities. There are also tables of Greek verbs arranged on a new plan, including (a) a list of the chief types of verbs, (b) a list of common Attic verbs regular according to the types in (a), and (c) a list of the irregular verbs with the irregular forms printed in special type. This arrangement is intended to remove many misconceptions about Greek verbs. Brief notes on syntax, &c., are given with each verb stating the ordinary constructions and any special uses. There will also be Appendices on (1) Greek Weights, Measures, and Dates, (2) Accents, and (3) Sound Changes. Particular attention has been given to the type, so that the essential part of Greek Grammar may be made specially clear, and that the beginner may have no difficulty in distinguishing the more important sections.

MR. MURRAY'S CLASS BOOKS—*continued.*Languages—continued.

PRINCIPIA GRÆCA. An Introduction to the Study of Greek, comprehending Grammar Delectus, and Exercise Book with Vocabularies. By H. E. HUTTON, M.A. Balliol College, Oxford. For the use of the Lower Forms in Public and Private Schools. Crown 8vo. 3s. 6d.

ELUCIDATIONS OF THE STUDENT'S GREEK GRAMMAR. By PROF. CURTIUS. From the German, with the Author's sanction. By EVELYN ABBOTT, M.A. 2nd Edition. Crown 8vo. 7s. 6d.

A SHORT PRACTICAL HEBREW GRAMMAR; WITH AN APPENDIX. Containing the Hebrew Text of Genesis I—VI, and Psalms I—VI. Grammatical Analysis Vocabulary. By the REV. STANLEY LEATHES, D.D. Crown 8vo. 7s. 6d.

PRACTICAL SPANISH. A GRAMMAR OF THE SPANISH LANGUAGE. With Exercises, Vocabularies, and Materials for Conversation.

Part I.: NOUNS, ADJECTIVES, PRONOUNS, ETC.

Part II.: VERBS, ETC., WITH COPIOUS VOCABULARIES.

By DON FERNANDO DE ARTEAGA, Taylorian Teacher of Spanish in the University of Oxford. 2 Parts. Crown 8vo. 7s. 6d.

This book has in the main been formed on the plan of Sir William Smith's well-known and deservedly popular "Principia Latina, Part I." It possesses, however, one new feature which is as novel as it is likely to prove valuable to the student who uses the book. English people, for the most part, who set themselves to learn Spanish, are not children, but either would-be travellers in the country, students of its literature, or persons engaged in commerce with Spain or Spanish-speaking countries. It has therefore been the aim of the Editor throughout to avoid the old-fashioned Ollendorfen sentences in illustration of the grammar, and instead to make use of phrases and expressions which are likely to prove of practical use to the traveller and the man of business.

Gradus.

AN ENGLISH-LATIN GRADUS, OR VERSE DICTIONARY, for Schools. By A. C. AINGER, Trinity Coll., Cambridge, Assistant-Master at Eton College, and the late H. G. WINTLE, M.A., Christ Church, Oxford. This Gradus is on a new plan, intended to simplify the Composition of Latin Verses by Classical Meanings, selected Epithets and Synonyms, etc. Crown 8vo. 9s.

MR. MURRAY'S CLASS BOOKS—*continued.*Geography.**PREPARATORY GEOGRAPHY for IRISH SCHOOLS.**

With numerous Coloured Maps, Relief Maps, Plans, and Views of well-known Places in Illustration of Geographical Terms. By JOHN COOKE, M.A., Lecturer in Geography, Church of Ireland Training College; and Examiner to the Board of Intermediate Education. Small Crown 8vo. 1s. 6d.

"Mr. Cooke's eminent services to the literature of education have seldom been better illustrated than in this Geography for Irish Schools. . . . Mr. Cooke claims that his Geography is suggestive rather than exhaustive. He might reasonably have gone a step further, and claimed the high merit of charm of attractiveness. With such a wealth of apt illustration drawn from our own country, no child could for a moment fail to comprehend what he sees and hears."

—*The Irish Times.*

History and Literature.**THE GROWTH OF THE EMPIRE.** By A. W. JOSE.

With many Coloured and other Maps and Diagrams. Cr. 8vo. 6s.

" . . . an eminently useful book . . . as serviceable as it is readable. It is systematic in method and accurate in statement."—*The Globe.*

HALLAM'S CONSTITUTIONAL HISTORY OF ENGLAND, Chapters I. to IX. Bound together in 1 Volume for the

special use of candidates for the London University Examinations.

Crown 8vo. 5s.

EUROPE IN THE MIDDLE AGES. By OLIVER J. THATCHER, Ph.D., and FERDINAND SCHWILL, Ph.D.

Large Crown 8vo. 9s.

This work has been written by men who have had long experience in teaching, to supply the want of a compendious History of Medieval Europe, from the middle of the Fourth to the close of the Fifteenth Century, which has been long felt in the universities and schools. A distinguished Professor of Modern History in one of our leading universities, to whom a copy has been sent, writes:

"The book covers ground on which it has always been hard to get a suitable book for educational purposes, and, so far as I can judge—I have as yet only examined the German History of the 10th Century—it is thoroughly sound and clear

A GENERAL HISTORY OF EUROPE, 350–1900.

By OLIVER J. THATCHER and FERDINAND SCHWILL, Authors of "Europe in the Middle Ages." Revised and adapted to the requirements of English Colleges and Schools, by ARTHUR HASSALL, M.A., Christ Church, Oxford. With Bibliographies at the end of each section. With Maps, Genealogical Tables. Crown 8vo. 9s.

" . . . a model of condensation, omitting no essential facts. . . . The volume is greatly enhanced by a wealth of maps and chronological and genealogical tables. Among general histories this will take a leading place."—

Dunee Advertiser.

MR. MURRAY'S CLASS BOOKS—*continued.*History and Literature—continued.

A POPULAR HISTORY OF THE CHURCH OF ENGLAND. FROM THE EARLIEST TIMES TO THE PRESENT DAY. By the Rt. Rev. WILLIAM BOYD CARPENTER, The Lord Bishop of Ripon. Illustrated. Crown 8vo. 6s.

"The title is, perhaps, hardly wide enough for the contents; one would almost call the book a history of Christianity in England. . . . He has the true judicial spirit, and is passionately eager to be entirely fair to every one. His history is impartial to the last degree. . . . His book should have a very wide circulation, and can do nothing but good wherever it is read."—*Morning Post.*

THE PUBLIC SCHOOL SPEAKER. Compiled by F. WARRE CORNISH, M.A., Vice-Provost of Eton College. Large 8vo. 7s. 6d.

This work, as its name implies, is a collection of pieces suitable for recitation at school "speeches." The Editor has made his selection in the widest manner and from various languages—Greek, Latin, English, German, French and Italian. He has included drama, general poetry, orations and other prose pieces, ancient and modern. The Editor is in hopes that no serious omissions can be found, unless it be those intentional ones from classics that are at everyone's command, which he has left out to make room for those more difficult of access.

It will be noticed that he has in many cases given an extract longer than is sufficient for a single recitation—he has done this advisedly with a view to affording greater scope for individual requirements and individual taste.

The publisher is of opinion that the Speaker will be found the most complete extant.

"No such comprehensive work has hitherto been issued, and in our opinion 'The Public School Speaker' has leaped at a single bound into the very foremost rank, and has become the classic of its kind."—*The Bookseller.*

ELEMENTARY TEACHERS' CERTIFICATE EDITION.

STANLEY'S LIFE OF ARNOLD. With a Preface by Sir JOSHUA FITCH, LL.D., formerly H.M. Chief Inspector of Training Colleges. Large type, 800 pages, in 1 volume. With Photogravure Portrait and 16 half-tone Illustrations. Crown 8vo. 6s.

"Stanley's Life of Arnold has been selected by the Board of Education as a subject of examination for intending teachers, so that this edition will be heartily welcomed."—*Educational Times.*

ÆSOP'S FABLES. A NEW VERSION. Chiefly from the Original Sources. By REV. THOMAS JAMES. With 100 Woodcuts. Illustrations by JOHN TENNIEL. Crown 8vo. 2s. 6d.

"This work is remarkable for the clearness and conciseness with which each tale is narrated; and the book has been relieved of those tedious and unprofitable appendages called 'morals,' which used to obscure and disfigure the ancient editions of the work."—*The Examiner.*

MR. MURRAY'S CLASS BOOKS—*continued.*Classical Study.

CHAPTERS FROM ARISTOTLE'S ETHICS. By J. H. MUIRHEAD, M.A., Professor of Mental and Moral Philosophy, Mason University College, Birmingham. Author of "The Elements of Ethics." Large crown 8vo. 7s. 6d.

"We cannot commend these 'chapters' too highly, not only to teachers, but to all students of Aristotle or of moral philosophy who feel that the problems of the Old Greeks are in any way unreal in these later days, or their solutions out of date."—*Pilot*.

HERODOTUS. THE TEXT OF CANON RAWLINSON'S TRANSLATION. With the Notes abridged for the use of Students. By A. J. GRANT, M.A., of King's College, Cambridge; Professor of History, Yorkshire College, Leeds; Author of "Greece in the Age of Pericles." With Map and Plans. 2 Vols. Crown 8vo. 12s.

"The delightful pages of the old Greek whose flavour has been so admirably presented by Canon Rawlinson, will thus be made accessible to a far wider circle than heretofore. There is no better introduction to Greek history and literature than Herodotus, and the English reader gets him here under the best possible conditions."—*Literary World*.

THE STORY OF THE PERSIAN WARS AS TOLD BY HERODOTUS. In English. Selected, arranged and edited, so as to form a History Reading Book for Schools. By the REV. C. C. TANCOCK, D.D., Head Master of Tonbridge School. With Illustrations, Map and Plans. Crown 8vo. 2s. 6d.

Biblical Study

GREEK TESTAMENT READER. FOR USE IN SCHOOLS, comprising consecutive Extracts from the Synoptic Gospel and Passages from the Epistles of St. Paul. By THEOPHILUS D. HALL, M.A. Crown 8vo. 2s. 6d.

THE SUNRISE OF REVELATION. New Testament Teachings for Secondary Schools. A Sequel to "The Dawn of Revelation." By Miss M. BRAMSTON, Author of "The Dawn of Revelation," "Judæa and her Rulers," etc. Crown 8vo. 5s. net.

"We do not think that any good judge will get far in the book without discovering that it is one of rare merit and exceptionally well suited to the class to whom it is addressed. We do not know of any book likely to be more useful to the teachers of secondary schools in the preparation of their Scripture lessons than this. It is clear, accurate, and full of instruction and suggestiveness. Miss Bramston shows a competent knowledge of the present position of criticism as to the Gospels and Acts, but she wisely keeps her learning in the background, and it only betrays itself by an occasional sentence or epithet. It is a great deal to say of any book dealing with the Scripture history that it is scholarly without being dry, and reverent without any trace of 'preaching.' Yet Miss Bramston has succeeded in all this and more. We do not often praise a book so unreservedly, but we shall be surprised if she does not attract a circle of readers far larger than that to which she has addressed herself in the first instance."—

The Guardian.

MR. MURRAY'S CLASS BOOKS—*continued.*Biblical Study—continued.**THE STUDENT'S COMMENTARY ON THE BIBLE.**

Abridged from the "Speaker's Commentary." Edited by JOHN M. FULLER, M.A., Vicar of Bexley, and formerly Fellow of St. John's College, Cambridge. Crown 8vo. 7s. 6d. each.

OLD TESTAMENT.—*Vol. I.*—Genesis to Deuteronomy. *Vol. II.*—Joshua to Esther. *Vol. III.*—Job to Song of Solomon. *Vol. IV.*—Isaiah to Malachi.

NEW TESTAMENT.—*Vol. I.*—Gospels to Acts. *Vol. II.*—Epistles to Revelation.

THE BIBLE IN THE HOLY LAND. Extracted from Dean Stanley's work on Sinai and Palestine. With Woodcuts. Crown 8vo. 3s. 6d.

Science (Elementary & General).

STUDENT'S ELEMENTS OF GEOLOGY. By SIR CHARLES LYELL. Thoroughly revised by PROF. J. W. JUDD. Crown 8vo. With 600 Woodcuts. 9s.

ELEMENTS OF AGRICULTURE. A Text-Book. Prepared under the authority of the Royal Agricultural Society of England. By W. FREAM, LL.D. New Edition (Seventh). Crown 8vo. 3s. 6d.

A HANDY BOOK OF HORTICULTURE. AN INTRODUCTION TO THE THEORY AND PRACTICE OF GARDENING. With Illustrations and Diagrams. By F. C. HAYES, M.A., Rector of Raheny; Lecturer in Practical Horticulture in Alexandra College, Dublin. Crown 8vo. 2s. 6d. net.

"... Just the book to place in the hands of young amateurs and Students, and should find a place on the shelves of every Village and County Council Library."—*The Field*.

THE INVISIBLE POWERS OF NATURE; SOME ELEMENTARY LESSONS IN PHYSICAL SCIENCE, HEAT, LIGHT, SOUND, GRAVITATION, SOLIDS, FLUIDS, ELECTRICITY, MAGNETISM, ETC. By E. M. CAILLARD. Post 8vo. 6s.

"We have rarely met with a work of the kind in which so much information is so clearly and so accurately set forth."—*Gardener's Chronicle*.

COLOUR IN NATURE: A STUDY IN BIOLOGY. By MARION NEWBIGIN. Crown 8vo. 7s. 6d.

"All who seek for well sifted results, and not merely superficial information, will thank her for this book, and congratulate her on a very timely contribution to biological literature."—*Journal of Education*.

MR. MURRAY'S CLASS BOOKS—*continued.*Science—continued.

EARLY CHAPTERS IN SCIENCE. A FIRST BOOK OF KNOWLEDGE OF NATURAL HISTORY, BOTANY, PHYSIOLOGY, PHYSICS AND CHEMISTRY FOR YOUNG PEOPLE. By Mrs. W. AWDRY (Wife of the Bishop of South Tokyo, Japan). Edited by W. F. BARRETT, F.R.S., Professor of Experimental Physics in the Royal College of Science for Ireland. With nearly 200 Illustrations. Crown 8vo. 6s.

"Deserves a warm welcome from all teachers of the young. . . . The illustrations are models of clear, careful, and unconventional work."—*Literature.*
"It can be confidently recommended to the young as a sound and pleasantly written introduction to science."—*Guardian.*

ELECTRICITY. THE SCIENCE OF THE NINETEENTH CENTURY. A Sketch for General Readers. By E. M. CAILLARD. With Illustrations. Crown 8vo. 7s. 6d.

THE FIVE WINDOWS OF THE SOUL: A POPULAR ACCOUNT OF THE HUMAN SENSES. By EDWARD HAMILTON AITKEN, author of "The Tribes on my Frontier," "Behind the Bungalow," "A Naturalist on the Prowl." Crown 8vo. 6s.

"There is probably nothing in recent literature which will so surely lead to a thirst for further and more technical knowledge than the author's treatment of these difficult subjects. . . . It is admirably written and cannot fail to give pleasure. It is so seldom that such a really good book as this is published that the hope may be expressed that it will meet with the success it deserves, and find a place in every good public and private library."—*Manchester Guardian.*

Jurisprudence.

AN ANALYSIS OF AUSTIN'S JURISPRUDENCE. By GORDON CAMPBELL. Crown 8vo. 6s.

STUDENT'S EDITION OF AUSTIN'S JURISPRUDENCE. Compiled from the larger work. By ROBERT CAMPBELL. Crown 8vo. 12s.

SIR WM. SMITH'S EDUCATIONAL SERIES.

English Course.

PRIMARY ENGLISH GRAMMAR for Elementary Schools. With 134 Exercises and carefully graduated passing lessons. By T. D. HALL, M.A. 16mo. 1s.

SCHOOL MANUAL OF ENGLISH GRAMMAR. With Historical Introduction and copious Exercises. By SIR WM. SMITH, D.C.L., and T. D. HALL, M.A. With Appendices. Crown 8vo. 3s. 6d.

MANUAL OF ENGLISH COMPOSITION. With Copious Illustrations and Practical Exercises. Suited equally for Schools and for Private Students of English. By T. D. HALL, M.A. Crown 8vo. 3s. 6d.

French Course.

FRENCH PRINCIPIA, Part I. A FIRST FRENCH COURSE, containing Grammar, Delectus and Exercises, with Vocabularies and Materials for French Conversation. Crown 8vo. 3s. 6d.

APPENDIX TO FRENCH PRINCIPIA, Part I. Containing Additional Exercises and Examination Papers. Cr. 8vo. 2s. 6d.

FRENCH PRINCIPIA, Part II. A READING BOOK. Containing Fables, Stories, and Anecdotes, Natural History, and Scenes from the History of France. With Grammatical Questions, Notes, and copious Etymological Dictionary. Crown 8vo. 4s. 6d.

FRENCH PRINCIPIA, Part III. PROSE COMPOSITION. Containing a Systematic Course of Exercises on the Syntax, with the Principal Rules of Syntax. Crown 8vo. 4s. 6d.

THE STUDENT'S FRENCH GRAMMAR; PRACTICAL AND HISTORICAL. FOR THE HIGHER FORMS. By C. HERON-WALL with INTRODUCTION by M. LITTRÉ. Crown 8vo. 6s.

A SMALLER FRENCH GRAMMAR. FOR THE MIDDLE AND LOWER FORMS. Abridged from the above Work. Crown 8vo. 3s. 6d.

SIR WM. SMITH'S EDUCATIONAL SERIES

— continued.

German Course.

GERMAN PRINCIPIA, Part I. A FIRST GERMAN COURSE. Containing Grammar, Delectus, Exercises, Vocabularies and materials for German Conversation. Cr. 8vo. 3s. 6d.

GERMAN PRINCIPIA, Part II. A READING BOOK. Containing Fables, Stories, and Anecdotes, Natural History, and Scenes from the History of Germany. With Grammatical Questions, Notes and Dictionary. Cr. 8vo. 3s. 6d.

Italian Course.

ITALIAN PRINCIPIA, Part I. A FIRST ITALIAN COURSE. Containing a Grammar, Delectus, Exercise Book, with Vocabularies, &c. Thoroughly revised and in part re-written by C. F. COSCIA, Professor of Italian in the University of Oxford. Crown 8vo. 3s. 6d.

ITALIAN PRINCIPIA, Part II. A FIRST ITALIAN READING-BOOK, containing Fables, Anecdotes, History, and Passages from the best Italian Authors, with Questions, Notes, and an Etymological Dictionary. Crown 8vo. 3s. 6d.

Spanish Course.

SPANISH PRINCIPIA. By H. J. WEINTZ. Crown 8vo.
[In Preparation.]

Latin Course.

THE YOUNG BEGINNER'S COURSE.

I. FIRST LATIN BOOK.—Grammar, Easy Questions, Exercises and Vocabularies. F'cap 8vo. 2s.

II. SECOND LATIN BOOK.—An easy Latin Reading Book with Analysis of Sentences. F'cap 8vo. 2s.

III. THIRD LATIN BOOK.—Exercises on the Syntax, with Vocabularies. F'cap 8vo. 2s.

IV. FOURTH LATIN BOOK.—A Latin Vocabulary for Beginners, arranged according to Subjects and Etymologies. F'cap 8vo. 2s.

PRINCIPIA LATINA, Part I. FIRST LATIN COURSE, Grammar, Delectus, Exercises, and Vocabularies. 38th Edition, Thoroughly revised so as to meet the requirements of Modern Teachers and Scholars. Crown 8vo. 3s. 6d.

APPENDIX TO PRINCIPIA LATINA, Part I. Containing Additional Exercises, with Examination Papers. Crown 8vo. 2s. 6d.

SIR WM. SMITH'S EDUCATIONAL SERIES
—continued.

Latin Course—continued.

- PRINCIPIA LATINA, Part II.** READING BOOK. An Introduction to Ancient Mythology, Geography, Roman Antiquities, and History. With Notes and a Dictionary. Crown 8vo. 3s. 6d.
- PRINCIPIA LATINA, Part III.** POETRY. 1. Easy Hexameters, and Pentameters. 2. Eclogæ Ovidianæ. 3. Prosody and Metre. 4. First Latin Verse Book. Crown 8vo. 3s. 6d.
- PRINCIPIA LATINA, Part IV.** PROSE COMPOSITION. Rules of Syntax, with Examples, Explanations of Synonyms, and Exercises on the Syntax. Crown 8vo. 3s. 6d.
- PRINCIPIA LATINA, Part V.** SHORT TALES AND ANECDOTES FROM ANCIENT HISTORY FOR TRANSLATION INTO LATIN PROSE. With an English-Latin Vocabulary. By SIR WM. SMITH, LL.D. Revised and considerably enlarged. By T. D. HALL, M.A. 3s. 6d.
- THE STUDENT'S LATIN GRAMMAR.** FOR THE USE OF COLLEGES AND THE HIGHER FORMS IN SCHOOLS. By SIR WM. SMITH, LL.D., and T. D. HALL. Crown 8vo. 6s.
- SMALLER LATIN GRAMMAR.** FOR THE MIDDLE AND LOWER FORMS. Crown 8vo. 3s. 6d.

Greek Course.

- INITIA GRÆCA, Part I.** A FIRST GREEK COURSE, containing Grammar, Delectus, Exercise Book, and Vocabularies. 26th Edition. Edited and carefully revised by FRANCIS BROOKS, M.A., Professor of Classics at University College, Bristol, and formerly Classical Scholar of Balliol College, Oxford. Crown 8vo. 3s. 6d.
- APPENDIX TO INITIA GRÆCA, Part I.** Containing Additional Exercises, with Examination Papers and Easy Reading Lessons with the Sentences Analysed, serving as an Introduction to INITIA GRÆCA, Part II. Crown 8vo. 2s. 6d.
- INITIA GRÆCA, Part II.** A READING BOOK. Containing short Tales, Anecdotes, Fables, Mythology, and Grecian History. With a Lexicon. Crown 8vo. 3s. 6d.
- INITIA GRÆCA, Part III.** PROSE COMPOSITION. Containing the Rules of Syntax, with copious Examples and Exercises. Crown 8vo. 3s. 6d.
- THE STUDENT'S GREEK GRAMMAR.** FOR THE HIGHER FORMS. By PROFESSOR CURTIUS. Edited by SIR WM. SMITH, D.C.L. Crown 8vo. 6s.
- A SMALLER GREEK GRAMMAR.** FOR THE MIDDLE AND LOWER FORMS. Abridged from the above Work. Crown 8vo. 3s. 6d.

ETON COLLEGE BOOKS.

ETON LATIN GRAMMAR. For use in the Higher Forms. By FRANCIS HAY RAWLINS, M.A., Fellow of King's Coll., Cambridge, and Assistant Master at Eton College, and Rev. W. R. INGE, M.A., Fellow of Hertford Coll., Oxford. Revised Edition. Crown 8vo. 6s.

"The Syntax has the merit of compressing a great deal of matter into a short space, and of avoiding much of the technical terminology which afflicts some of the readers of the Public School Grammar. It is also lucid in arrangement, and clear in its presentation of facts."—Prof. NETTLESHIP in the *Classical Review*.

ETON ELEMENTARY LATIN GRAMMAR. For use in the Lower Forms. Compiled with the sanction of the Head Master, by A. C. AINGER, M.A., Trinity College, Cambridge, and H. G. WINTLE, M.A., Christ Church, Oxford, Assistant Masters at Eton College. Crown 8vo. 3s. 6d.

PREPARATORY ETON LATIN GRAMMAR. Containing the Accidence and the Syntax Rules with the sanction of the Head Master. By A. C. AINGER, M.A., Trinity College, Cambridge, and H. G. WINTLE, M.A., Christ Church, Oxford, Assistant Masters at Eton College. Crown 8vo. 2s.

ETON LATIN SYNTAX AND EXERCISE BOOK. Consisting of pages 97-127 and 152-306 from the Eton Elementary Latin Grammar, together with the First Latin Exercise Book. Compiled, with sanction of the Head Master, by A. C. AINGER, M.A., Trinity College, Cambridge, and H. G. WINTLE, M.A., Christ Church, Oxford, Assistant Masters at Eton College. Crown 8vo. 5s.

A FIRST LATIN EXERCISE BOOK. Adapted to the Eton Latin Grammar. By A. C. AINGER, M.A., and H. G. WINTLE M.A. Crown 8vo. 2s. 6d.

OVID LESSONS: being Easy Passages selected from the Elegiac Poems of OVID, with Explanatory Notes by A. C. AINGER, M.A., and H. F. W. TATHAM, M.A., of Trinity College, Cambridge, Assistant Masters at Eton College. Crown 8vo. 2s. 6d.

ETON HORACE. The Odes, Epodes, and Carmen Sæculare. With Notes. By F. W. CORNISH, M.A. In Two Parts. With Maps. Crown 8vo. 6s.

As it is considered desirable that the notes should be used only in the preparation of the lesson, and not in the class, they are bound up separate from the text.

"One good feature is that the notes are printed entirely separate from the text in a separate volume. They are just those that are suited to boys at that stage."
—*Schoolmaster*.

ETON EXERCISES IN ALGEBRA. By E. P. ROUSE and A. COCKSHOT, Assistant Masters at Eton College. Crown 8vo. 3s.

ETON EXERCISES IN ARITHMETIC. By Rev. T. DALTON, M.A., Assistant Master at Eton College. Crown 8vo. 3s.

UNIVERSITY MANUALS.

Edited by PROFESSOR KNIGHT, of St. Andrew's University.

A HISTORY OF ASTRONOMY. By ARTHUR BERRY, M.A.,
Fellow of King's College, Cambridge With over 100 Illustrations.
Crown 8vo. 6s.

Primitive Astronomy—Greek Astronomy—The Middle Ages—
Copernicus—The Reception of the Copernican Theory and the
Progress of Observation—Galileo—Kepler—From Galilei to Newton
—Universal Gravitation—Observational Astronomy in the 18th
Century—Gravitational Astronomy in the 18th Century—Herschel—
The 19th Century—List of Authorities and of Books for Students—
Index.

THE STUDY OF ANIMAL LIFE. By J. ARTHUR
THOMSON, Regius Professor of Natural Science in the University
of Aberdeen; Joint Author of the "Evolution of Sex"; Author of
"Outlines of Zoology." With many Illustrations. Crown 8vo. 5s.

Part I.—The Everyday Life of Animals. *Part II.*—The Powers
of Life. *Part III.*—The Forms of Animal Life. *Part IV.*—The
Evolution of Animal Life.

THE ELEMENTS OF ETHICS. By JOHN R. MUIRHEAD,
Balliol College, Oxford, Lecturer on Moral Science, Royal
Holloway College, Examiner in Philosophy to the University of
Glasgow. Crown 8vo. 3s.

Book I.—The Science of Ethics. *Book II.*—Moral Judgement.
Book III.—Theories of the End. *Book IV.*—The End as Good.
Book V.—Moral Progress.

THE REALM OF NATURE: A MANUAL OF PHYSIOGRAPHY.
By DR. HUGH ROBERT MILL, Director of British Rainfall
Organization. With 19 Coloured Maps and 68 Illustrations. Crown
8vo. 5s.

The Study of Nature—The Substance of Nature: Energy, the
Power of Nature—The Earth a Spinning Ball—The Earth a Planet
—The Solar System Universe—The Atmosphere—Atmospheric
Phenomena—Climates of the World—The Hydrosphere—The Bed
of the Oceans—The Crust of the Earth—Action of Water on the
Land—The Record of the Rocks—The Continental Area—Life and
Living Creatures—Man in Nature.

UNIVERSITY MANUALS—*continued.*

ENGLISH COLONIZATION AND EMPIRE. By A. CALDECOTT, Fellow and Dean of St. John's College, Cambridge; and Professor of Philosophy, King's College, London. Coloured Maps and Plans. Crown 8vo. 3s. 6d.

Introduction—Pioneer Period—International Struggle—Development and Separation of America—The English in India—Reconstruction and Fresh Development—Government of the Empire—Trade and Trade Policy—Supply of Labour—Native Races—Education and Religion—General Reflections—Appendix: Books of Reference.

FRENCH LITERATURE. By H. G. KEENE, Wadham College, Oxford, Fellow of the University of Calcutta. Crown 8vo. 3s.

The Age of Infancy (*a.* Birth)—The Age of Infancy (*b.* Growth)—The Age of Adolescence (XVIth Cent.)—The Age of Glory (Poetry)—The Age of Glory (Prose)—The Age of Reason—The Age of 'Nature'—Source of Modern French Literary Art: Poetry—Sources of Prose Fiction.

THE PHILOSOPHY OF THE BEAUTIFUL, Part I. By PROFESSOR KNIGHT, University of St. Andrew's. Crown 8vo. 3s. 6d.

Introductory—Prehistoric Origins—Oriental Art and Speculation—The Philosophy of Greece—The Neoplatonists—The Graeco-Roman Period—Mediaevalism—The Philosophy of Germany—The Philosophy of France—The Philosophy of Italy—The Philosophy of Holland—The Philosophy of Britain—The Philosophy of America.

THE PHILOSOPHY OF THE BEAUTIFUL, Part II. By PROFESSOR KNIGHT, University of St. Andrew's. Crown 8vo. 3s. 6d.

Prolegomena—The Nature of Beauty—The Ideal and the Real—Inadequate or Partial Theories—Suggestions towards a more complete Theory of Beauty—Art, its Nature and Functions—The Correlation of the Arts—Poetry—Music—Architecture—Sculpture—Painting—Dancing—Appendix.

UNIVERSITY MANUALS—*continued.*

THE USE AND ABUSE OF MONEY. By W. CUNNINGHAM, D.D., Fellow of Trinity College, Cambridge, Professor of Economic Science, King's College, London. Crown 8vo. 3s.

Part I.—Social Problems. *Part II.*—Practical Questions. *Part III.*—Personal Duty.

THE JACOBAN POETS. By EDMUND GOSSE. Crown 8vo. 3s. 6d.

Preface; The Last Elizabethans; Ben Jonson—Chapman; John Dorne; Beaumont and Fletcher; Campion—Drayton—Sir John Beaumont; Heywood—Middleton—Powley; Giles and Phineas Fletcher—Browne; Tournear—Webster—Day—Darorne; Wither—Quarles—Lord Brooke; Philip Massingen; Index.

THE RISE OF THE BRITISH DOMINION IN INDIA, FROM THE EARLY DAYS OF THE EAST INDIA COMPANY TO THE CONQUEST OF THE PANJAB. By SIR ALFRED LYALL, K.C.B. With Coloured Maps. Crown 8vo. 4s. 6d.

"No student should be without this excellent instructor into the technicalities of the many phases through which our Empire has passed."—*Daily Telegraph.*

THE ENGLISH NOVEL, FROM ITS ORIGIN TO SIR W. SCOTT. By WALTER RALEIGH, Professor of English Literature in Glasgow University. Crown 8vo. 3s. 6d.

The Romance and the Novel—The Elizabethan Age: Euphuës: Sydney and Nash—The Romances of the 17th Century—The Beginnings of the Modern Novel—Richardson and Fielding—The Novels of the 18th Century—The Revival of Romance—The Novel of Domestic Satire: Miss Burney; Miss Austen; Miss Edgeworth—Sir Walter Scott.

THE FRENCH REVOLUTION. By C. E. MALLET, Balliol College, Oxford. Crown 8vo. 3s. 6d.

The Condition of France in the Eighteenth Century—The Last Years of the Ancien Régime—The Early Days of the Revolution—The Labours of the Constituent Assembly—Parties and Politicians under the Constituent Assembly—The Rise of the Jacobin Party—The Influence of the War upon the Revolution—The Fall of the Gironde—The Jacobins in Power—The Struggles of Parties and the Ascendancy of Robespierre—The Reaction.

UNIVERSITY MANUALS—*continued.*

AN INTRODUCTION TO MODERN GEOLOGY. By R. D. ROBERTS, sometime Fellow of Clare College, Cambridge; Fellow of University College, London; Secretary to the Cambridge and London University Extension Syndicate. With Coloured Maps and Illustrations. Crown 8vo. 5s.

Part I.—PROGRESS OF GEOLOGICAL THOUGHT.

Part II.—DESTRUCTION OF LAND.

Part III.—CONSTRUCTION OF LAND.

Part IV.—EVOLUTION OF LAND AREAS.

OUTLINES OF ENGLISH LITERATURE. By WILLIAM RENTON. With Illustrative Diagrams. Crown 8vo. 3s. 6d.

First Period.—The Old English Metric Chronicle, 600-1350—The Renaissance, 1350-1500—The Reformation, 1500-1600—The Romantic Drama, 1550-1650.

Second Period.—The Serious Age, 1600-1700—The Age of Gaiety, 1650-1750—The Sententious Age, 1700-1800—The Sympathetic Age, 1800-1900—The Literature of America.

THE PHYSIOLOGY OF THE SENSES. By JOHN McKENDRICK, Professor of Physiology in the University of Glasgow, and Dr. SNODGRASS, Physiological Laboratory, Glasgow. With Illustrations. Crown 8vo. 4s. 6d.

1. Touch, Taste, and Smell—2. The Sense of Sight—3. Sound and Hearing.

CHAPTERS IN MODERN BOTANY. By PATRICK GEDDES, Professor of Botany, University College, Dundee. With Illustrations. Crown 8vo. 3s. 6d.

Pitcher Plants—Other Insectivorous Plants. Difficulties and Criticisms—Movement and Nervous Action in Plants—The Web of Life—Relations between Plants and Animals—Spring and its Studies; Geographical Distribution and World-Landscapes; Seedling and Bud—Leaves—Suggestions for Further Study.

GREECE IN THE AGE OF PERICLES. By A. J. GRANT, King's College, Cambridge, and Staff Lecturer in History to the University of Cambridge. With Illustrations. Crown 8vo. 3s. 6d.

The Essentials of Greek Civilization—The Religion of the Greeks—Sparta, Argos, Corinth, Thebes—The Earlier History of Athens—The Rivalry of Athens and Sparta—Civil Wars in Greece—The Athenian Democracy—Pericles: his Policy and his Friends—Society in Greece—From the Outbreak of the Peloponnesians to the Death of Pericles—The Peloponnesian War.

UNIVERSITY MANUALS—*continued.*

LOGIC, INDUCTIVE AND DEDUCTIVE. By WILLIAM MINTO, late Professor of Logic and Literature, University of Aberdeen. With Diagrams. Crown 8vo. 4s. 6d.

Introduction—The Logic Consisting; Syllogism and Definition—The Element of Propositions—Definition—The Interpretation of Propositions—The Interdependence of Propositions—Inductive Logic or the Logic of Science.

HISTORY OF RELIGION. A SKETCH OF PRIMITIVE BELIEFS AND PRACTICES, AND OF THE ORIGIN AND CHARACTER OF THE GREAT SYSTEMS. By ALLAN MENZIES, D.D., Professor of Biblical Criticism in the University of St. Andrew's. Crown 8vo. 5s.

The Religion of the Early World—Isolated National Religions—The Semitic Group—The Aryan Group—Universal Religion.

LATIN LITERATURE. By J. W. MACKAIL, Balliol College, Oxford. Crown 8vo. 3s. 6d.

The Republic — The Augustan Age — The Empire — Index of Authors.

ELEMENTS OF PHILOSOPHY. By GEORGE CROOM ROBERTSON, late Grote Professor, University College, London. Edited from Notes of Lectures delivered at the College, 1870—1892, by (Mrs.) C. A. FOLEY RHYS DAVIDS, M.A. Crown 8vo. 3s. 6d.

ELEMENTS OF PSYCHOLOGY. By GEORGE CROOM ROBERTSON, late Grote Professor, University College, London. Edited from Notes of Lectures delivered at the College, 1870—1892, by (Mrs.) C. A. FOLEY RHYS DAVIDS, M.A. Crown 8vo. 3s. 6d.

SHAKSPERE AND HIS PREDECESSORS IN THE ENGLISH DRAMA. By F. S. BOAS, Professor of English Literature, Queen's College, Belfast. Crown 8vo. 6s. Library Edition, on larger paper. 7s. 6d.

"It is impossible to part with this work without a word of cordial congratulation to the author on the vigour of his style, the originality of some of his views and theories, and the painstaking appreciation he has brought to bear on his subject —*Morning Post.*

*** The Volumes in this Series may be obtained in the ordinary Red binding or in Library binding with uncut edges.*

WORKS FOR ADVANCED STUDENTS

Art.

THE FINE ARTS. THE ORIGIN, AIMS AND CONDITION OF ARTISTIC WORK AS APPLIED TO PAINTING, SCULPTURE AND ARCHITECTURE. By G. BALDWIN BROWN, M.A., Professor of Fine Art in the University of Edinburgh; Formerly Fellow of Brasenose College, Oxford. New Edition. With many new Illustrations. Crown 8vo. 6s. *net*.

"It is a work that ought to be in the library of all thoughtful students of Art."
—*Literary World*.

Banking.

THE COUNTRY BANKER. HIS CLIENTS, CARES, AND WORK. From an Experience of Forty Years. By GEORGE RAE, Author of "Bullion's Letters to a Bank Manager." With Portrait of the Author. A Cheap Edition. Crown 8vo. 2s. 6d. *net*.

Education.

NATIONAL EDUCATION. ESSAYS TOWARDS A CONSTRUCTIVE POLICY. By the Rev. BERNARD REYNOLDS, M.A.; FRANCIS STORR, B.A.; Sir JOSHUA G. FITCH, LL.D.; Prof. H. E. ARMSTRONG, LL.D., Ph.D., F.R.S.; A. D. PROVAND, formerly M.P. for Glasgow; T. A. ORGAN, B.A., L.C.C.; Prof. W. A. S. HEWINS, Director of the London School of Economics and Political Science; JOHN C. MEDD, M.A.; H. W. EVE, formerly Headmaster of University College School. Edited, with an Introductory Chapter and a Bibliography, by LAURIE MAGNUS, M.A., Magdalen College, Oxford. 8vo. 7s. 6d. *net*.

"Professor ARMSTRONG writes vigorously on the need for 'drastic reform' in the schools in which our governing classes are educated, as the most important feature in the reorganization of a national educational programme."—*Times*.

EDUCATION AND EMPIRE. ADDRESS ON TOPICS OF THE DAY. By the Right Hon. R. B. HALDANE, K.C., M.P., LL.D. Crown 8vo. 5s. *net*.

THE SCHOOLMASTER. A COMMENTARY UPON THE AIMS AND METHODS OF AN ASSISTANT-MASTER IN A PUBLIC SCHOOL. By A. C. BENSON, Eton College. Crown 8vo. 5s. *net*.

WORKS FOR ADVANCED STUDENTS—*continued.*Geography.

A HISTORY OF ANCIENT GEOGRAPHY AMONG THE GREEKS AND ROMANS FROM THE EARLIEST AGES TILL THE FALL OF THE ROMAN EMPIRE. By SIR E. H. BUNBURY. With Twenty Illustrative Maps. 2 Vols. 8vo. 21s.

THE DAWN OF MODERN GEOGRAPHY. By C. RAYMOND BEAZLEY, M.A., F.R.G.S., late Fellow of Merton College, Oxford. A HISTORY OF EXPLORATION AND GEOGRAPHICAL SCIENCE.

VOL. I.—From the Conversion of the Roman Empire to A.D. 900, with an account of the achievements and writings of the early Christian, Arab and Chinese Travellers and Students. With Reproductions of the Principal Maps of the Time. 8vo. 18s.

"Mr. Beazley is only at the threshold of his great subject, and the manner in which he has dealt with the obscurest part of his theme causes us to look forward with pleasant anticipations to its continuation. It is gratifying to think that the best extant account of the dawn of Geography should emanate from an Englishman."—*Athenaeum*.

VOL. II.—From the Opening of the Tenth to the Middle of the Thirteenth Century (A.D. 900—1260). With Maps and Illustrations. Demy 8vo. 18s.

"... Marked by the same admirable qualities which characterised the first volume—scholarship, immense research, and exhaustiveness... on the method he has adopted he has rendered an immense service to geography of the middle ages, which is accessible in no other single work."—*The Times*.

Greek.

A.—Texts, Commentaries, etc.

PRINCIPLES OF GREEK ETYMOLOGY. By Professor G. CURTIUS, of the University of Leipzig. Translated into English, with the Author's sanction, by A. S. WILKINS, Litt.D., LL.D., and E. B. ENGLAND, M.A., Owens College, Manchester. Fifth Edition, thoroughly revised. 2 vols. 8vo. 28s.

SOPHOCLES. The Seven Plays in English Verse. By LEWIS CAMPBELL, M.A., LL.D., Emeritus Professor of Greek in the University of St. Andrews. Demy 8vo. 10s. 6d.

THE GREEK VERB; ITS STRUCTURE AND DEVELOPMENT. By Professor CURTIUS. Translated by A. S. WILKINS, M.A., and E. B. ENGLAND, M.A. 8vo. 12s.

THE GREEK THINKERS. A HISTORY OF ANCIENT PHILOSOPHY. By Professor THEODOR GOMPERZ, of Vienna University. Hon. LL.D., Dublin, Ph.D. Königsberg, &c.

VOL. I.—Translated by LAURIE MAGNUS, M.A., Magdalen College, Oxford. Demy 8vo. 14s. net.

"We are glad to welcome the first instalment of the authorised translation of Professor Gomperz's great history of ancient philosophy. . . . The translation is excellently done and the translator has had the benefit of untiring help from the author. Such an excellent reproduction of so important a foreign work on one of the greatest of themes is an event in its way. . . . We shall look forward with great pleasure to the appearance of the next volume."—*Spectator*.

VOL. II.—SOCRATES, THE SOCRATICS AND PLATO. Translated by G. G. BERRY, M.A., Balliol College, Oxford. [In the Press.]

WORKS FOR ADVANCED STUDENTS—*continued.*Greek—continued.A.—*Texts, Commentaries, etc.*

PLATO AND THE OTHER COMPANIONS OF SOCRATES. By GEORGE GROTE, Author of "The History of Greece." 4 vols. Crown 8vo. 5s. each.

SELECT PASSAGES FROM THE INTRODUCTIONS TO PLATO. By BENJAMIN JOWETT, M.A. Edited by LEWIS CAMPBELL, M.A., LL.D. With a Portrait. F'cap 8vo. 2s. 6d. *net.*

THE ILIAD OF HOMER, rendered into English Blank Verse. By the EARL OF DERBY. Portrait. 2 vols. Crown 8vo. 10s.

THE ODYSSEY OF HOMER. Books I.—VIII. Translated into English Verse by J. W. MACKAIL, Formerly Fellow of Balliol College; Oxford. Crown 8vo.

CONCISE DICTIONARY OF THE ENGLISH AND THE MODERN GREEK LANGUAGES, AS ACTUALLY WRITTEN AND SPOKEN. Being a Copious Vocabulary of all Words and Expressions Current in Ordinary Reading and in Everyday Talk, for the Guidance of Students and Travellers through Greece and the East. Compiled by Prof. A. N. JANNARIS, Ph.D., St. Andrew's University. Crown 8vo. 10s. 6d.

B.—*History.*

A HISTORY OF GREECE, from the Earliest Period to the close of Alexander the Great. By GEORGE GROTE. With Portrait, Maps, and Plans. 10 vols. 5s. each.

THE GREAT PERSIAN WAR and its Preliminaries. A STUDY OF THE EVIDENCE, LITERARY AND TOPOGRAPHICAL. By G. B. GRUNDY, M.A., Lecturer at Brasenose College, and University Lecturer in Classical Geography. With Maps and Illustrations. Demy 8vo. 21s. *net.*

'It is but seldom that we have the privilege of reviewing so excellent a work in Greek history. This book on the great war which freed Greece from the attacks of Persia will long remain the standard work on the subject.'—

The Athenæum.

THE TOPOGRAPHY OF THE BATTLE OF PLATÆA
THE CITY OF PLATÆA, THE FIELD OF LEUCTRA. By G. B. GRUNDY, M.A. With Maps and Plans. Demy 8vo. 7s. 6d.; sewed, 5s.

PHILIP AND ALEXANDER OF MACEDON. Two ESSAYS IN BIOGRAPHY. With Maps and Illustrations. By D. G. HOGARTH, M.A., Fellow of Magdalen College, Oxford. 14s.

WORKS FOR ADVANCED STUDENTS—*continued.*History.*Church and Scripture.*

THE HISTORY OF THE CHRISTIAN CHURCH FROM THE APOSTOLIC AGE TO THE REFORMATION, A.D. 64—1517. By JAMES C. ROBERTSON, M.A., Canon of Canterbury, Professor of Ecclesiastical History in King's College, London. 8 vols. Crown 8vo. 6s. each.

THE HISTORY OF CHRISTIANITY FROM THE BIRTH OF CHRIST TO THE ABOLITION OF PAGANISM IN THE ROMAN EMPIRE. By HENRY HART MILMAN. 3 vols. Post 8vo. 4s. each.

THE HISTORY OF LATIN CHRISTIANITY INCLUDING THAT OF THE POPES TO THE PONTIFICATE OF NICHOLAS V. By HENRY HART MILMAN. 9 vols. Post 8vo. 4s. each.

THE HISTORY OF THE JEWS FROM THE EARLIEST PERIOD DOWN TO MODERN TIMES. By HENRY HART MILMAN, D.D., late Dean of St. Paul's. 3 vols. Post 8vo. 4s. each.

LECTURES ON THE HISTORY OF THE JEWISH CHURCH FROM THE EARLIEST TIMES TO THE CHRISTIAN ERA. By the Late DEAN STANLEY. With Portrait and Maps. 3 vols. Crown 8vo. 6s. each.

THE EVOLUTION OF THE ENGLISH BIBLE. BEING AN HISTORICAL SKETCH OF THE SUCCESSIVE VERSIONS FROM 1382—1885. By H. W. HOARE, late of Balliol College, Oxford, now an Assistant Secretary to the Board of Education, Whitehall. With Portraits and Specimen-pages from Old Bibles. Second and Cheaper Edition, Revised. Crown 8vo. 7s. 6d. net.

THE REFORMATION. A RELIGIOUS AND HISTORICAL SKETCH. By the REV. J. A. BABINGTON, M.A., Assistant Master at Tonbridge School, formerly Scholar of New College, Oxford. Demy 8vo. 12s. net.

"This masterly essay . . . gives evidence on every page of wide reading and of a remarkable power of condensation. . . . It is a notable piece of work, one that deserves to be widely read."—*Daily Chronicle*.

AN INTRODUCTION TO THE STUDY OF THE NEW TESTAMENT, and an Investigation into Modern Biblical Criticism, based on the most Recent Sources of Information. By the Rev. GEO. SALMON, D.D., D.C.L., etc., Provost of Trinity College, Dublin. Crown 8vo. 9s.

WORKS FOR ADVANCED STUDENTS—*continued.*History—continued.*Egypt.*

AN ACCOUNT OF THE MANNERS AND CUSTOMS OF THE MODERN EGYPTIANS. Written in Egypt during the Years, 1833-34 and 35. Partly from Notes made during a former visit to that country in the Years 1825-26-27 and 28. By EDWARD WILLIAM LANE. Fifth Edition, with numerous additions and improvements from a copy annotated by the Author. Edited by his Nephew EDWARD STANLEY POOLE. 2 Vols. Crown 8vo. 12s.

EGYPT UNDER THE PHARAOHS. By HEINRICH BRUGSCH-BEY. Condensed and Revised by M. BRODRICK. With Maps, Plans and Illustrations. Demy 8vo. 18s.

OUTLINES OF ANCIENT EGYPTIAN HISTORY. By AUGUSTE MARIETTE. Translated and Edited with Notes by MARY BRODRICK. Second Edition. With Maps. Crown 8vo. 5s.

✱

POPULAR ACCOUNT OF THE ANCIENT EGYPTIANS. By SIR J. GARDNER WILKINSON, F.R.S. Revised and abridged from his larger work. Illustrated with five hundred Woodcuts. 2 Vols. Post 8vo. 12s.

England.

THE CONSTITUTIONAL HISTORY OF ENGLAND FROM THE ACCESSION OF HENRY VII. TO THE DEATH OF GEORGE II. By HENRY HALLAM, LL.D. Cabinet Edition. 3 vols. Post 8vo. 12s.

HISTORY OF ENGLAND, COMPRISING THE REIGN OF QUEEN ANNE TO THE PEACE OF VERSAILLES, 1701-1783. By LORD MAHON (Earl Stanhope). Fifth Edition, Revised. Post 8vo. 9 vols. 5s. each.

Europe.

HISTORY OF EUROPE DURING THE MIDDLE AGES. By HENRY HALLAM, LL.D. Cabinet Edition. 3 vols. Post 8vo. 12s.

LITERARY HISTORY OF EUROPE DURING THE 15th, 16th and 17th CENTURIES. By HENRY HALLAM, LL.D. Cabinet Edition. 4 vols. Post 8vo. 16s.

WORKS FOR ADVANCED STUDENTS—*continued.*History—continued.*France.*

THE STATE OF SOCIETY IN FRANCE BEFORE THE REVOLUTION OF 1789 AND THE CAUSES WHICH LED TO THAT EVENT. By ALEXIS DE TOCQUEVILLE, Member of the French Academy. Translated by HENRY REEVE, D.C.L. Third Edition. Demy 8vo. 12s.

India and the East.

THE HISTORY OF INDIA. THE HINDU AND MAHOMETAN PERIODS. By the Hon. MOUNTSTUART ELPHINSTONE. Seventh Edition. With Notes and Additions by E. B. COWELL, M.A., late Principal of Sanskrit College, Calcutta. With Map Demy 8vo. 18s.

THE RISE OF THE BRITISH POWER IN THE EAST. By the late Hon. MOUNTSTUART ELPHINSTONE. Being a Continuation of his "History of India." Edited by SIR EDWARD COLEBROOK, Bart. With Maps. Medium 8vo. 16s. #

THE RISE AND EXPANSION OF THE BRITISH DOMINION IN INDIA. By SIR ALFRED LYALL, K.C.B., D.C.L. Third and Enlarged Edition. With Maps. 8vo. 12s. net.

CHINA: HER HISTORY, DIPLOMACY AND COMMERCE, FROM THE EARLIEST TIMES TO THE PRESENT DAY. By E. H. PARKER, Professor of Chinese at the Owens College; Acting-Consul-General in Corea, Nov., 1886—Jan., 1887; Consul in Hainan, 1891-2, 1893-4; and in 1892-3, Adviser in Chinese Affairs to the Burma Government. With 19 Maps, &c. Large Crown 8vo. 8s. net.

Netherlands.

HISTORY OF THE UNITED NETHERLANDS. FROM THE DEATH OF WILLIAM THE GREAT TO THE TWELVE YEARS TRUCE, 1609. By JOHN LOTHORP MOTLEY, D.C.L., LL.D. With Portraits. 4 Vols. Post 8vo. 6s. each.

Vol. I.—1584-86. *Vol. II.*—1586-89. *Vol. III.*—1590-1600. *Vol. IV.*—1600-1609.

LIFE AND DEATH OF JOHN OF BARNEVELD (Advocate of Holland). WITH A VIEW OF THE PRIMARY CAUSES AND MOVEMENTS OF THE THIRTY YEARS' WAR. By JOHN LOTHORP MOTLEY, D.C.L., LL.D. With Illustrations. 2 Vols. Post 8vo. 6s. each.

WORKS FOR ADVANCED STUDENTS—*continued.*History—continued.*Rome.*

THE HISTORY OF THE DECLINE AND FALL OF THE ROMAN EMPIRE. By EDWARD GIBBON. With Notes by Dean MILMAN, M. GUIZOT, and Sir WILLIAM SMITH. With Portrait and Maps. Demy 8vo. 8 vols. 60s.

Complete sets of the above work may be purchased through any Bookseller at reduced rates.

Latin.

THE ANNALS OF TACITUS. FOR ENGLISH READERS. Books I.—VI. An English Translation with Introduction and Notes. By GEORGE G. RAMSAY Litt.D., LL.D., Professor of Humanity in the University of Glasgow; Editor of Selections from Tibullus and Propertius, Latin Prose Composition, etc. With Maps. Demy 8vo.

The aim of the translator is to produce a version, which while being exact in scholarship and faithful to the original, shall be such as may be read with pleasure and profit by those who are unacquainted with Latin. The notes will be mainly historical, and designed to put the English reader in possession of all information essential to the understanding of the text, and to enable him to compare the narrative and the judgments of Tacitus with those of other authorities for the period.

VIRGIL. In English Verse. Eclogues and Æneid, Books I—VI. By the Rt. Hon Sir CHARLES BOWEN. 8vo. 12s.

Law and Politics.

LECTURES ON JURISPRUDENCE OR THE PHILOSOPHY OF POSITIVE LAW. By the late JOHN AUSTIN. Fifth Edition, Revised and Edited by ROBERT CAMPBELL, Advocate (Scotch Bar), and of Lincoln's Inn, Barrister-at-Law. 2 vols. 8vo. 32s.

FIRST PRINCIPLES IN POLITICS. By WILLIAM SAMUEL LILLY. Demy 8vo. 14s.

LAW AND POLITICS IN THE MIDDLE AGES. By EDWARD JENKS, Reader in English Law in the University of Oxford. Demy 8vo. 12s.

"By far the most important and original book relating to jurisprudence published for some years in England is Mr. Jenks's 'Law and Politics in the Middle Ages.'"—*Times*.

WORKS FOR ADVANCED STUDENTS—*continued.*Law and Politics—continued.*Works by Sir Henry S. Maine, K.C.S.I.*

ANCIENT LAW; its Connection with the Early History of Society, and its Relation to Modern Ideas. Sixteenth Edition. 8vo. 9s.

LECTURES ON THE EARLY HISTORY OF INSTITUTIONS, in continuation of the above work. 8vo. 9s.

VILLAGE - COMMUNITIES IN THE EAST AND WEST, with other Lectures, Addresses, and Essays. Seventh Edition. 8vo. 9s.

DISSERTATIONS ON EARLY LAW AND CUSTOM. 8vo. 9s.

POPULAR GOVERNMENT. Four Essays. I. Prospects of Popular Government.—II. Nature of Democracy.—III. Age of Progress.—IV. Constitution of the United States. Fifth Edition. 8vo. 7s. 6d.

INTERNATIONAL LAW. The Whewell Lectures delivered at Cambridge in 1887. 8vo. 7s. 6d.

Medical.

HANDBOOK OF PHYSIOLOGY. By W. D. HALLIBURTON, M.D., F.R.S., Professor of Physiology, King's College, London. Fourth Edition, being the Seventeenth of Kirkes' (see Note below). Again thoroughly revised, with the addition of new matter and new illustrations, and certain alteration of the arrangement in deference to the wishes and advice of numerous teachers. With upwards of Six Hundred Illustrations, including some Coloured Plates. Large Cr. 8vo. 14s.

EXTRACT FROM PUBLISHER'S NOTE TO THIS EDITION.

Three completely revised editions of KIRKES' HANDBOOK have now been published since the editorship was first undertaken by Professor W. D. Halliburton in 1896. So extensive have been the changes made in these years, that but little remains of the original work, and the manual has now obtained a higher reputation and a wider popularity than at any time before.

In these circumstances it has been suggested by several professional men and other readers of the book that it would be well to drop the time-honoured name of "Kirkes'," and to substitute for it that of the real author of the present volume—Professor Halliburton. Whatever prestige attached to the old title has now been rightly transferred to the new, and we have accordingly decided to adopt this suggestion, and to call the book in future "HALLIBURTON'S PHYSIOLOGY."

WORKS FOR ADVANCED STUDENTS—*continued*Medical—continued.**MANUAL OF PATHOLOGY.** A HANDBOOK FOR STUDENTS.

By SIDNEY MARTIN, B.Sc., M.D., M.R.C.S., Professor of Pathology, University College. With numerous Woodcuts from Micro-Photographs. Medium 8vo.

A TREATISE ON MEDICAL JURISPRUDENCE.

Based on Lectures delivered at University College, London. By G. VIVIAN POORE, M.D. With Illustrations. 8vo. 12s. net.

"... Admirable and interesting treatise . . . the reader can almost hear Dr. Poore's genial and witty voice as he turns these instructive pages. They are marked by a kind of 'golden common-sense,' which is the most valuable lesson that any medical or legal student can lay to heart . . . an ideal handbook of the subject for the young student."—*The Spectator*

Sociology.

THE BASIS OF SOCIAL RELATIONS. A STUDY IN ETHNIC PSYCHOLOGY. By the late DANIEL G. BRINTON, A.M., M.D., LL.D., D.Sc., Author of "A History of Primitive Religions," "Races and Peoples," &c. Edited by LIVINGSTON FARRAND. 8vo. 8s. net.

. The above is the work upon which Professor Brinton was engaged at the time of his death.

Tides.

THE TIDES AND KINDRED PHENOMENA IN THE SOLAR SYSTEM. The substance of Lectures delivered at the Lowell Institute, Boston, Massachusetts, in 1897. By GEORGE HOWARD DARWIN, Plumian Professor and Fellow of Trinity College, in the University of Cambridge. With Illustrations. Crown 8vo. 7s. 6d.

"Professor Darwin has succeeded in giving a very clear and lucid account of the matters of which he treats."—*Times*.

CHARLES DARWIN'S WORKS.

THE ORIGIN OF SPECIES BY MEANS OF NATURAL SELECTION. Library Edition. 2 vols. 12s.—Popular Edition. 6s.—Cheaper Edition. With a Photogravure Portrait of the Author. Large crown 8vo. 2s. 6d. net.—Also in Paper Covers. 1s. net.

Mr. Murray desires to inform the public that the edition which has just lost copyright is the imperfect edition which was subsequently thoroughly revised by Mr. Darwin. This imperfect edition has been reprinted by other publishers without the consent or authority of Mr. Darwin's representatives.

The only authorised and complete editions are those published by Mr. Murray, and these do not lose copyright for several years to come.

DESCENT OF MAN, AND SELECTION IN RELATION TO SEX. Woodcuts. Library Edition. 2 vols. 15s.—1 Vol. Popular Edition. 7s. 6d.—Cheaper Edition. With Illustrations. Large crown 8vo. 2s. 6d. net.

VARIATION OF ANIMALS AND PLANTS UNDER DOMESTICATION. Woodcuts. 2 vols. 15s.

EXPRESSION OF THE EMOTIONS IN MAN AND ANIMALS. With Illustrations. 12s.

VARIOUS CONTRIVANCES BY WHICH ORCHIDS ARE FERTILIZED BY INSECTS. Woodcuts. 7s. 6d.

MOVEMENTS AND HABITS OF CLIMBING PLANTS. Woodcuts. 6s.

INSECTIVOROUS PLANTS. Woodcuts. 9s.

CROSS AND SELF-FERTILIZATION IN THE VEGETABLE KINGDOM. 9s.

DIFFERENT FORMS OF FLOWERS ON PLANTS OF THE SAME SPECIES. 7s. 6d.

FORMATION OF VEGETABLE MOULD THROUGH THE ACTION OF WORMS. Illustrations. 6s.

JOURNAL OF A NATURALIST DURING A VOYAGE ROUND THE WORLD IN H.M.S. "BEAGLE." With 100 Illustrations. Medium 8vo. 21s.—Popular Edition. With Portrait. 3s. 6d.—Cheaper Edition. With 16 full-page Plates. Large crown 8vo. 2s. 6d. net.

MR. MURRAY'S MUSICAL SERIES.

Crown 8vo. 5s. net each.

SONGS AND SONG WRITERS. By HENRY T. FINCK,
Author of "Wagner and his Works," "Chopin and other Musical
Essays," etc., etc. With 8 Portraits.

THE ORCHESTRA AND ORCHESTRAL MUSIC.
By W. J. HENDERSON, Author of "What is Good Music,"
etc., etc. With 8 Portraits and other Illustrations.

THE OPERA, PAST AND PRESENT. AN HISTORICAL
SKETCH. By WILLIAM FOSTER APTHORP, Author of
"Musicians and Music Lovers," etc. With Portraits.

CHOIRS AND CHORAL MUSIC. By ARTHUR MEES.
With Portraits.

MUSIC: HOW IT CAME TO BE WHAT IT IS. By HANNAH
SMITH. With Illustrations.

HOW MUSIC DEVELOPED. By W. J. HENDERSON,
Author of "What is Good Music."

HOW TO LISTEN TO MUSIC. HINTS AND SUGGESTIONS
TO UNTAUGHT LOVERS OF THE ART. By HENRY EDWARD
KREHBIEL, Author of "Studies in the Wagnerian Drama,"
etc., etc. With 11 Portraits.

WHAT IS GOOD MUSIC? SUGGESTIONS TO PERSONS
DESIRING TO CULTIVATE A TASTE IN MUSICAL ART. By W. J.
HENDERSON.

A BOOK OF BRITISH SONG.

FOR HOME AND SCHOOL

Edited by CECIL J. SHARP, Principal of the Hampstead Conserva-
toire. With Pianoforte Score and Words. Large 4to. 7s. 6d. net.
Also a Small Crown 8vo. Edition with Words and Airs only. Cloth, 2s.;
paper, 1s. 6d.

LIST OF KEYS.

*These Keys are not sold to the Public, and care is taken that they do not get into the hands of boys at school. They can only be obtained by **authenticated Teachers** on written application to the **Publisher**, and their prices are **strictly net, post free.***

ETON COLLEGE SERIES.

	<i>s. d.</i>		<i>s. d.</i>
First Latin Exercise Book	2 1	Eton Exercises in Arith-	
Eton Exercises in Algebra		metic (Answers only) ...	2 1
(Answers only) ...	2 1		

HALL, Professor T. D.

Translation at Sight	1 1
--------------------------	-----	-----	-----	-----	-----

HOME AND SCHOOL LIBRARY.

Algebra, Part I. (Answers only)	1 1
-------------------------------------	-----	-----	-----	-----	-----

SECONDARY EDUCATION TEXT-BOOKS.

Commercial German, Part I.	
--------------------------------	-----	-----	-----	-----	--

SIR WM. SMITH'S EDUCATIONAL SERIES.

ENGLISH.

School Manual of English Grammar	Primary English Grammar	0 7
--------------------------------------	-----	-----	-------------------------	-----

FRENCH.

French Principia, Part I. ...	1 1	French Principia, Part II.	1 7
Appendix to French Principia, Part I.	1 1	French Principia, Part III.	1 7

GERMAN.

German Principia, Part I.	1 1	German Principia, Part II.	2 7
---------------------------	-----	----------------------------	-----

ITALIAN.

Italian Principia, Part I. ...	1 1	Italian Principia, Part II.	2 7
--------------------------------	-----	-----------------------------	-----

SPANISH.

Spanish Principia	
-----------------------	-----	-----	-----	-----	--

LATIN.

Principia Latina, Part I. ...	0 7	Principia Latina, Part IV.	0 7
Appendix to Principia Latina, Part I.	0 7	Principia Latina, Part V.	1 1
Principia Latina, Part II.	2 7	Young Beginner's Latin Course, Part III.	...
Principia Latina, Part III.	1 7		0 7

GREEK.

Initia Græca, Part I. For use with the 26th or any later Editions. Keys to all previous Editions are quite out of print ...	1 1	Appendix to Initia Græca, Part I. ...	1 1
		Initia Græca, Part II. ...	1 1
		Initia Græca, Part III. ...	1 1

LONDON: JOHN MURRAY, ALBEMARLE STREET, W.

